PROJECT FEATURE

PROJECT TITLE	:	**BATARAZA PORT EXPANSION PROJECT**
LOCATION	:	**Port of Bataraza, Brgy. Buliluyan, Bataraza, Palawan**

A. RC PIER AND RORO RAMP (Area = 1,619.10 sq.m.)

1 Remove and dispose existing roro ramp (deck and beam included) (125 sq.m.)
2 Chip-off of existing pile cap for build-up (19 no.)
3 Remove existing rubber dock fender and turn-over to the Authority (3 no.)
4 Chip-off RC curb and smoothened with mortar (17 l.m.)
5 Supply, deliver and drive 450mm x 450mm PSC Test piles (3 no.)
6 Supply and deliver to site PSC piles (450mm x 450mm) (5,982 l.m.)
7 Handle, pitch and drive vertical PSC piles (450mm x 450mm) (3,024 l.m.) and batter PSC piles (450mm x 450mm) (2,958 l.m.)
8 Chip/cut and dispose portion of driven PSC piles up to required elevation (213 no.)
9 Apply concrete epoxy to existing concrete prior to concrete pouring (19 sq.m .)
10 Supply and place 3,500 psi concrete for the superstructure (815 cu.m.)
11 Supply and install steel reinforcement for the superstructure (122,755 kg.)
12 Supply and install 20mm thk. steel ramp protection plate (ASTM A572, Grade 50) including dowel connectors (5,616 kg.)
13 Supply and install hot-dipped galvanized 100mm x 100mm x 10mm angle bar for construction joints, including dowel bars (54 l.m.)
14 Supply, deliver to site and install Rubber Dock Fender (V600H x 2,000L) including accessories (12 sets)
15 Supply, deliver to site and install Rubber Dock Fender (V500H x 1,500L) including accessories (5 sets)
16 Supply, deliver to site and install Mooring Bollard (50-Tons, T-head) including accessories (5 sets)
17 Supply, deliver to site and install Mooring Bollard (35-Tons, T-head) including accessories (7 sets)

APPROVED BUDGET FOR THE CONTRACT	:	**Php**	**126,311,651.23**
SOURCES OF FUNDING	:	**PPA Corporate Fund**	
TOTAL PROJECT COST	:	**Php**	**142,732,165.89**
PROJECT DURATION	:	**450 Calendar Days**	