PROJECT FEATURE

PROJECT TITLE	:	**CONSTRUCTION OF CRANE RAILWAY & INSTALLATION OF QUAY CRANE**
LOCATION	:	**Iloilo Commercial Port Complex (ICPC), Loboc, Lapaz, Iloilo City**

: **A REMOVAL, DISPOSAL AND EXCAVATION WORKS**

1 Removal of existing rubber dock fender and mooring bollard
2 Removal & disposal of existing RC deck including piles
3 Removal of existing building structure
4 Removal & disposal of pavement
5 Excavation and backfilling work

B UPGRADING OF EXISTING R.C. WHARF

1 Supply & delivery of Steel Pipe Piles including polyurethane
2 Handling, pitching & driving of Steel Pipe piles
3 Fabrication of band tip and splicing of steel pipe piles
4 Cutting & disposal of newly driven Steel Pipe piles
5 Extraction of clogged materials inside the SPP
6 Supply & placing of concrete filler for SPP
7 Supply & installation of reinforcing steel cage for SPP
8 Supply & installation of reinforcing steel bars for the superstructure
9 Supply & placing of concrete for the superstructure
10 Construction of cable trench
11 Installation of crane rail system and accessories
12 Supply & installation of cone fenders
13 Reinstallation of mooring bollards

C. POWER HOUSE, FENCE AND GATE

1 Construction of powerhouse, complete with architectural finishes, structural, electrical, plumbing, drainge and painting etc.
2 Construction of cable trench and accessories
3 Construction of perimeter fence
4 Drainage system
5 Supply and placing of gravel for the substation compound
6 Restoration of the newly removed concrete pavement

D. QUAY CRANE & ELECTRICAL SYSTEM

1 Supply, delivery & installation of primary cables
2 Supply, delivery & installation of conduit pipes
3 Supply, delivery & installation of lighting protection
4 Supply, delivery & installation of primary service entrance
5 Supply, delivery & installation of switch gear assembly
6 Supply, delivery & installation of generation set
7 Supply, delivery & installation of powerhouse distribution panels
8 Supply, delivery & installation of pad mounted transfomer
9 Supply, delivery & installation of quay crane and accessories

APPROVED BUDGET FOR THE CONTRACT	:	**Php**	**1,790,369,324.03**
SOURCES OF FUNDING	:	**PPA Corporate Fund**	
TOTAL PROJECT COST	:	**Php**	**1,888,839,636.85**
PROJECT DURATION	:	**720 Calendar Days**	