

LFP MOC NO. 004-2022

## PROJECT FEATURE

|   |   |  |
|---|---|--|
| <b>PROJECT TITLE</b>                    | : | Proposed Dredging of Ports of Cagayan De Oro, Opol and Balingoan, Misamis Oriental; Benoni, Balbagon and Guinsiliban, Camiguin   |
| <b>LOCATION</b>                         | : | Misamis Oriental and Camiguin Island   |
| <b>MAJOR SCOPE OF WORK</b>              | : | <p>1) Dredging along berths and maneuvering areas of the Ports to a designed depth below Mean Lower Low Water (MLLW) as follows:</p> <p>a. Cagayan de Oro Port = 14.00 m.</p> <p>b. Opol Port = 9.50 m.</p> <p>c. Balingoan Port = 6.00 m.</p> <p>d. Benoni Port = 6.00 m.</p> <p>e. Balbagon Port = 6.00 m.</p> <p>f. Guinsiliban Port = 6.00 m.</p> <p>2) Total Volume to be Dredged : 194,300 cu.m. for berths and maneuvering area of loose to medium dense clayish soil, mud, silt and sand with possible compacted/hard materials.</p> <p>3) Disposal of dredged soil materials 20.00 kms away from the project site</p> |
| <b>APPROVED BUDGET FOR THE CONTRACT</b> | : | 92,722,490.39  |
| <b>TOTAL PROJECT COST</b>               | : | 95,967,777.55  |
| <b>PROJECT (DREDGING) UNIT COST</b>     | : | <p>P 461.72 per cubic meter</p> <p>(Dredging Works Only, excluding General Expenses and Re-imbursable Items)</p>   |
| <b>PROJECT DURATION</b>                 | : | <p>281 calendar days</p> <p>(inclusive of Sundays / Holidays and unworkable condition)</p>   |

