



LFP NBB NO. 005-2022

PROJECT FEATURE

PROJECT TITLE	:	Proposed Dredging of Ports of Banago, San Carlos and Danao, Escalante; Negros Occidental
LOCATION	:	Negros Occidental
MAJOR SCOPE OF WORK	:	<div>1) Dredging along berths and maneuvering areas of the Port and Navigational Channel to a designed depth below Mean Lower Low Water (MLLW) as follows: 6.50 m. for Banago port 4.50m & 6.00 m. for Danao Port 6.50 m. for San Carlos Port 2) Total Volume to be Dredged : 566,000 cubic meters Banago Port = 239,600 cubic meters Danao Port = 281,400 cubic meters San Carlos Port = 45,000 cubic meters 3) Kind of materials to be dredged : dense clayish soil, mud, silt and sand with possible compacted/hard materials. 4) Disposal of dredged soil materials 16.00 kms away from the project site</div>
APPROVED BUDGET FOR THE CONTRACT	:	P 260,617,845.17
TOTAL PROJECT COST	:	P 263,536,765.03
PROJECT (DREDGING) UNIT COST	:	P 452.87 per cubic meter (Dredging Works Only, excluding General Expenses and Re-Imbursable Items)
PROJECT DURATION	:	697 calendar days (inclusive of Sundays / Holidays and unworkable condition)

A large, stylized handwritten signature or checkmark in the bottom left corner.

A handwritten signature or mark in the bottom right corner.