



LFP NCS NO. 003-2022  
Form No. 1

PROJECT FEATURE

PROJECT TITLE : Proposed Dredging of Pasig River (El Codo to Mouth)

LOCATION : South Harbor, Manila

MAJOR SCOPE OF WORK :

- 1) Deepening/dredging of Pasig River waterways, from its Mouth to El Codo area, up to designed project depth of 5.0 meter below Mean Lower Low Water (MLLW) with 1:5 sideslope on both sides
- 2) Total Volume to be dredged :  
550,000.00 cu.m. of loose to medium dense clayish soil, mud, silt, sand, trash and debris with possible compacted/hard materials
- 3) Disposal of dredged/excavated soil materials  
18.50 km. away from the project site

APPROVED BUDGET FOR THE CONTRACT : P 256,096,297.38,

TOTAL PROJECT COST : P 262,498,704.81

PROJECT (DREDGING) UNIT COST : P 453.56 per cubic meter  
(Dredging Works Only)

PROJECT DURATION : 705 calendar days  
(inclusive of Sundays / Holidays and unworkable condition)