

PROJECT FEATURE

PROJECT TITLE : **RE-CONSTRUCTION OF R.C. PIER & CONST. OF RORO RAMP**

LOCATION : **Port of Carmen, San Agustin, Romblon**

- SCOPE OF WORK** :
- A. CONSTRUCTION OF RORO RAMP & PLATFORM**
 - 1 Supply, & driving of PSC square piles (1,208 l.m.)
 - 2 Splicing & Chipping/cutting of newly driven PSC Piles (42 no.)
 - 3 Supply & placing of concrete (135 cu.m.)
 - 4 Supply & installation of steel reinforcement (28,878 kg.)
 - 5 Supply & installation of construction joints (11 l.m.)
 - 6 Supply & installation of rubber dock fenders (4 sets)
 - 7 Supply & installation of mooring bollards (4 sets)

 - B. RECONSTRUCTION OF R.C. PIER**
 - 1 Chipping & disposal of existing R.C. Curb (19 l.m.)
 - 2 Removal of existing mooring & fenders (5 set)
 - 3 Demolition & disposal of existing R.C. Piers deck (351 sq.m.)
 - 4 Cutting & disposal existing R.C. Piles up to seabed elevation (52 no.)
 - 5 Supply, deliver & drive of PSC square piles (1,508 l.m.)
 - 6 Splicing & Chipping/cutting of newly driven PSC Piles (52 no.)
 - 7 Supply & placing of concrete (158 cu.m.)
 - 8 Supply & installation of steel reinforcement (23,404 kg.)
 - 9 Supply & installation of construction joints (19 l.m.)
 - 10 Supply & installation of rubber dock fenders (7 sets)
 - 11 Supply & installation of mooring bollards (6 sets)

APPROVED BUDGET FOR THE CONTRACT : **Php 44,084,950.00**

SOURCES OF FUNDING : **PPA Corporate Fund**

TOTAL PROJECT COST : **Php 48,008,510.55**

PROJECT DURATION : **300 Calendar Days**