

PROJECT FEATURE

PROJECT TITLE : COBO PORT DEVELOPMENT PROJECT

LOCATION : Port of Cobo, Pandan, Catanduanes

SCOPE OF WORK A. CONSTRUCTION OF ROCK CAUSEWAY AND BACK-UP AREA

- 1 Excavation of existing seabed (175 cu.m.)
- 2 Supply and place 50-100 kg./pc. core rocks (3,092 cu.m.)
- 3 Supply and place 1,000 kg./pc. armour rocks (1,086 cu.m.)
- 4 Supply and place 2,000 kg./pc. armour rocks (3,229 cu.m.)
- 5 Supply, spread and compact sand and gravel fill (3,505 cu.m.)
- 6 Supply and install geotextile fabric filter (1,680 sq.m.)
- 7 Supply, spread and compact selected fill (1,476 cu.m.)
- 8 Supply, spread and compact aggregate base course (370 cu.m.)
- 9 Construct Portland cement concrete pavement, 250mm thk. (1,903 sq.m.)
- 10 Supply and place 3,500 psi concrete for the stairlanding, RC curb, lamp post foundation and mooring cleat foundation (204 cu.m.)
- 11 Supply and install steel reinforcement for the stairlanding, RC curb, lamp post foundation and mooring cleat foundation (12,202 kg.)
- 12 Supply, deliver and install mooring cleat (905 kg.) including accessories (6 no.)
- 13 Supply, fabricate and install perimeter fence using Cyclone wire mesh (3.10mm Ø x 50mm x 50mm hole) and G.I. pipes including painting (203 l.m)
- 14 Supply, deliver and install 10m high steel tapered lamp post with 70 watt LED integrated solar street light lamp fixture and accessories (6 no.)

APPROVED BUDGET FOR THE CONTRACT : Php 49,974,613.04

SOURCES OF FUNDING : PPA Corporate Fund

TOTAL PROJECT COST : Php 56,471,312.73

PROJECT DURATION : 300 Calendar Days