

PROJECT FEATURE

PROJECT TITLE : **PROPOSED CONSTRUCTION OF RC WHARF EXTENSION**

LOCATION : **Port of Liloy, Lamao, Zamboanga del Norte**

SCOPE OF WORK **A. CONSTRUCTION OF RC WHARF EXTENSION**
(Area = 594 sq.m.)

1. Supply and drive A252 Grade 2, 500mm ϕ x 12mm thk. Steel Pipe Piles (318 m.t.- 2,196 l.m.) including application of polyurethane external coating (1,493 sq.m.) , splicing (72 pcs), cutting (72 pcs) and installation of reinforcing band tip (72 pcs)
2. Supply and place 3,500 psi concrete filler (197 cu.m.) and reinforcing steel cage (52859 kgs of various sizes) for steel pipe piles including extraction of clogged materials (65 cu.m.)
3. Supply and place 3,500 psi concrete (309 cu.m.) and reinforcing steel bars (43,201 kg of various sizes) for superstructure
4. Supply and install mooring bollard, 35 tons, T-head (10 sets), and rubber dock fender, V-type, 500H x 1500L (18 sets)

APPROVED BUDGET FOR THE CONTRACT : P **63,789,567.78**
Sources of Funding : **PPA Corporate Fund**

TOTAL PROJECT COST : P **70,806,420.24**

PROJECT DURATION : **300 C.D.**

ok

P