

PROJECT FEATURE

PROJECT TITLE	:	PALOMPON PORT IMPROVEMENT PROJECT	
LOCATION	:	Port of Palompon, Leyte	
SCOPE OF WORK	:	<p>A. DEMOLITION & REMOVAL WORKS</p> <ol style="list-style-type: none"> 1 Demolition and disposal of existing concrete pavement (3,503 sq.m.) 2 Chipping and disposal of existing R.C. Curb (70 l.m.) 3 Scraping of existing gravel base materials (3,503 cu.m.) <p>B. CONST. OF BACK-UP AREA WITH RO-RO RAMP (ON-FILL)</p> <ol style="list-style-type: none"> 1 Supply and driving of 3500 x 600mm PSC Sheet piles (2,070 l.m.) 2 Supply and installation of Tie rods (various sizes, 42 sets) 3 Supply and placing of 3,500 psi concrete (267 cu.m.) 4 Supply and installation of steel reinforcement (23,809 kg.) 5 Supply and placing of 50-1000 kg/pc. Rocks (719 cu.m.) 6 Supply and placing of fill materials (3,540 cu.m.) 7 Construction of 250mm thk. PCC pavement (901 sq.m.) 8 Supply and installation of V-type Rubber Dock Fenders (6 sets) 9 Supply and installation of 35T Mooring Bollard (4 sets) <p>C. CONST. OF PORT OPERATIONS BUILDING</p> <ol style="list-style-type: none"> 1 Supply and driving of 400 x 400mm PSC foundation piles (840 l.m.) 2 Construction of 1-storey Port Operations Building (625 sq.m., 250 pax) 3 Construction of Pumphouse (12.24 sq.m.) 4 Construction of 300mm thk. Concrete Pavement (936 sq.m.) 5 Construction of R.C. Ductbank, handhole & pedestal (33 cu.m.) 6 Supply, delivery, installation of gang chairs (1 lot) <p>D. CONST. OF TRANSIT SHED</p> <ol style="list-style-type: none"> 1 Supply and driving of 400 x 400mm PSC foundation piles (840 l.m.) 2 Construction of Transit Shed Building (1,456 sq.m.) 3 Construction of 300mm thk. Concrete Pavement (656 sq.m.) 4 Construction of R.C. Ductbank & handhole (10 cu.m.) 5 Supply & installation of distribution line (1 lot) 	
APPROVED BUDGET FOR THE CONTRACT	:	Php	124,476,174.60
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:	Php	129,953,126.28
PROJECT DURATION	:	540 Calendar Days	

45

8

2