



PROJECT FEATURE

PROJECT TITLE : Proposed Dredging of Batangas Clustered Project:
Ports of Calatagan, Bauan and Nasugbu

LOCATION : Province of Batangas

MAJOR SCOPE OF WORK :

- 1) Dredging along berths, approaches and maneuvering areas of the Ports to a designed depth below Mean Lower Low Water (MLLW) as follows:
4.50 m. @ Calatagan Port
6.00 m and 8.00 m @ Bauan Port
6.00 m. @ Nasugbu Port
- 2) Total Volume to be Dredged : 360,000 cu.m.
(225,000cu.m. at Calatagan Port comprising of medium to highly dense with limestone like materials and
75,000 cu.m. and 60,000 cu.m. at Bauan and Nasugbu Ports, respectively of soft to medium clayish sand/mud, silt, sand and pebbles with possible compacted soil)
- 3) Disposal of dredged soil materials 15.00 kms away from the project site

APPROVED BUDGET FOR THE CONTRACT : P 205,351,654.79

TOTAL PROJECT COST : P 210,485,446.16

PROJECT (DREDGING) UNIT COST : P 587.46 per cubic meter @ Calatagan Port

P 480.76 per cubic meter @ Bauan and Nasugbu Ports

(Dredging Works Only, excluding General Expenses and Re-Imbursable Items)

PROJECT DURATION : 541 calendar days
(inclusive of Sundays / Holidays and unworkable condition)