

LFP MDO No. 002 - 2021

PROJECT FEATURE

PROJECT TITLE : **PROPOSED RC PIER EXTENSION**

LOCATION : **Port of San Jose, Caminawit, San Jose, Occidental Mindoro**

SCOPE OF WORK : **A. RC PIER EXTENSION**
(Area = 75m x 12m = 900 sq.m.)

- 1 Chip-off portion of existing RC curb (12 l.m.)
- 2 Supply and drive A252 Grade 2, 500mmØ Steel Pipe Piles (445 m.t.- 3,534 l.m.) including application of polyurethane external coating (1,801 sq.m.), installation of reinforcing band tip (94 pcs), splicing (94 pcs) and cutting (94 pcs)
- 3 Supply and place 3,500 psi concrete filler (243 cu.m.) and reinforcing steel cage (69,284 kgs of various sizes) for steel pipe piles including extraction of clogged materials (51 cu.m.)
- 4 Supply and place 3,500 psi concrete (471 cu.m.) and reinforcing steel bars (71,131 kg of various sizes) for superstructure
- 5 Supply and install construction joints 100mm x 100mm x 10mm angle bar (12 l.m.) and BWT 175x38 (12 l.m.)
- 6 Supply and install of Rubber Dock Fenders (V500 x 1500L - 18 sets) and Mooring Bollard, (35-Tons, T-head - 18 sets)

APPROVED BUDGET FOR THE CONTRACT : **Php 88,234,376.24** ✓

SOURCES OF FUNDING : **PPA Corporate Fund**

TOTAL PROJECT COST : **Php 99,704,845.16** ✓

PROJECT DURATION : **360 Calendar Days** ✓

mf

[Signature]

[Signature]

[Signature]