

PROJECT FEATURE

PROJECT TITLE	: Proposed Dredging of Dapitan, Iligan and Cagayan de Oro Ports
LOCATION	: Northern Mindanao
MAJOR SCOPE OF WORK	<p>: 1) Dredging along berths and maneuvering areas of the Ports to a designed depth below Mean Lower Low Water (MLLW) as follows: 6.00 and 8.00 m. for Dapitan Port 5.50, 8.00 and 11.00 m for Iligan Port 11.00 and 13.00 m. for Cagayan de Oro Port</p> <p>2) Total Volume to be Dredged : 155,000 cu.m. (45,000 cu.m., 40,000 cu.m. and 70,000 cu.m., respectively) of loose to medium dense clayish soil, mud, silt and sand with possible compacted/hard materials.</p> <p>3) Disposal of dredged soil materials 16.00 kms away from the project site</p>
APPROVED BUDGET FOR THE CONTRACT	: P 81,981,666.52
TOTAL PROJECT COST	: P 84,851,024.85
PROJECT (DREDGING) UNIT COST	: P 482.89 per cubic meter (Dredging Works Only, excluding General Expenses and Re-Imbursable Items)
PROJECT DURATION	: 230 calendar days (inclusive of Sundays / Holidays and unworkable condition)