

LFP WLB NO. 010-2022

# PROJECT FEATURE

PROJECT TITLE : CONSTRUCTION OF PORT OPERATIONAL AREA ✓

LOCATION : Port of Guadalupe, Maasin City, Southern Leyte ✓

SCOPE OF WORK : A. DEMOLITION, EXCAVATION AND REMOVAL WORKS ✓

- 1 Chipping & disposal of existing R.C. Curb (86 l.m.) ✓
- 2 Demolition & disposal of existing R.C. breasting dolphin (33 cu.m.) ✓
- 3 Cutting & disposal of existing piles (18 units) ✓
- 4 Excavation of existing seabed (528 cu.m.) ✓
- 5 Removal of existing mooring bollard & rubber dock fenders (4 sets) ✓

B. PORT OPERATIONAL AREA ✓

- 1 Supply, delivery & driving of PSC Sheet Piles & RC Corner Piles (2,460 l.m.) ✓
- 2 Chipping & cutting of newly driven Sheet piles and Corner piles (164 units) ✓
- 3 Supply & placing of 3,500 psi concrete for retaining wall, etc. (512 cu.m.) ✓
- 4 Supply & installation of steel reinforcement for retaining wall, etc. (38,465 kg.) ✓
- 5 Supply & placing of core rocks & armour rocks (7,558 cu.m.) ✓
- 6 Supply & installation of concrete blocks (4 sets) ✓
- 7 Supply & installation of Tie-rod of various sizes (51 sets) ✓
- 8 Supply & placing of fill materials (22,664 cu.m.) ✓
- 9 Construction of PCC Pavement including Agg. Base Course (4,618 sq.m.) ✓
- 10 Supply & installation of rubber dock fenders (8 sets) ✓
- 11 Supply & installation/reinstallation of Mooring bollard (4 sets) ✓
- 12 Supply & installation of Portlighting system (5 sets) ✓

APPROVED BUDGET FOR THE CONTRACT : Php 129,207,028.61 ✓

SOURCES OF FUNDING : PPA Corporate Fund ✓

TOTAL PROJECT COST : Php 146,003,942.33 ✓

PROJECT DURATION : 360 Calendar Days

*[Handwritten mark]*

*[Handwritten mark]*

*[Handwritten mark]*

*[Handwritten mark]*