

## PROJECT FEATURE

**PROJECT TITLE** : **PROPOSED SALOMAGUE PORT IMPROVEMENT PROJECT**

**LOCATION** : **Port of Salomague, Cabugao, Ilocos Sur**

**SCOPE OF WORK**

**A. EXTENSION OF RC PIER**

**( Area = 1,647 sq.m.)**

1. Chipping of existing rc curb (9 l.m.)
2. Supply and drive 450mm x 450mm PSC piles (6,960 l.m.), including splicing (62 pcs), chipping and cutting of newly driven piles up to required elevation (244 pcs), supply and place 3,500 psi reinforced concrete (848 cu.m.) and steel bars (110,009 kg of various sizes) for superstructure
3. Supply and install rubber dock fenders, V-Type, 500H x 1,500L (42 sets) and mooring bollards, 35 tons, T-head (22 sets)

**B. CONSTRUCTION OF CRUISE SHIP BERTH**

**( Area = 1,100.45 sq.m.)**

1. Supply and drive 450mm x 450mm PSC piles (5,539 l.m.), including splicing (163 pcs), chipping and cutting of newly driven piles up to required elevation (163 pcs), supply and place 3,500 psi reinforced concrete (571 cu.m.) and steel bars (73,353 kg of various sizes) for superstructure
2. Supply and install rubber dock fenders, V-Type, 500H x 2,000L (28 sets) and mooring bollards, 50 tons, T-head (14 sets)

**APPROVED BUDGET FOR THE CONTRACT** : P **152,196,809.05**  
**Sources of Funding** : **PPA Corporate Fund**

**TOTAL PROJECT COST** : P **171,982,394.23**

**PROJECT DURATION** : **420 C.D.**