

PROJECT FEATURE

PROJECT TITLE : **Proposed Dredging of Calapan and Roxas Ports**

LOCATION : **Oriental Mindoro**

MAJOR SCOPE OF WORK : **1) Dredging along the berths and maneuvering areas of the Ports to a designed depth of 6.0 meter below Mean Lower Low Water (MLLW)**

2) Total Combined Volume to be Dredged :
60,000.00 cu.m. of loose to medium dense clayish soil, mud, silt and sand with possible compacted/hard materials

3) Disposal of dredged soil materials 16.00 kms away from the project site

APPROVED BUDGET FOR THE CONTRACT : **P 34,455,338.72**

TOTAL PROJECT COST : **P 35,661,275.58**

PROJECT (DREDGING) UNIT COST : **P 490.59 per cubic meter**
(Dredging Works Only, excluding General Expenses and Re-Imbursable Items)

PROJECT DURATION : **90 calendar days**
(inclusive of Sundays / Holidays and unworkable condition)

