

PROJECT FEATURE

PROJECT TITLE : Proposed Dredging of Lamao Port

LOCATION : Limay, Bataan

MAJOR SCOPE OF WORK :

- 1) Dredging along the berths and maneuvering areas of the Port to a designed depth of 5.50 meter below Mean Lower Low Water (MLLW)
- 2) Total Volume to be Dredged :
60,000.00 cu.m. of loose to medium dense clayish soil, mud, silt and sand with possible compacted/hard materials
- 3) Disposal of dredged soil materials 16.00 kms away from the project site

APPROVED BUDGET FOR THE CONTRACT : P 31,370,762.17

TOTAL PROJECT COST : P 32,468,738.86

PROJECT (DREDGING) UNIT COST : P 489.82 per cubic meter
(Dredging Works Only, excluding General Expenses and Re-Imbursable Items)

PROJECT DURATION : 90 calendar days
(inclusive of Sundays / Holidays and unworkable condition)