

# PROJECT FEATURE

**PROJECT TITLE** : Proposed Dredging of Puerto Princesa Port

**LOCATION** : Puerto Princesa City, Palawan

**MAJOR SCOPE OF WORK** :

- 1) Dredging along berths of the Port to a designed depths of 6.0m, 10.0m and 11.0m below Mean Lower Low Water (MLLW) as indicated in the plan
- 2) Total Volume to be Dredged :  
150,000.00 cu.m. of loose to medium dense clayish soil, mud, silt and sand with possible compacted/hard materials
- 3) Disposal of dredged/excavated soil materials  
16.00 kms away from the project site

**APPROVED BUDGET FOR THE CONTRACT** : P 76,647,252.17

**TOTAL PROJECT COST** : P 79,329,906.00

**PROJECT (DREDGING) UNIT COST** : P 478.46 per cubic meter  
(Dredging Works Only, excluding General Expenses and Re-Imbursable Items)

**PROJECT DURATION** : 180 calendar days  
(inclusive of Sundays / Holidays and unworkable condition)