

PROJECT FEATURE

PROJECT TITLE : **PROPOSED CONSTRUCTION OF RC PIER EXTENSION**

LOCATION : **Port of Dapitan, Dapitan City, Zamboanga del Norte**

SCOPE OF WORK **A. CONSTRUCTION OF RC PIER EXTENSION**
(Area = 810.00 sq.m.)

1. Supply and drive A252 Grade 2, 550mm ϕ x 12mm thk. Steel Pipe Piles (352 m.t.- 2,205 l.m.) including application of polyurethane external coating (519 sq.m.) , cutting (75 pcs), and installation of reinforcing band tip (75 pcs)
2. Supply and place 3,500 psi concrete filler (278 cu.m.) and reinforcing steel cage (58,858 kgs of various sizes) for steel pipe piles including extraction of clogged materials (83 cu.m.)
3. Supply and place 3,500 psi concrete (387 cu.m.) and reinforcing steel bars (55,928 kg of various sizes) for superstructure
4. Supply and install mooring bollard, 35 tons, T-head (8 sets), and rubber dock fender, V-type, 500H x 1500L (14 sets)

APPROVED BUDGET FOR THE CONTRACT : P **66,228,667.57**

Sources of Funding : **PPA Corporate Fund**

TOTAL PROJECT COST : P **71,526,960.98**

PROJECT DURATION : **330 C.D.**