

LFP MRQ 011-2021

**PROJECT FEATURE**

<b>PROJECT TITLE</b>	:	<b>PLARIDEL PORT DEVELOPMENT / IMPROVEMENT PROJECT</b>	
<b>LOCATION</b>	:	<b>Port of Plaridel (Siain), Quezon</b>	
<b>SCOPE OF WORK</b>	:	<b>A. DEMOLITION AND REMOVAL WORKS</b> 1 Demolition & disposal of existing R.C. deck (1,000 sq.m.) 2 Cutting & disposal of existing R.C. Pile up to elevation +1.00m (67 nos.) 3 Cutting & disposal of existing R.C. Pile up to seabed elevation (84 nos.)  <b>B. ROCK CAUSEWAY</b> 1 Excavation of existing seabed (5,170 cu.m.) 2 Supply & placing of concrete (206 cu.m.) 3 Supply & installation of reinforcing steel bars (18,238 kg.) 4 Supply & placing of rocks (6,563 cu.m.) 5 Supply & placing of fill materials (1,491 cu.m.) 6 Supply & placing of aggregate base course (118 cu.m.) 7 Construction of Concrete pavement (589 sq.m.)  <b>C. R.C. PIER</b> 1 Supply & delivery of Steel Pipe Piles (443 m.t.) 2 Handling, pitching & driving of Steel Pipe piles (4,193 l.m.) 3 Splicing of Steel Pipe piles (182 nos.) 4 Cutting of newly driven Steel Pipe piles (91 nos.) 5 Extraction of clogged materials inside SPP (72 cu.m.) 6 Supply & placing of 3,500 psi concrete for SPP & Deck (608 cu.m.) 7 Supply & installation of reinforcing steel bars for SPP & Deck (97,293 kg.) 8 Supply & installation of construction joints (24 l.m.) 9 Supply & installation of Mooring bollards (16 sets) 10 Supply & installation of Rubber dock fenders (16 sets)	
<b>APPROVED BUDGET FOR THE CONTRACT</b>	:	<b>Php</b>	<b>142,829,373.05</b> ✓
<b>SOURCES OF FUNDING</b>	:	<b>PPA Corporate Fund</b>	
<b>TOTAL PROJECT COST</b>	:	<b>Php</b>	<b>161,397,191.54</b> ✓
<b>PROJECT DURATION</b>	:	<b>540 Calendar Days</b>	/