

PROJECT FEATURE

PROJECT TITLE	:	CONSTRUCTION OF BACK-UP AREA	
LOCATION	:	Port of Getafe, Bohol	
SCOPE OF WORK	:	A. BACK-UP AREA 1 Demolition & disposal of existing concrete pavement (299 sq.m) 2 Excavation of existing seabed (11,568 cu.m.) 3 Excavation of existing fill materials (60 cu.m.) 4 Supply & placing of concrete (541 cu.m.) 5 Supply & installation of steel reinforcement (56,864 kg.) 6 Supply & installation of concrete blocks (229 cu.m.) 7 Supply, driving & chipping of PSC Sheet piles & corner piles (6,594 l.m.) 9 Supply & installation of core rocks (11,178 cu.m.) 10 Supply & placing of fill materials (21,674 cu.m.) 11 Supply & placing of aggregate base course (61 cu.m.) 12 Construction of Portland Cement Concrete Pavement (299 sq.m.) 13 Supply & installation of Tie-rods (90 sets) 14 Supply & installation of rubber dock fenders & mooring bollards (21 sets) 15 Construction of Security Fence (45 l.m.)	
APPROVED BUDGET FOR THE CONTRACT	:	Php	163,296,490.50
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:	Php	184,525,034.27
PROJECT DURATION	:	360 Calendar Days	



