

PROJECT FEATURE

PROJECT TITLE : CONSTRUCTION OF PORT OPERATIONS BUILDING AND TRANSIT SHED

LOCATION : Port of Masbate, Masbate City

: **A. REMOVAL WORKS**

- 1 Removal of existing drainage including disposal (76 l.m.)
- 2 Removal of existing concrete pavement including disposal (2,159 sq.m.)
- 3 Scraping and compaction of existing gravel base materials (2,159 sq.m.)
- 4 Removal of existing building structures including disposal (1 lot)
- 5 Removal of existing fence including disposal (53 l.m.)
- 6 Removal of existing light post (1 unit)
- 7 Removal of existing high mast tower (1 unit)

B. PORT OPERATIONS BUILDING

- 1 Construction of 2-storey Port Operations Building (3,187.67 sq.m., 500 pax capacity)
- 2 Supply and driving of 400 x 400mm PSC foundation piles (1,704 l.m.)
- 3 Construction of Pumphouse and apurtenances (14.28 sq.m.)
- 4 Construction of 300mm thk. Concrete Pavement (512 sq.m.)
- 5 Supply, delivery and installation of office furnitures, gang chairs, modular worktop and accessories (1 lot)
- 6 Supply & installation of distribution line transformmer (1 lot)

C. TRANSIT SHED

- 1 Construction of Transit Shed Building (1,100.14 sq.m.)
- 2 Supply and driving of 400 x 400mm PSC foundation piles (528 l.m.)
- 3 Construction of 300mm thk. Concrete Pavement (1,103 sq.m.)

APPROVED BUDGET FOR THE CONTRACT	:	₱142,613,052.34
SOURCE OF FUNDING	:	PPA Corporate Fund
TOTAL PROJECT COST	:	₱161,152,749.14
PROJECT DURATION	:	540 Calendar days