

## PROJECT FEATURE

PROJECT TITLE	:	PUERTO PRINCESA PORT EXPANSION PROJECT (PHASE 1)	
LOCATION	:	Port of Puerto Princesa, Puerto Princesa City, Palawan	
SCOPE OF WORK	:	<p><b>A. REMOVAL AND EXCAVATION WORKS</b></p> <ol style="list-style-type: none"><li>1 Removal and disposal of existing rc curb</li><li>2 Removal and turnover of existing interlocking paving block</li><li>3 Excavation of existing filling materials</li><li>4 Removal and turnover of existing mooring and fendering system</li><li>5 Removal and disposal of existing sheet pile containment</li><li>6 Excavation of existing sea bed</li></ol> <p><b>B. ENCLOSURE &amp; UPGRADING OF PORT OPERATIONAL AREA</b></p> <ol style="list-style-type: none"><li>1 Supply &amp; driving of Steel Pipe pile including connector &amp; polyurethane</li><li>2 Supply, fabrication of cylinder band tip for the steel pipe piles</li><li>3 Handling, pitching &amp; driving of Steel Pipe piles</li><li>4 Supply &amp; installation of steel waling and splice plate</li><li>5 Cutting of newly driven steel pipe piles</li><li>6 Supply &amp; placing of sand filler for SPP</li><li>7 Supply &amp; placing of concrete filler for SPP</li><li>8 Supply &amp; installation of reinforcing steel cage for SPP</li><li>9 Supply &amp; placing of 3,500 psi concrete</li><li>10 Supply &amp; installation of reinforcing steel bars</li><li>11 Supply &amp; placing of gravel bedding</li><li>12 Supply &amp; placing of 50 to 100 kg. rocks</li><li>13 Supply &amp; installation of Tie-rod</li><li>14 Supply &amp; installation of geotextile fabric</li><li>15 Supply &amp; placing of fill materials</li><li>16 Supply &amp; placing of aggregate base course</li><li>17 Construction of PCC Pavement</li><li>18 Construction of Drainage system</li></ol>	
APPROVED BUDGET FOR THE CONTRACT	:	Php	599,145,965.51 ✓
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:	Php	677,034,941.03 ✓
PROJECT DURATION	:	660 Calendar Days	

9

8