

PROJECT FEATURE			
PROJECT TITLE	:	RESTORATION OF DAMAGED PORT FACILITIES CAUSED BY TYPHOON ODETTE	
LOCATION	:	PORT OF MAASIN, SOUTHERN LEYTE	
SCOPE OF WORK			
		BILL NO. 1 GENERAL EXPENSES	
		1.01	Mobilization and Demobilization and Clean Up of Site
		1.02	Provide and Maintenance of Engineer's Site Office
		1.03	Provide Environmental Safety and Health Program
		BILL NO. 2 RETAINING WALL WITH ANCHOR TIE RODS	
		2.01	Demolition and Disposal of Damaged Existing Structure
		2.02	Supply and Installation of Steel Reinforcements
		2.03	Supply, Installation and Removal of Formworks
		2.04	Supply, Place and Compaction of 4000 Psi concrete
		2.05	Supply and Installation of Geotextile Filter Fabric
		2.06	Removal and Replacement of Anchor Tie Rods
		2.07	Supply and Installation of Rubble Stone
		BILL NO. 3 EARTHWORKS	
		3.01	Excavation of Existing Granular Fill, Base Course and Sub Base Course
		3.02	Supply, Backfill and Compaction of Granular Fill
		BILL NO. 4 BASE AND SUB BASE COURSE	
		4.01	Supply, Backfilling, Spreading and Compaction of Sub Base Course
		4.02	Supply, Backfilling, Spreading and Compaction of Base Course
		BILL NO. 5 PORTLAND CEMENT CONCRETE PAVEMENT, 280MM	
		5.01	Demolition and Disposal of Damaged Existing Structure
		5.02	Supply, Place and Compaction of 4000 Psi Portland Cement Concrete Pavement
		BILL NO. 6 CONCRETE FENCE WITH PLANT BOX	
		6.01	Demolition and Disposal of Damaged Existing Structure
		6.02	Excavation and Backfilling Works
		6.03	Supply and Installation of Steel Reinforcements
		6.04	Supply, Installation and Removal of Formworks
		6.05	Supply, Place and Compaction of 3500 Psi concrete
		6.06	Supply and Installation of CHB
		6.07	Supply and Application of Paints for Fence and Plant Box
		BILL NO. 7 MOORING AND FENDERING SYSTEM	
		7.01	Removal and Turn-over of Five (5) Units Cylindrical Rubber Dock Fenders and Six (6) Units Mooring Bollards at Wharf
		7.02	Supply, Place and Compaction of Gravel Bedding
		7.03	Supply, and Installation of Steel Reinforcements for Mooring Blocks
		7.04	Supply, Place and Compaction of 3500psi Concrete for Mooring Blocks
		7.05	Supply, Delivery and Installation of Ten (10) Units Cylindrical Rubber Dock Fenders
		7.06	Re-installation of Five (5) Units Mooring Bollards and Three (3) Units Cylindrical Rubber Dock Fenders
APPROVED BUDGET FOR THE CONTRACT	:	Php	42,313,237.21
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:		47,179,259.49
	:	Say	47,179,260.00
PROJECT DURATION	:	420 Calendar Days	