

PROJECT FEATURE

PROJECT TITLE : PROPOSED ABRA DE ILOG PORT EXPANSION PROJECT
LOCATION : Port of Abra de Ilog, Brgy. Matabang, Abra de Ilog, Occidental Mindoro

SCOPE OF WORK

A. CONSTRUCTION OF RC PIER (Area = 81m x 9m = 729 sq.m.)

1. Chipping of existing rc curb (130 l.m.)
2. Supply and drive 400mm x 400mm PSC piles (2,862 l.m.), including chipping and cutting of newly driven piles up to required elevation (108 pcs), supply and place 3,500 psi reinforced concrete (349 cu.m.) and steel bars (56,525 kg of various sizes) for superstructure
3. Supply and install rubber dock fenders, V-Type, 400H x 2,000L (22 sets) and mooring bollards, 35 tons, T-head (12 sets)

B. CONSTRUCTION OF RORO RAMP (Area = 2 pcs - 11m x 9m = 198 sq.m.)

1. Supply and drive 400mm x 400mm PSC piles (972 l.m.), including chipping and cutting of newly driven piles up to required elevation (36 pcs), supply and place 3,500 psi reinforced concrete (148 cu.m.) and steel bars (35,766 kg of various sizes) for superstructure.
2. Supply and install rubber dock fenders, V-Type, 400H x 2,000L (6 sets)

C. CONSTRUCTION OF ACCESS TRESTLE (Area = 775.90 sq.m.)

1. Demolish and dispose existing RC wharf (99 sq.m.), remove and turn-over existing mooring bollard (8 sets)
2. Supply and drive 400mm x 400mm PSC piles (2,427 l.m.), including chipping and cutting of newly driven piles up to required elevation (111 pcs), supply and place 3,500 psi reinforced concrete (301 cu.m.) and steel bars (53,997 kg of various sizes) for superstructure

APPROVED BUDGET FOR THE CONTRACT : P 77,064,149.36
Sources of Funding : PPA Corporate Fund

TOTAL PROJECT COST : P 87,082,488.78

PROJECT DURATION : 360 C.D.