

PROJECT FEATURE

PROJECT TITLE : **PROVISION OF LAY-BY AREA FOR WEIGH BRIDGE**

LOCATION : **PORT OF LUCENA, LUCENA CITY**

SCOPE OF WORK :

1. **Provision of Lay-By Area (A = 820.00 sq.m.)**
 - a) Portland Cement Concrete Pavement, PCCP (A = 524.00 sq.m.)
 - b) Weigh-Bridge Foundation (A = 20.00 sq.m.)
 - c) Control Room (1.80m x 1.80m)
 - d) Segregation Island (A = 113.00 sq.m.)
 - e) Sidewalk and Gutter (A = 156.00 sq.m.)
2. **Provision of Integrated Solar-Powered Port Lights (3 - units)**
 - a) 25 Ft. Tapered Post
 - Tapered Post, 25 ft. Hot-Dip Galvanized w/ Base plate (300mm x 300mm x 20mm w/ 6mm thk. Stiffener Plate) and 4 - 25mmØ x 762mm Anchor Bolt
 - b) 120W LED Integrated Solar-Powered Lighting Assembly
 - 120W, 12V LED Lamp
 - 59AH, 12V Lithium Battery
 - 36V/170W Polycrystal Silicon

APPROVED BUDGET FOR THE CONTRACT : **Php** **6,528,871.53**

SOURCES OF FUNDING : **PPA Corporate Fund**

TOTAL PROJECT COST : **Php** **6,626,804.60**

PROJECT DURATION : **135 Calendar Days**

