

PROJECT FEATURE

PROJECT TITLE : HIGATANGAN PORT DEVELOPMENT PROJECT

LOCATION : Brgy. Libertad, Higatangan Island, Naval, Biliran

- SCOPE OF WORK :
- A. CONSTRUCTION OF CAUSEWAY
 - a. Chipping/demolition of existing R.C. Curb (113 l.m.)
 - b. Demolition/disposal of existing concrete pavement (93 sq.m.)
 - c. Demolition and disposal of existing R.C. Pier (28 sq.m.)
 - d. Scraping of existing fill materials (93 sq.m.)
 - e. Sub-grade preparation (127 cu.m.)
 - f. Supply & placing of 3,500 psi concrete (75 cu.m.)
 - g. Supply & installation of reinforcing steel bars (3,689 kg.)
 - h. Supply & placing of 500 kg. rocks (879 cu.m.)
 - i. Supply & placing of 10-100kg. rocks (817 cu.m.)
 - j. Supply and placing of geotextile fabric (527 sq.m.)
 - k. Supply and placing of sand and gravel fill (28 cu.m.)
 - l. Supply and placing of gravel base course (65 cu.m.)
 - m. Supply and placing of gravel base course (75 cu.m.)
 - n. Construction of Portland Cement Concrete pavement (411 sq.m.)
 - o. Supply and installation of mooring cleat (8 sets)
 - B. CONSTRUCTION OF PASSENGER TERMINAL SHED
 - a. Complete construction of Terminal Shed (30 sq.m.)

APPROVED BUDGET FOR THE CONTRACT	:	Php	9,154,652.93
SOURCES OF FUNDING	:	General Appropriation Act (GAA)	
TOTAL PROJECT COST	:	Php	9,969,417.04
		Say	10,000,000.00
PROJECT DURATION	:	120 Calendar Days	