

After removal of side forms, the ends at transverse expansion joints at the edges of the pavement shall be carefully cleaned of any concrete within the expansion spaces for the entire depth of slab, care being taken not to injure the ends of the joints. Expansion and contraction joints shall then be poured with a hot joint sealer to the depth as indicated on the Drawings. Joint sealer shall be poured using approved hand pouring pots, with liquid at a temperature not less than that recommended by the approved manufacturer.

#### Opening to Traffic

The pavement shall be closed to traffic, including the vehicles of the Contractor, for a period of 10 days after the concrete is placed or longer if in the opinion of the Engineer, the weather conditions make it necessary to extend this time. The Contractor shall furnish, place and maintain satisfactory barricades and lights as directed, to exclude all traffic from the pavement.

Any damage to the pavement due to traffic shall be repaired or replaced at the expense of the Contractor. Paving mixers, mechanical concrete spreaders and finishers and other heavy paving equipment shall not be operated on completed concrete lanes in order to construct alternate lanes until after the regular curing period is completed. Even then, planks shall be laid on the finished pavement or other precautions taken to prevent damage to the concrete pavement.

#### Pavement Smoothness, Thickness and Tolerance

Portland cement concrete pavement shall be constructed to the designed level and transverse slope shown on the Drawing. The allowable tolerance shall be as listed hereunder:

- |    |  |         |
|----|--|---------|
| 1. | Permitted variation from design thickness of layer | + - 5mm |
| 2. | Permitted variation from design level of surface   | + - 5mm |

The thickness of the pavement will be determined by measurement of cores from the completed pavement in accordance with AASHTO T 148.

The completed pavement shall be accepted on a lot basis. A lot shall be considered as 2,500 sq.m of pavement. The last unit in each slab constitutes a lot in itself when its length is at least  $\frac{1}{2}$  of the normal lot length. If the length of the last unit is shorter than  $\frac{1}{2}$  of the normal lot length, it shall be included in the previous lot.

Other areas such as intersections, entrances, crossovers, ramp, etc., will be grouped together to form a lot. Small irregular areas may be included with other unit areas to form a lot.

## ITEM 15 : INTERLINK/ CYCLONE WIRE MESH FENCE

### SCOPE

This work covers all the following requirements regarding the construction of CHB wall, cyclone wire mesh or chain link fences and manufacturing and installation of steel angle frames as all other accessories in accordance with the lines, grades and dimensions shown in the drawings.

### PHYSICAL PROPERTIES

1. All steel, angle frames and accessories shall be inside and out in accordance with international standards for galvanizing BS EN1460.
2. The stiffeners of the steel fences shall be attached to the steel panels using the Welding Process.
3. The allowable tolerances on dimensions on the angular bars shall not exceed the following:
  - a. Thickness - 0.2mm  
(i.e. for 3mm required load bar thickness, the allowable thickness is from 2.8mm to above 3.0 mm only)
  - b. Height - 0.5mm  
(i.e. for 25mm required load bar height, the allowable height is from 24.5 to above 25mm only)
4. Welding shall be in accordance with the AWS Code and as herein specified or any other welding standard, approved by the Engineer.

### MECHANICAL PROPERTIES

The steel fence, barbed wire, steel gratings and angle framing supplier shall be required to submit test certificates for steel materials for the fence panel used in its manufacture; and for hot dip galvanizing which shall meet or exceed the following properties:

ASTM A36 Carbon Steel (Yield Strength = 250 Mpa; Tensile Strength = 400 Mpa)

### DELIVERY, STORAGE, INSTALLATION AND MEASUREMENT

1. Upon delivery at site, the hot dip galvanized steel fence panels, steel gratings and angle frames shall not be subjected to the following activities:
  - a. Re-fabrication
  - b. Cutting
  - c. Grinding
  - d. Welding
  - e. Sawing
  - f. Any hot works or similar activities
2. Stainless steel nuts and bolts may be tack welded using stainless steel welding rods.
3. The steel fence panels steel gratings and angle frames shall not be exposed to sea water and other corrosive chemicals or substances prior to installation.

Installation of the steel fence panels, steel gratings and angle frames shall be in accordance with the Engineer.

## **MATERIALS**

### **1. Concrete Post**

Concrete post shall be made of Class A concrete in accordance with Item 9, Reinforced Concrete. The post shall be cast to the length shown on the detailed Plans, and shall have a smooth surface finish.

### **2. Steel Reinforcement**

Steel reinforcement for concrete post shall be deformed steel bars conforming to the provisions of Item 409, Reinforced Concrete.

### **3. Concrete Hollow Blocks (CHB)**

Concrete hollow blocks shall be standard machine vibrated, and shall have fine and even texture and well defined edges. Units shall be non-load bearing unless otherwise indicated in the drawings. Samples shall be submitted to the Engineer for approval.

### **4. Angular Bar**

The steel angular bar shall be ASTM A36 Carbon Steel with yield strength of 250MPa and Tensile Strength of 400MPa.

### **5. Cyclone Wire Mesh**

Cyclone Wire Mesh shall conform to the requirements of ASTM A 121, Class I.

## **SHOP DRAWING**

Prior to fabrication, the Contractor shall submit for the Engineer's approval shop drawings details of the proposed fencing.

## **CONSTRUCTION**

The Contractor shall perform such clearing and grubbing as may be necessary to construct the fence to required grade and alignment. Fence shall generally follow the contour of the ground. Grading shall be performed where necessary to provide a neat appearance.

The post shall be erected vertically in position inside the formwork of the foundation block prior to the placing of concrete shall be adequately supported by bracing to prevent movement of the post during the placing and setting of the concrete. The post shall be erected to the height and location shown on the Plans, or as ordered by the Engineer.

## **ITEM 16 : DRAINAGE WORKS**

### **SCOPE OF WORK**

The works shall consist of excavation, backfilling and construction of lateral drains, construction of manholes, reconnection to existing lateral and other related works in accordance with the dimensions, size, elevation and grade as shown on the drawing and shall conform with the Specification.

At least thirty (30) days before the start of any construction related to drainage works, the Contractor shall submit to the Engineer for his approval, shop drawings of the drainage work he intends to construct. The shop drawings shall include the materials and the general method of installation he intends to employ.

### **MATERIAL REQUIREMENTS**

#### **SELECTED FILL**

Fill shall be in accordance with Item "Reclamation and Fill".

#### **CRUSHED AGGREGATE BASE COURSE**

Gravel base course shall be in accordance with Item "Crushed Aggregate Base Course".

#### **CONCRETE**

Mixing/Casting and steel reinforcements shall be in accordance with Item "Reinforced Concrete" while the dimensions shall be as shown on the Drawings.

#### **CEMENT MORTAR**

Cement mortar shall consist of one part portland cement to two parts of fine aggregate with water added as necessary to obtain the required consistency.

#### **REINFORCED CONCRETE PIPE**

The fabrication of reinforced concrete pipes shall conform to the Specifications of ASTM C-76. The Engineer reserves the right to inspect and test the pipe delivered for intended purpose. Defects that are discovered after acceptance of delivery of the pipe but before installation shall be a cause for rejection.

Reinforced steel bar for pipe shall be in accordance with Item "Reinforced Concrete" while concrete to be used shall be 4,000 psi.

### **EXECUTION**

#### **EARTHWORKS**

All earthworks for concrete pipe culvert shall conform to the lines, grades and elevations shown on the drawings or as directed by the Engineer.

The lateral drain shall be excavated to the depth, grade and width established by the Engineer. The bedding surface shall provide a firm foundation of uniform density throughout the entire length. Soft, spongy, or otherwise unstable material encountered that will not provide a firm foundation for the concrete drainage shall be removed to the full width of the trenches and replaced by suitable material to a depth of not less than 30 cm. 100mm thick gravel bedding shall be used as foundation or otherwise as specified.

## PIPE LAYING

The pipe shall be tested for water-tightness of joints before backfilling the trench. Unsatisfactory work shall be corrected without additional cost to the PPA. The collar shall have set sufficiently prior to backfilling.

## LATERAL DRAIN

Concrete cover and the existing steel gratings shall be set to the required elevations as shown on the drawings to fit the adjoining surfaces and shall be installed after the adjoining concrete is struck off and finished, and the fit on the frames shall be such that there is no rocking.

All completed structures shall be thoroughly cleaned of any accumulations of silts, debris or foreign matter of any kind, until finally accepted and put into service.

## CATCH BASIN INLETS, MANHOLES AND OUTLETS

Lid frames shall be set to the required elevations as shown on the drawings to fit the adjoining surfaces. Lids shall be installed after the adjoining concrete is struck off and finished, and the fit on the frames shall be such that there is no rocking.

Where reconstruction of existing catch basin inlets, manholes, outlets, or similar structures are indicated, the work shall be in accordance to the details and elevations as shown on the drawings, including re-installation of existing metal frames, gratings and lids, or replacing of concrete covers instead of gratings that may have been lost or found lacking. All completed structures shall be thoroughly cleaned of any accumulations of silts, debris or foreign matter of any kind, until finally accepted and put into service.

## FIELD DENSITY TEST

Field Density tests to determine the percent of compaction of the fill material shall be conducted until a field density of at least 95 percent of the maximum dry density in accordance with AASHTO T180, Method D has been achieved. In place density determination shall be made in accordance with AASHTO T191.

## ITEM 17 : ELECTRICAL WORKS

### SCOPE OF WORK

The work to be done shall consist of fabricating, trenching, furnishing, delivering and installing electrical materials/fixtures completed in accordance with all the details of the electrical works as shown on the drawings including materials, labor, tools and equipment and all incidental works as found necessary.

Refer to electrical plans/drawings for location and extent of work involved.

### GENERAL REQUIREMENTS

- a) All works shall be done in accordance with the requirements of the publications and agencies having jurisdiction, as well as the requirements of the approved standards.
  1. National Fire Protection Association - (NFPA)
  2. National Electrical Manufacturer Association - (NEMA)
  3. Underwriter Laboratories, Inc. - (UL)
  4. Philippine Electrical Code - (PEC)  
Philippine National Standard - (PNS)
  5. Federation Specification:  
Circuit Breaker, Molded Case, Branch  
Circuit and Service
  6. American National Standard Institute - (ANSI)
  7. American Society for Testing and Materials - (ASTM)
  8. Illuminating Engineering Society - (IES)
  9. Light Emitting Diode - (LED)
- b) The electrical power shall be Integrated Solar LED Street Light.
- c) The Contractor shall employ a licensed Registered Electrical Engineer or Master electrician to perform or to supervise and to conduct the continuous inspection of all electrical work.
- d) The Contractor shall first obtain approval from the Authority before procurement, fabrication or delivery of electrical materials to the site. Partial submittals will not be acceptable and will be returned without review. Submittals shall include the Manufacturer's Name, Trade Name, Place of Manufacture, Catalog Model or Number, Nameplate Data, Size, Layout Dimensions, Capacity, Project Specification and Paragraph Reference, Technical Society Publication References and other information necessary to establish contract compliance of each item to be furnished.

- e) All excavations fill and backfill and concrete works involved herein, shall be carried to the required elevations and shall conform to the provisions of specification under Earthwork and Concrete Construction of this tender document.
- f) The materials and equipment to be furnished shall be standard products of reputable manufacturer engaged in the reproduction of such materials and equipment.
- g) All permits and electrical fees required for this work shall be obtained at the expense of the Contractor. The Contractor shall furnish the Engineer-in-Charge, the final Certificates of Inspections and approval from the proper government authorities after the completion of work. The Contractor shall prepare all as-built plans and all other paper works as required by the enforcing authorities.
- h) The Contractor shall furnish and install electrical materials as shown in the drawings. A licensed Electrical Engineer or Master Electrician is required to implement the installation of the electrical system. A licensed electrical contractor shall oversee/conduct the installation of the main circuit breaker.
- i) Electrical installation shall conform to the requirements of Philippine Electrical Code (PEC) and the other approved standards.
- j) The contractor shall install all electrical works with the supervision of the qualified Registered Electrical Engineer (REE) or Master Electrician. All electrical installation applications regardless of capacity and voltage whether new, addition or revision shall be accompanied by electrical plans signed and sealed by a duly licensed Professional Electrical Engineer (PEE).

## **MATERIAL REQUIREMENTS**

All materials shall be brand new and shall be of the approved type meeting all the requirements of the Philippine Electrical Code and bearing the Philippine Standard Agency (PSA) mark.

### **PRODUCTS**

#### **WIRES AND CABLES**

The conductor material to be furnished and installed shall be copper wire Heat-Resistant Thermoplastic (THHN/THWN-2). All conductors shall be rated 600 volts insulation and shall be standard for all sizes.

#### **CONDUIT AND FITTINGS**

Underground PVC conduit shall be polyvinyl chloride with concrete covered. It shall be manufactured to schedule 40 outside diameter. All fittings and bends shall be solvent bonded using manufacturers recommended product.

#### **70 WATT LED INTEGRATED SOLAR STREET LIGHT**

##### **Specifications:**

Solar Module Type	: 120W Monocrystalline
Service Life	: 25 years
Battery Type	: LIFE PO4 (Lithium Phosphate) 12.8V, 57AH
Service Life	: 6 years
Charge Time	: 6-8 HRS (Depending on Irradiation Levels)

Discharge Time	: 15 Hrs. Full Power / 30 Hrs. Half Power
LED Lamp	: 12V, 70 Watt
Lumens	: 10,000 – 10,800 lm
Viewing Angle	: 120 degrees
Service Life	: 50,000 Hrs. (11yrs 12 Hrs. Per/Night)
Working Temperature	: -30 C / 70 C
Colour	: 6500K – 7000K
Mounting Height	: 7-10 Meter
Distance	: 25 – 35 Meter
Warranty	: 3 years
Certificates	: CE /ROHS /IP65
Product Weight	: 27 Kg

#### STEEL TAPERED LAMP POST

Lamp Post shall be 10.0 m ht. steel tapered, furnished installed and tested as shown on the approved plans. The post/s shall be dimensioned for a wind velocity of 185 km/hr. It shall be locally fabricated or manufactured. The post shall be Hot –Dipped Galvanized, prime-coated with red lead and shall be painted at site with the final coating preferably aluminum paint to be approved by the Engineer.

#### EXECUTION

##### INSTALLATION

Lamp Post shall be installed as shown on the approved plans.

Pole Setting:       Depth as shown on the approved plans.

Construction of reinforced concrete lamp post foundation shall be in accordance with the shape and dimensions as shown on the approved plans.

Excavations / backfilling required before /after installation of lamp post with the trench shall conform to the provisions of Earthwork and Concrete construction.

##### WORKMANSHIP

The work throughout shall be executed in the best and most thorough manner under the direction of and at the satisfaction of the Registered Electrical Engineer or Master Electrician, who will interpret the intent meaning of the drawings and specification and shall have the power to reject any work and materials which in his judgment, are not in full accordance therewith.

##### TESTING OPERATIONS

When the electrical installation is completed, the Contractor shall test the installed electrical materials and equipment in the presence of Registered Electrical Engineer or Master Electrician. The system shall be free from any defects, shorts or grounds. The Contractor at no extra cost shall furnish all necessary instruments and personnel required for the testing.

## GUARANTEE

Upon completion and before final acceptance of the work, the Contractor shall furnish the Engineer a written guarantee stating that all works executed are free from defects on materials and workmanship. The guarantee shall be for a period of one year from the date of the final acceptance. Any work that becomes defective during the said period shall be corrected / replaced by the Contractor at his own expense in a manner satisfactory to the Authority.

---

**ITEM 18 : PROJECT BILLBOARD**


**SPECIFICATION**


The Project Billboard shall be installed at location(s) designated by the Engineer.

The size and specifications of materials for the standard billboard shall be 4ft. x 8ft. (1,200mm x 2,400mm) using ½ inch (12mm) marine plywood or tarpaulin poster on 3/16 inch (5mm) marine plywood.

Project billboards shall not contain Name(s) and/or picture(s) of any personages.

See attached drawings for further details of the standard billboard.





**BILLBOARD FRAME**

(NOT TO SCALE, ALL DIMENSIONS ARE IN MILLIMETERS)

## ITEM 19 : SAFETY SIGNAGES AND BARRICADES

### DESCRIPTION

This work includes the furnishing and installing of safety signages and barricades in accordance with the specifications and to the details shown below in the drawings, or as directed by the Engineer.


### SPECIFICATION

The Signage's and Barricades shall be installed at location(s) designated by the Engineer.

The sizes of the standard signages shall be 2-2/3ft x 4ft (800mm X 1,200mm) for fixed type and 2ft x 2-2/3ft (600mm x 800mm) for mobile type. For barricade standard 2ft x 2-2/3ft (600mm x 800mm) shall be provided.

The materials to be used for signages and barricades are ½ inch (12mm) marine plywood or tarpaulin poster on 2" x 2" (50mm x 50mm) good lumber frame (see drawing below).

The printing or painting shall be the discretion of the Engineer.



## STANDARD PLAN FOR SIGNAGES AND BARRICADES

**SECTION VII**

**PROJECT DRAWINGS**

## SECTION VII

# PROJECT DRAWINGS (SEE ISSUED APPROVED PLANS)

### LIST OF DRAWINGS:

01 of 43	Vicinity Map, Development Plan, General Notes, List of Drawings
02 of 43	General Plan
03 of 43	Paving Plan
04 of 43	Drainage Layout Plan
05 of 43	Section A-A, Section B-B
06 of 43	Section C-C, Section D-D
07 of 43	Section E-E, Section F-F
08 of 43	Section G-G, Section H-H
09 of 43	Section I-I, Section J-J
10 of 43	Section @ Sta. 0 + 010, Section @ Sta. 0 + 020, Section @ Sta. 0 + 030, Section @ Sta. 0 + 040, Section @ Sta. 0 + 050, Section @ Sta. 0 + 060
11 of 43	Section @ Sta. 0 + 070, Section @ Sta. 0 + 080, Section @ Sta. 0 + 090, Section @ Sta. 0 + 100, Section @ Sta. 0 + 110, Section @ Sta. 0 + 120
12 of 43	Section @ Sta. 0 + 130, Section @ Sta. 0 + 140, Section @ Sta. 0 + 150, Section @ Sta. 0 + 160, Section @ Sta. 0 + 170, Section @ Sta. 0 + 180
13 of 43	Section @ Sta. 0 + 190
14 of 43	Section @ Sta. 0 + 200
15 of 43	Section @ Sta. 0 + 210
16 of 43	Section @ Sta. 0 + 220
17 of 43	Section @ Sta. 0 + 230
18 of 43	Section @ Sta. 0 + 240
19 of 43	Section @ Sta. 0 + 250
20 of 43	Section K-K, Section L-L
21 of 43	Section M-M, Section N-N

22 of 43	Section O-O, Section P-P
23 of 43	Section Q-Q, Section R-R
24 of 43	Section S-S, Section T-T
25 of 43	General Plan (Proposed Wharf & Proposed Platform)
26 of 43	Piling Plan (Proposed Wharf), Pile Schedule (Proposed Wharf)
27 of 43	off-Shore Elevation (Proposed Wharf)
28 of 43	Piling Plan (Proposed Platform), Pile Schedule (Proposed Platform)
29 of 43	Typical Reinforcement of R.C. Deck (Proposed Wharf)
30 of 43	Typical Reinforcement of R.C. Deck (Proposed Platform)
31 of 43	Section Detail (Proposed Wharf)
32 of 43	Detail of Curtain Wall(Cw), Detail of Construction Joint, Typical Detail of Mooring and Fender Block
33 of 43	Section Detail (Proposed Platform)
34 of 43	Typical Detail of Pile Cap For Batter Piles (Proposed Wharf), Typical Detail of Pile Cap For Vertical Piles (Proposed Wharf)
35 of 43	Typical Section OF 700mm Ø X 13mm Thk. Tubular Steel Piles, Weld Preparation Dimensions, General Notes
36 of 43	Detail of Pre-Stress Concrete Pile (400 Mm X 400 Mm)
37 of 43	Detail of Hyper Omega Fender (Hom-1000h X 100) And Accessories
38 of 43	Detail of 100 Tons Mooring Bollard (Tee Head)
39 of 43	Typical Pavement Joint, Section Detail of Concrete Edging, Detail of R.C. Curb, Detail of Retaining Wall - 1, Detail of Retaining Wall - 2, Detail of Retaining Wall - 3, Detail of Outfall (Breather)
40 of 43	Detail of Steel Main Gate, Column Footing Detail of Steel Gate, Detail of Catch Drain Manhole Cover, Detail of Catch Drain Manhole
41 of 43	Detail of Fence
42 of 43	Port Lighting Layout, General Notes, Legend
43 of 43	Detail of Lamp Post Foundation, Integrated Solar Street Light, Specification

**SECTION VIII**

**BILL OF QUANTITIES**  
**and**  
**ATTACHMENTS**

**BILL OF QUANTITIES**  
**PROPOSED CONSTRUCTION OF CARGO SHIP PORT**  
Port of Jubang, Dapa, Surigao del Norte

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
<b>BILL NO. 1</b>	<b>GENERAL EXPENSES</b>				
1.01	Mobilization, demobilization and cleaning	lot	1		
1.02	Rental of temporary site office and residence for the Engineer and staff	mo.	22		
1.03	Maintain temporary site office and residence for the Engineer and staff	mo.	22		
1.04	Provide Construction Safety and Health Program in the execution of the project	mo.	22		
<b>TOTAL FOR BILL NO. 1</b>					<b>-</b>

**BILL OF QUANTITIES**  
**PROPOSED CONSTRUCTION OF CARGO SHIP PORT**  
Port of Jubang, Dapa, Surigao del Norte

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
<b>BILL NO. 2</b>	<b>CONSTRUCTION OF RC WHARF</b>				
2.01	Supply and deliver to site steel pipe piles (A252 Grade 2, 700mm Ø x13mm thk)	m.t	2,221		
2.02	Application of polyurethane external coating and mastic filler for steel pipe piles (Polyurethane : 32-10 @ 1,500 microns dry film thickness or equivalent)	sq.m.	2,464		
2.03	Splice steel pipe piles as directed by the engineer	no	280		
2.04	Supply and install 9mm thk reinforcing band tip for steel pipe piles	no	280		
2.05	Handle, pitch and drive steel pipe vertical piles (700mm x 13mm thk)	l.m	4,900		
2.06	Handle, pitch and drive steel pipe batter piles (700mm Ø x 13mm thk)	l.m.	5,180		
2.07	Extract clogged materials from steel pipe piles	cu.m.	1,312		
2.08	Supply and place 3,500 psi concrete filler for steel pipe piles	cu.m	1,999		
2.09	Supply and install reinforcing steel cage for steel pipe piles	kg	462,715		
2.10	Cutting of driven steel pipe piles up to cut-off elevation including turn-over to authority of excess piles	no.	280		
2.11	Supply and place 3,500 psi concrete for superstructure	cu.m.	1,529		
2.12	Supply and install steel reinforcements for superstructure	kg.	226,230		

**BILL OF QUANTITIES**  
**PROPOSED CONSTRUCTION OF CARGO SHIP PORT**  
Port of Jubang, Dapa, Surigao del Norte

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
2.13	Supply and deliver to site rubber dock fender (Hyper Omega Fender, HOM-1000H x 100) including accessories	set	12		
2.14	Install rubber dock fender (Hyper Omega Fender, HOM-1000H x 100)	set	12		
2.15	Supply and deliver to site mooring bollard (100T, T-head) including accessories	set	12		
2.16	Install mooring bollard (100T, T-head) including accessories	set	12		
2.17	Supply and install hot-dipped galvanized 100mm x 100mm x 10mm angle bar for construction joints including dowel bars	l.m.	147		
<b>TOTAL FOR BILL NO. 2</b>					-

**BILL OF QUANTITIES**  
**PROPOSED CONSTRUCTION OF CARGO SHIP PORT**  
Port of Jubang, Dapa, Surigao del Norte

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
<b>BILL NO. 3</b>	<b>CONSTRUCTION OF RC PLATFORM</b>				
3.01	Supply and deliver to site 0.40m x 0.40m PSC piles	l.m.	3,444		
3.02	Handle, pitch and drive 0.40m x 0.40m vertical PSC piles	l.m.	1,728		
3.03	Handle, pitch and drive 0.40m x 0.40m PSC batter piles	l.m.	1,716		
3.04	Chipping and cutting of driven PSC piles up to cut-off elevation including disposal of debris	no.	138		
3.05	Supply and place 3,500 psi concrete for superstructure	cu.m.	403		
3.06	Supply and install steel reinforcements for superstructure	kg.	61,794		
3.07	Supply and install hot-dipped galvanized 100mm x 100mm x 10mm angle bar for construction joints including dowel bars	l.m.	123		
<b>TOTAL FOR BILL NO. 3</b>					

**BILL OF QUANTITIES**  
**PROPOSED CONSTRUCTION OF CARGO SHIP PORT**  
Port of Jubang, Dapa, Surigao del Norte

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
<b>BILL NO. 4</b>	<b>CONSTRUCTION OF BACK-UP AREA</b>				
4.01	Supply and place 1000 kg rocks	cu.m.	3,234		
4.02	Supply and place 50-100 kg rocks	cu.m.	4,656		
4.03	Supply and place 3,500 psi concrete for retaining walls	cu.m.	553		
4.04	Supply and install steel reinforcement for retaining walls	kg	56,239		
4.05	Supply and install geotextile fabric	sq.m.	4,181		
4.06	Supply and place sand and gravel fill	cu.m.	27,061		
4.07	Supply, spread and compact selected fill materials	cu.m.	6,680		
4.08	Supply, spread and compact aggregate base course	cu.m.	1,088		
4.09	Construct concrete edging including steel reinforcement	sq.m.	178		
4.10	Supply, spread and compact 10% cement treated base course (150mm thk.)	cu.m.	1,061		
4.11	Supply and spread leveling sand cushion (50mm thk.)	cu.m.	354		
4.12	Supply and install Interlocking Concrete Blocks Pavement (100mm x 200mm x 125mm)	sq.m.	7,073		
<b>TOTAL FOR BILL NO. 4</b>					-

**BILL OF QUANTITIES**  
**PROPOSED CONSTRUCTION OF CARGO SHIP PORT**  
 Port of Jubang, Dapa, Surigao del Norte

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
<b>BILL NO. 5</b>	<b>CONSTRUCTION OF ACCESS ROAD WITH BACK-UP AREA</b>				
5.01	Supply and place 1000 kg rocks	cu.m.	3,732		
5.02	Supply and place 50-100 kg rocks	cu.m.	4,989		
5.03	Supply and place 3,500 psi concrete for retaining walls, rc curb, perimeter fence column and footings	cu.m.	652		
5.04	Supply and install steel reinforcements for retaining walls, rc curb, perimeter fence column and footings, and CHB	kg	62,226		
5.05	Supply and install geotextile fabric	sq.m.	4,907		
5.06	Supply and place sand and gravel fill	cu.m.	8,089		
5.07	Supply, spread and compact selected fill materials	cu.m.	6,852		
5.08	Supply, spread and compact aggregate base course	cu.m.	1,054		
5.09	Supply and place portland cement concrete pavement (PCCP, 250mm thk.)	sq.m.	5,269		
5.10	Construct CHB wall (150mm thk.) for perimeter fence	sq.m.	198		
5.11	Supply and place plain cement plaster finish for CHB wall and column	sq.m.	501		
5.12	Supply, fabricate and install various materials for cyclone wire mesh fence	sq.m.	665		
5.13	Supply and install 600mmØ RCP for drainage	l.m.	117		
5.14	Construct catch drain manhole including cover	no.	10		

**BILL OF QUANTITIES**  
**PROPOSED CONSTRUCTION OF CARGO SHIP PORT**  
Port of Jubang, Dapa, Surigao del Norte

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
5.15	Supply and place gravel bedding	cu.m.	90		
5.16	Scrape/cut and dispose existing materials	cu.m.	593		
5.17	Subgrade preparation	sq.m.	439		
5.18	Supply, fabricate and install various materials for steel gate	lot	1		
5.19	Supply and install 1000mmØ RCP for drainage	l.m.	72		
<b>TOTAL FOR BILL NO. 5</b>					-

**BILL OF QUANTITIES**  
**PROPOSED CONSTRUCTION OF CARGO SHIP PORT**  
Port of Jubang, Dapa, Surigao del Norte

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
<b>BILL NO. 6</b>	<b>PORT LIGHTING SYSTEM</b>				
6.01	Supply, deliver and install, single arm steel tapered lamp post, 10.00 mtrs. ht., hot dipped galvanized with 70 watt LED, integrated solar street light	set	21		
6.02	Construct street lamp post foundation	no.	21		
<b>TOTAL FOR BILL NO. 6</b>					-

**BILL OF QUANTITIES**  
**PROPOSED CONSTRUCTION OF CARGO SHIP PORT**  
Port of Jubang, Dapa, Surigao del Norte

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
<b>BILL NO. 7</b>	<b>REIMBURSABLE ITEMS</b>				
7.01	Provide reimbursable items necessary in the implementation of the project as determined by the Authority	lot	1	1,939,333.85	1,939,333.85
<b>TOTAL FOR BILL NO. 7</b>					<b>1,939,333.85</b>

## **BASIS OF PAYMENT FOR WORK ITEMS INCLUDED IN THE PROPOSAL**

The work items included in the proposal and the basis of payments are as follows:

### **BILL NO. 1**

#### **GENERAL EXPENSES**

**Item 1.01      Mobilization, demobilization and cleaning**

The quantity to be paid for shall be the minimum equipment requirement enumerated in the bid documents mobilized, demobilized and cleaning of the site and accepted by the Engineer. The contract lump sum price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to mobilize and demobilize all the minimum equipment requirement enumerated in the bid documents including cleaning of the site. Fifty percent (50%) of the total amount shall be payable after the mobilization activity while the remaining (50%) payable after demobilization and cleaning.

**Item 1.02      Rental of temporary site office and residence for the Engineer and staff**

The quantity to be paid for shall be the actual rental for temporary site office and residence for the engineer and staff and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary for the provision of temporary site office and residence for the engineer and staff at least 48.00 m<sup>2</sup>

**Item 1.03      Maintain temporary site office and residence for the Engineer and staff**

The quantity to be paid for shall be the actual services rendered in maintaining the site office and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the maintenance of the temporary site office and residence as well as other expenses such as provision for electric power, telephone bill, potable water supply, janitorial and security services.

**Item 1.04      Provide construction safety and Health Program in the execution of the project**

The quantity to be paid for shall be the actual implementation of construction safety and health program and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the implementation of the Construction Safety and Health Program, as required and approved by the Department of Labor and Employment (DOLE).

## BILL NO. 2

### CONSTRUCTION OF RC WHARF

**Item 2.01      Supply and deliver to site steel pipe piles (A252 Grade 2, 700mm Ø x 13mm thk.)**

The quantity to be paid for shall be the actual weight in metric tons of steel pipe piles (700mm dia. x 13mm thk., A252 Grade 2), supplied and delivered to site in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.02      Application of polyurethane external coating and mastic filler for steel pipe piles (Polyurethane: 32-10 @ 1,500 microns dry film thickness or equivalent)**

The quantity to be paid for shall be the actual area in square meter of polyurethane external coating and mastic filler (Polyurethane: 32-10 @ 1,500 microns dry film thickness or equivalent), applied on the steel pipe piles in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.03      Splice steel pipe piles as directed by the engineer**

The quantity to be paid for shall be the actual number of steel pipe piles, spliced as directed by the engineer, in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.04      Supply and install 9mm thk. reinforcing band tip for steel pipe piles**

The quantity to be paid for shall be the actual number of reinforcing band tip (9mm thk.), supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.05      Handle, pitch and drive steel pipe vertical piles (700mm Ø x 13mm thk.)**

The quantity to be paid for shall be the actual length in linear meter of steel pipe vertical piles (700mm Ø x 13mm thk.), handled, pitched and driven in accordance with the plans and specifications, measured from the tip of piles to cut-off elevation and accepted by the Engineers. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.06      Handle, pitch and drive steel pipe batter piles (700mm Ø x 13mm thk.)**

The quantity to be paid for shall be the actual length in linear meter of steel pipe batter piles (700mm Ø x 13mm thk.), handled, pitched and driven in accordance with the plans and specifications, measured from the tip of piles to cut-off elevation and accepted by the Engineers. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.07      Extract clogged materials from steel pipe piles**

The quantity to be paid for shall be the actual volume in cubic meter of clogged materials from the steel pipe piles, extracted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.08      Supply and place 3,500 psi concrete filler for steel pipe piles**

The quantity to be paid for shall be the actual volume in cubic meter of 3,500 psi concrete filler for steel pipe piles, supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.09      Supply and install reinforcing steel cage for steel pipe piles**

The quantity to be paid for shall be the actual weight in kilogram of reinforcing steel cage for steel pipe piles, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.10      Cutting of driven steel pipe piles up to cut-off elevation including turn-over to Authority of excess piles**

The quantity to be paid for shall be the actual number of steel pipe piles, cut-off to required elevation including turn-over to Authority of excess piles, in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.11      Supply and place 3,500 psi concrete for superstructure**

The quantity to be paid for shall be the actual volume in cubic meter of 3,500 psi concrete, supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.12      Supply and install steel reinforcements for superstructure**

The quantity to be paid for shall be the actual weight in kilogram of steel reinforcements, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.13      Supply and deliver to site rubber dock fender (Hyper Omega Fender, HOM-1000H x 100) including accessories**

The quantity to be paid for shall be the actual number in set of rubber dock fender (Hyper Omega Fender, HOM-1000H x 100) including accessories, supplied and delivered to site in accordance with the plans and specifications and accepted by the

Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.14      Install rubber dock fender (Hyper Omega Fender, HOM-1000H x 100)**

The quantity to be paid for shall be the actual number in set of rubber dock fenders (Hyper Omega Fender, HOM-1000H x 100), installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.15      Supply and deliver to site mooring bollard (100T, T-head) including accessories**

The quantity to be paid for shall be the actual number in set of mooring bollard (100T, T-head) including accessories, supplied and delivered to site in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.16      Install mooring bollard (100T, T-head) including accessories**

The quantity to be paid for shall be the actual number in set of mooring bollard (100T, T-head) including accessories, installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.17      Supply and install hot-dipped galvanized 100mm x 100mm x 10mm angle bar for construction joints including dowel bars**

The quantity to be paid for shall be the actual length in linear meter of hot-dipped galvanized angle bar (100mm x 100mm x 10mm) for construction joints including dowel bars, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

### BILL NO. 3

#### CONSTRUCTION OF RC PLATFORM

**Item 3.01      Supply and deliver to site .40m x .40m PSC piles**

The quantity to be paid for shall be the actual length in linear meter of .40m x .40m PSC piles, supplied and delivered to site in accordance with the plans and specifications, measured from the tip of piles to cut-off elevation and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete.

**Item 3.02      Handle, pitch and drive .40m x .40m vertical PSC piles**

The quantity to be paid for shall be the actual length in linear meter of .40m x .40m vertical PSC piles to be handled, pitched and driven in accordance with the plans and specifications, measured from the tip of piles to cut-off elevation and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete.

**Item 3.03      Handle, pitch and drive .40m x .40m PSC batter piles**

The quantity to be paid for shall be the actual length in linear meter of .40m x .40m PSC batter piles to be handled, pitched and driven in accordance with the plans and specifications, measured from the tip of piles to cut-off elevation and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete.

**Item 3.04      Chipping and cutting of driven PSC piles up to cut-off elevation including disposal of debris**

The quantity to be paid for shall be the actual number of driven PSC piles, chipped-off to cut-off elevation including disposal of debris in accordance with the plans and specifications and disposal of debris at the designated area and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 3.05      Supply and place 3,500 psi concrete for superstructure**

The quantity to be paid for shall be the actual volume in cubic meter of 3,500 psi concrete, supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 3.06      Supply and install steel reinforcements for superstructure**

The quantity to be paid for shall be the actual weight in kilogram of steel reinforcements, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 3.07      Supply and install hot-dipped galvanized 100mm x 100mm x 10mm angle bar for construction joints including dowel bars**

The quantity to be paid for shall be the actual length in linear meter of hot-dipped galvanized angle bar (100mm x 100mm x 10mm) for construction joints including dowel bars, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**BILL NO. 4**

**CONSTRUCTION OF BACK-UP AREA**

**Item 4.01      Supply and place 1000 kg. rocks**

The quantity to be paid for shall be the actual volume in cubic meter of 1000 kg. rocks, supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.02      Supply and place 50-100 kg. rocks**

The quantity to be paid for shall be the actual volume in cubic meter of 50-100 kg. rocks, supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.03      Supply and place 3,500 psi concrete for retaining walls**

The quantity to be paid for shall be the actual volume in cubic meter of 3,500 psi concrete for retaining walls, supplied, set-in-place and finished in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.04      Supply and install steel reinforcement for retaining walls**

The quantity to be paid for shall be the actual weight in kilogram of steel reinforcement for retaining walls, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.05      Supply and install geotextile fabric**

The quantity to be paid for shall be the actual area in square meter of geotextile filter fabric, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.06      Supply and place sand and gravel fill**

The quantity to be paid for shall be the actual volume in cubic meter of sand and gravel fill, supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. Hydrographic/Topographic Surveys before and after placing of sand and gravel fill shall be made to determine the actual elevations along the cross sections and the actual quantities for payment. Volume due to settlement as established using settlement plates shall also be considered for payment. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.07      Supply, spread and compact selected fill materials**

The quantity to be paid for shall be the actual volume in cubic meter of selected fill materials to be supplied, spread and compacted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.08      Supply, spread and compact aggregate base course**

The quantity to be paid for shall be the actual volume in cubic meter of aggregate base course to be supplied, spread and compacted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full

compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.09      Construct concrete edging including steel reinforcement**

The quantity to be paid for shall be the actual area in square meter of concrete edging including steel reinforcement, constructed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.10      Supply, spread and compact 10% cement treated base course (150mm thk.)**

The quantity to be paid for shall be the actual volume in cubic meter of 10% cement treated base course (150mm thk.) to be supplied, spread and compacted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.11      Supply and spread leveling sand cushion (50mm thk.)**

The quantity to be paid for shall be the actual volume in cubic meter of leveling sand cushion (50mm thk.), supplied and spread in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.12      Supply and install interlocking concrete blocks pavement (100mm x 200mm x 125mm)**

The quantity to be paid for shall be the actual area in square meter of interlocking concrete blocks pavement (100mm x 200mm x 125mm) to be supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**BILL NO. 5**

**CONSTRUCTION OF ACCESS ROAD WITH BACK-UP AREA**

**Item 5.01      Supply and place 1000 kg. rocks**

The quantity to be paid for shall be the actual volume in cubic meter of 1000 kg. rocks, supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 5.02      Supply and place 50-100 kg. rocks**

The quantity to be paid for shall be the actual volume in cubic meter of 50-100 kg. rocks, supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 5.03      Supply and place 3,500 psi concrete for retaining walls, rc curb, perimeter fence column and footings**

The quantity to be paid for shall be the actual volume in cubic meter of 3,500 psi concrete for retaining walls, rc curb, perimeter fence column and footings, supplied, set-in-place and finished in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 5.04      Supply and install steel reinforcement for retaining walls, rc curb, perimeter fence column and footings and CHB**

The quantity to be paid for shall be the actual weight in kilogram of steel reinforcement for retaining walls, rc curb, perimeter fence column and footings and CHB, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 5.05      Supply and install geotextile fabric**

The quantity to be paid for shall be the actual area in square meter of geotextile filter fabric, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 5.06      Supply and place sand and gravel fill**

The quantity to be paid for shall be the actual volume in cubic meter of sand and gravel fill, supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. Hydrographic/Topographic Surveys before and after placing of sand and gravel fill shall be made to determine the actual elevations along the cross sections and the actual quantities for payment. Volume due to settlement as established using settlement plates shall also be considered for payment. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 5.07      Supply, spread and compact selected fill materials**

The quantity to be paid for shall be the actual volume in cubic meter of selected fill materials to be supplied, spread and compacted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 5.08      Supply, spread and compact aggregate base course**

The quantity to be paid for shall be the actual volume in cubic meter of aggregate base course to be supplied, spread and compacted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 5.09      Supply and place portland cement concrete pavement (PCCP, 250mm thk.)**

The quantity to be paid for shall be the actual area in square meter of portland cement concrete pavement (PCCP, 250mm thk.), supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 5.10      Construct CHB wall (150mm thk.) for perimeter fence**

The quantity to be paid for shall be the actual area in square meter of CHB wall (150mm thk.) for perimeter fence, constructed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 5.11      Supply and place plain cement plaster finish for CHB wall and column**

The quantity to be paid for shall be the actual area in square meter of plain cement plaster finish and column, supplied and set-in place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 5.12      Supply, fabricate and install various materials for cyclone wire mesh fence**

The quantity to be paid for shall be the actual area in square meter of various materials for cyclone wire mesh fence, supplied, fabricated and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 5.13      Supply and install 600mmØ RCP for drainage**

The quantity to be paid for shall be the actual length in linear meter of 600mmØ RCP for drainage, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 5.14      Construct catch drain manhole including cover**

The quantity to be paid for shall be the actual number of catch drain manhole including cover, constructed in accordance with the plans and specifications and disposal of debris at the designated area and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 5.15      Supply and place gravel bedding**

The quantity to be paid for shall be the actual volume in cubic meter of gravel bedding, supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 5.16      Scrape/cut and dispose existing materials**

The quantity to be paid for shall be the actual volume in cubic meter of existing materials, scraped/cut off up to required elevation and disposed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 5.17      Subgrade preparation**

The quantity to be paid for shall be the actual area in square meter of subgrade preparation in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 5.18      Supply, fabricate and install various materials for steel gate**

The quantity to be paid for shall be the actual quantity of various materials for steel gate, supplied, fabricated and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 5.19      Supply and install 1000mmØ RCP for drainage**

The quantity to be paid for shall be the actual length in linear meter of 1000mmØ RCP for drainage, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**BILL NO. 6**

**PORT LIGHTING SYSTEM**

**Item 6.01      Supply, deliver and install single arm steel tapered lamp post, 10.00mtrs. ht., hot dipped galvanized with 70 watt LED, integrated solar street light**

The quantity to be paid for shall be the actual number in set of single arm steel tapered lamp post, 10.00mtrs. ht., hot dipped galvanized with 70 watt LED, integrated solar street light to be supplied, delivered and installed in accordance with the plans and specifications accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 6.02      Construct street lamp post foundation**

The quantity to be paid for shall be the actual number of street lamp post foundation, constructed in accordance with the plans and specifications accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

## **BILL NO. 7**

### **REIMBURSABLE ITEMS**

**Item 7.01      Provide reimbursable items necessary in the implementation of the project as determined by the Authority.**

The quantity to be paid for shall be the actual quantity of determined items by the Authority deemed necessary in the implementation of the project, supplied, delivered and accepted by the Authority. Payment for said items shall be made only upon complete delivery/acceptance of such. The contract lump sum price shall be full compensation for providing all determined items. The Contractor's Profit and Overhead, Contingencies and Miscellaneous (OCM) should not be included in the cost of said items. The amount of bid should be fixed as indicated in the amount stated in the Bid Data Sheet [ITB Clause 13.1(a)] and as provided in the Bill of Quantities (BOQ). Claims for payment shall be supported by Official Receipt(s) (OR) and at least three (3) canvasses. The amount to be paid for shall be the price indicated in the OR but should not exceed the contract lump sum price. The determined items shall be the property of PPA. Operation and maintenance shall be borne by PPA.

## **FACILITIES TO BE PROVIDED FOR THE ENGINEER & HIS STAFF**

### **TEMPORARY FACILITIES OF THE CONTRACTOR**

The Contractor shall provide and maintain such temporary offices, stores, workshops, latrines, housing and messing accommodations as are necessary. The location, dimension and layout of such buildings and places shall be subject to the approval in writing of the Engineer. By the end of the contract, the Contractor shall remove all buildings and the area shall be cleared and graded as required by the Engineer.

### **SITE OFFICE AND RESIDENCE FOR THE ENGINEER & STAFF**

The Contractor shall provide (**Rental**) and maintain a temporary site office and residence with an area of at least 48 square meters for use of the Engineer and staff, including all the necessary electricity, water, communication services and consumables.

**MINIMUM EQUIPMENT REQUIREMENTS**

1	unit	Crane Barge (319 GW, minimum) with 60T crane, owned
1	unit	Crane Barge (319 GW, minimum) with 60T crane, owned/leased
2	units	Crawler Crane (30T, minimum), owned
1	unit	Pile Hammer (Diesel, 10,500 kg.m.), owned
1	unit	Pile Hammer (Diesel, 7,500 kg.m.), owned
2	units	Drop Hammer (2T, minimum), owned/leased
1	unit	Clamshell, owned
2	units	Concrete Mixer (1-bagger, minimum), owned
2	units	Concrete Vibrator (3.5 hp, minimum), owned
1	unit	Concrete Cutter (5 hp, minimum), owned
1	unit	Forklift (1.36T), owned
2	units	Bar Cutter (electric, 25mm dia min.), owned
2	units	Bar Bender (electric, 25mm dia min.), owned
1	unit	Dump Truck (8 cu.m., minimum), owned
1	unit	Water Truck with pump (1,000 gal., minimum), owned
1	unit	Concrete Screeder, owned
1	unit	Centrifugal Trash Pumps (100mm, 16hp), owned
1	unit	Air-Compressor (250 cfm, minimum), owned
2	units	Suction Hose, 100mm, owned
2	units	Welding Machine (400 amp., minimum), owned
2	units	Oxy/Acetylene Cutting Outfit, owned
2	units	Tugboat (500hp, minimum), owned/leased
1	unit	Road Roller (12.05T, vibratory, minimum), owned/leased
1	unit	Road Grader (125 hp, minimum), owned/leased
1	unit	Payloader (1.06cu.m., 93 hp, minimum), owned/leased
1	unit	Backhoe (0.40 cu.m., 94.30 hp, minimum), owned/leased
1	unit	Concrete Bucket, owned/leased
2	units	Transit Mixer (5-6 cu.m. cap., minimum), owned/leased
2	units	Plate Compactor (5 hp, minimum), owned

## CONSTRUCTION SAFETY AND HEALTH REQUIREMENTS

The Contractor shall implement the construction safety and health program in accordance with the applicable provisions of the Occupational Safety and Health Standards (OSHS) of the Department of Labor and Employment (DOLE).

The Contractor, subject to the approval of the Engineer shall provide and maintain throughout the duration of the contract a medical room with at least 15 square meters together with all necessary supplies to be sited in the Contractor's main area.

The Contractor shall provide the following minimum requirements:

### LABOR

1	no.	Safety Engineer / Officer
1	no.	Nurse / Health Officer

### EQUIPMENT / MATERIALS

#### Personnel Protective Equipment

109	pcs.	Hard Hats
109	pcs.	Gloves
4	pcs.	Goggles
2	pcs.	Aprons
4	pcs.	Safety Belts
109	pcs.	Safety Shoes
4	pcs.	Life Lines

#### Safety Devices

1	lot	Barricades
1	lot	Warning signs
2	units	Fire extinguisher

Medical and First Aid System                      -                      For twenty-two (22) mos.

### NOTE:

The Contractor shall provide the above-cited minimum construction safety and health requirements or as required by the Engineer.

**SECTION IX**  
**BIDDING FORMS**

## Bid Form

Date: \_\_\_\_\_

ITB No: \_\_\_\_\_

To: **Philippine Ports Authority**  
Bonifacio Drive, South Harbor,  
Port Area, Manila

We, the undersigned, declare that:

- (a) We have examined and have no reservation to the Bidding Documents, including Addenda, for the Contract **Proposed Construction of Cargo Ship Port, Port of Jubang, Dapa, Surigao del Norte**;
- (b) We offer to execute the Works for this Contract in accordance with the Bid and Bid Data Sheet, General and Special Conditions of Contract accompanying this Bid;

The total price of our Bid, excluding any discounts offered below is:

BILL NO	DESCRIPTION	TOTAL AMOUNT
1	General Expenses	₱
2	Construction of RC Wharf	
3	Construction of RC Platform	
4	Construction of Back-up Area	
5	Construction of Access Road with Back-up Area	
6	Port Lighting System	
7	Reimbursable Items	
	<b>TOTAL AMOUNT OF BID (including VAT)</b>	<b>₱</b>

The discounts offered and the methodology for their application are: insert information;

- (c) Our Bid shall be valid for a period of 120 days from the date fixed for the Bid submission deadline in accordance with the Bidding Documents, and it shall remain binding upon us and may be accepted at any time before the expiration of that period;

- (d) If our Bid is accepted, we commit to obtain a Performance Security in the amount of *[insert percentage amount]* percent of the Contract Price for the due performance of the Contract;
- (e) Our firm, including any subcontractors or suppliers for any part of the Contract, have nationalities from the following eligible countries: *[insert information]*;
- (f) We are not participating, as Bidders, in more than one Bid in this bidding process, other than alternative offers in accordance with the Bidding Documents;
- (g) Our firm, its affiliates or subsidiaries, including any subcontractors or suppliers for any part of the Contract, has not been declared ineligible by the Funding Source;
- (h) We understand that this Bid, together with your written acceptance thereof included in your notification of award, shall constitute a binding contract between us, until a formal Contract is prepared and executed; and
- (i) We understand that you are not bound to accept the Lowest Calculated Bid or any other Bid that you may receive.
- (j) We likewise certify/confirm that the undersigned, is the duly authorized representative of the bidder, and granted full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for the **Proposed Construction of Cargo Ship Port, Port of Jubang, Dapa, Surigao del Norte** of the **Philippine Ports Authority**.
- (k) We acknowledge that failure to sign each and every page of this Bid Form, including the Bill of Quantities, shall be a ground for the rejection of our bid.

Name: \_\_\_\_\_

In the capacity of: \_\_\_\_\_

Signed: \_\_\_\_\_

Duly authorized to sign the Bid for and on behalf of: \_\_\_\_\_

Date: \_\_\_\_\_

**STATEMENT OF ALL ON-GOING GOVERNMENT AND PRIVATE CONTRACTS,  
INCLUDING CONTRACTS AWARDED BUT NOT YET STARTED, WHETHER SIMILAR OR NOT SIMILAR IN NATURE**

Name of the Contract or Title Of the Project 1]	Owner's Name and Address	Nature/ Scope of Work 2]	Contractor's Role (in percentage) 3]	Total Contract Value At		Date of Award 5]	Value of Outstanding Works	Estimated Time of Completion	% of Accomplishment		Contract Duration 5]	
				Award	Escalated Value to Present Prices 4]				Planned	Actual	Start	Completed
A) Government Contracts i. On-going ii. Awarded but not yet started B) Private Contracts i. On-going ii. Awarded but not yet started												

**NOTE:**

- 1] As appearing or defined in the contract entered/executed by the parties
- 2] With special reference to the Scope of Works as described/enumerated in the advertised Invitation To Bid.
- 3] Indicate whether as Sole Contractor, Sub-Contractor or Member in a Joint Venture / Consortium
- 4] Indicate the FOREX used if Contract Value is expressed in a currency other than the Philippine Peso. Specify the "Escalation Factor" used to escalate the Contract Value from completion date to the advertisement date of the Invitation to Bid per section 23.11.2 (3) of R.A. 9184.
- 5] State Month and Year.

This Statement shall be supported by:  
a) Notice of Award and/or Contract  
b) Notice to Proceed

\_\_\_\_\_  
Name of Firm/Applicant

\_\_\_\_\_  
Authorized Signing Official

\_\_\_\_\_  
Date

STATEMENT OF THE BIDDER'S SINGLE LARGEST COMPLETED CONTRACT (SLCC) SIMILAR TO THE CONTRACT TO BE BID

Name of the Contract or Title Of the Project	Owner's Name and Address	Nature/Scope of Work	Contractor's Role and Percentage Of Participation	Total Contract Value At		Date of Award	Value of Outstanding Works	Contract Duration	
				Award	Completion			Start	Completed

NOTE :

1. The prospective bidder must have completed an SLCC that is similar to the contract to be bid, and whose value, adjusted to current prices using the PSA consumer price indices, must be at least fifty percent (50%) of the ABC to be bid.
2. This Statement shall be supported by:

a. Notice of Award and / or Notice to Proceed.

b. Project Owner's Certificate of Final acceptance issued by the owner other than the Contractor or Constructors Performance Evaluation System (CPES) Final Rating, which must be at least satisfactory.

Name of Firm/Applicant

Authorized Signing Official

Date

## EXPERIENCE RECORD ON SIMILARLY COMPLETED PROJECTS

Similar Major Operations of Work 1]	Unit of Measure	Quantity	Title of the Project				Unit of Measure	Quantity
			Title of the Project	Title of the Project	Title of the Project	Title of the Project		
1. Off-shore Pile Driving of steel pipe piles	l.m.	5,040						
2. Off-shore Pile Driving of concrete piles	l.m.	1,722						
3. Reinforced Concrete Works	cu.m.	2,568						
4. Rock Works a) 1000 kg./pc. b) 50-100 kg./pc.	cu.m. cu.m.	3,483 4,823						
5. Fill Materials	cu.m.	24,341						
6. Construction of Portland Cement Concrete Pavement (PCCP)	sq.m.	2,635						
7. Construction of Interlocking Concrete Block Pavement (ICBP)	sq.m.	3,537						

NOTE: 1] Submit the Certificate of Completion/Certificate of Acceptance by the project owner, Final Recapitulation/Bill of Quantities and/or Constructor Performance Evaluation System (CPES) ratings, 1<sup>st</sup>, 2<sup>nd</sup> & Final visit (if applicable). Projects with no Certificate of Completion/Acceptance and Recapitulation/Bill of Quantities shall not be considered.

2] The Owner's Certificate of Final Acceptance; or the Constructors Performance Evaluation Summary (CPES) Final Rating and/or the Certificate of Completion, must be satisfactory.

Name of Firm/Applicant

Authorized Signing Official

Date

(Revised Form : September 2012)

## FINANCIAL DATA

- A. The prospective bidder's audited Financial Statements, showing, among others, the prospective bidder's total and current assets and liabilities, stamped "RECEIVED" by the Bureau of Internal Revenue (BIR), or its duly accredited and authorized institutions, for the preceding calendar year which should not be earlier than two (2) years from the date of bid submission.

	Year
1. Total Assets	
2. Current Assets	
3. Total Liabilities	
4. Current Liabilities	
5. Net worth (1-3)	
6. Net Working Capital (2-4)	

- B. The computation of the bidders Net Financial Contracting Capacity (NFCC) must be at least equal to the ABC to be bid, as follows:

NFCC = [ (Current assets minus current liabilities) (15) ] minus the value of all outstanding or uncompleted portions of the projects under ongoing contracts, including awarded contracts yet to be started coinciding with the contract to be bid.

NFCC = \_\_\_\_\_

Attached herewith are certified true copies of the audited financial statements stamped received by the BIR or BIR authorized collecting agent for the latest/immediately preceding calendar year.

\_\_\_\_\_  
Name of Firm/Applicant

\_\_\_\_\_  
Authorized Signing Official

Date: \_\_\_\_\_

### NOTES:

If Partnership or Joint Venture, each Partner or Member Firm of Joint venture shall submit separate financial statements.

## LIST OF CONTRACTOR'S PERSONNEL

I hereby declare that the following key personnel enumerated below, with attached resume/bio-data, including valid PRC License, for the various positions mentioned, are available for the project applied for:

Position of Key Personnel	Name	No. of Key Personnel	Similar Experience in the Position (Years) <sup>1)</sup>	Total Experience in the Position (Years)	Attachment(s)	Annex(es)
Project Manager					PRC License (CE Preferred) Complete Qualification and Experience Data Certificate of Commitment	Annex " " _
Project Engineer					PRC License (CE Preferred) Complete Qualification and Experience Data Certificate of Commitment	Annex " " _
Materials Engineer					PRC License (CE Preferred) Submit Valid and Renewed DPWH Certificate of Accreditation Submit Accreditation Identification Card as Materials Engineer Complete Qualification and Experience Data Certificate of Commitment	Annex " " _
Construction Safety and Health Officer					Certificate of Safety and Health Construction Related Course Issued by DOLE Accredited Trainings Complete Qualification and Experience Data Certificate of Commitment	Annex " " _
Foreman					Complete Qualification and Experience Data Certificate of Commitment	Annex " " _
Other Position(s)					Complete Qualification and Experience Data Certificate of Commitment	Annex " " _

NOTE: 1. Minimum qualification requirements: (work experience is similar in nature and complexity to the project to be bid with regard to Registration Particulars of the Contractor's License)

Project Manager - Five (5) years	Materials Engineer - One (1) year
Project Engineer - Three (3) years	Materials Engineer I - for projects costing up to 100M
Foreman - Five (5) years	Materials Engineer II - for projects costing more than 100M

Name of Firm/Applicant

Authorized Signing Official

Date

REVISED FORM (September 2012)

## LIST OF CONTRACTOR'S EQUIPMENT UNITS

I hereby declare that the following equipment listed below which are owned, leased or under purchase agreement are in good operating condition and are available for the duration of the project:

DESCRIPTION (Type, Model, Make)	No. of Unit(s)	Capacity Output 2]	Owned, Leased and/or under purchase agreement 1]	Submitted Proof of Ownership/Leased/ Purchase Agreement (Mark as Annex "A.....Z")	OTHER INFORMATIONS (As Applicable)				
					Manufacturer	Engine Serial No.	Chassis No./ Name of Vessel	Location	Status

1] Indicate if owned or leased as listed in the Checklist/Bidding Documents. For owned equipment, as required, submit proof of ownership (i.e. deed of sale, sales invoice, official receipt). For Water Truck, Dump Truck and Transit Mixer submit LTO Certificate of Registration and valid Official Receipt. For owned barge/tugboat, submit Marina Certificate of Ownership and valid Cargo Ship Safety Certificate. For newly purchased barge/tugboat, submit Deed of Sale together with an application for Marina Certificate of Ownership duly received/authenticated by Marina with corresponding valid Cargo Ship Safety Certificate. For leased equipment, submit duly notarized copy of lease contract together with a copy of the Marina Owner's (Lessor's) Certificate and valid Cargo Ship Safety Certificate.

2] The unit of each equipment shall be as indicated in the Checklist/Bidding Documents, i.e. GW (for crane barge), DWT (for deck barge and hopper barge), TON (for crane, road roller and drop hammer), kg.-m/blow (for diesel hammer), cu.m (for dump truck), hp. (for tugboat, road grader, bulldozer and concrete vibrator), cfm (for compressor), gal. (for water truck with pump), amp. (for welding machine), bagger (for concrete mixer).

Name of Firm/Applicant

Authorized Signing Official

Date

REVISED FORM (January 2011)

## OMNIBUS SWORN STATEMENT FOR SOLE PROPRIETORSHIP

REPUBLIC OF THE PHILIPPINES)  
CITY OF \_\_\_\_\_)SS

### AFFIDAVIT

I (Name), of legal age, (Civil Status), (Nationality), and residing at (Address), after having been duly sworn in accordance with law, do hereby depose and state that:

1. I am the sole proprietor or authorized representative of (Name of Bidder) with office address at \_\_\_\_\_;
2. As the owner and sole proprietor or authorized representative of (Name of Bidder), I have full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for (Name of Project) of the Philippine Ports Authority, (as shown in the attached duly notarized "Special Power of Attorney" for the authorized representative);
3. (Name of Bidder) is not "blacklisted" or barred from bidding by the Government of the Philippines or any of its agencies, offices, corporations, or Local Government Units, foreign government / foreign or international financing institution whose blacklisting rules have been recognized by the Government Procurement Policy Board;
4. Each of the documents submitted in satisfaction of the bidding requirements is an authentic copy of the original, complete, and all statements and information provided therein are true and correct;
5. (Name of Bidder) is authorizing the Head of the Procuring Entity or its duly authorized representative(s) to verify all the documents submitted;
6. The owner or sole proprietor is not related to the Head of Procuring Entity, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management office or the end – user unit, and the project consultants by consanguinity or affinity up to the third civil degree;
7. (Name of Bidder) complies with existing labor laws and standards; and
8. (Name of Bidder) is aware of and has undertaken the following responsibilities as a Bidder:
  - a) Carefully examine all of the Bidding Document;
  - b) Acknowledge all conditions, local or otherwise, affecting the implementation of the contract;
  - c) Made an estimate of the facilities available and needed for the contract to be bid, if any; and
  - d) Inquire or secure Supplemental / Bid Bulletin(s) issued for the *Proposed Construction of Cargo Ship Port, Port of Jubang, Dapa, Surigao del Norte*.

9. (Name of Bidder) did not give or pay directly or indirectly, any commission, amount, fee, or any form of consideration, pecuniary or otherwise, to any person or official, personnel or representative of the government in relation to any procurement project or activity.

IN WITNESS WHEREOF, I have hereunto set my hand this \_\_\_\_ day of \_\_\_\_ 20\_\_ at \_\_\_\_\_, Philippines.

\_\_\_\_\_  
Bidder's Representative / Authorized Signatory

**SUBSCRIBED AND SWORN** to before me this \_\_\_\_ day of [month] [year] at [place of execution], Philippines. Affiant/s is/are personally known to me and was/were identified by me through competent evidence of identity as defined in the 2004 Rules on Notarial Practice (A.M. No. 02-8-13-SC). Affiant/s exhibited to me his/her [insert type of government identification card used], with his/her photograph and signature appearing thereon, with no. \_\_\_\_\_ and his/her Community Tax Certificate No. \_\_\_\_\_ issued on \_\_\_\_ at \_\_\_\_\_.

Witness my hand and seal this \_\_\_\_ day of [month] [year].

**NAME OF NOTARY PUBLIC**

Serial No. of Commission \_\_\_\_\_

Notary Public for \_\_\_\_\_ until \_\_\_\_\_

Roll of Attorneys No. \_\_\_\_\_

PTR No. \_\_\_\_\_ [date issued], [place issued]

IBP No. \_\_\_\_\_ [date issued], [place issued]

Doc. No. \_\_\_\_\_

Page No. \_\_\_\_\_

Book No. \_\_\_\_\_

Series of \_\_\_\_\_

## OMNIBUS SWORN STATEMENT FOR PARTNERSHIP OR COOPERATIVE

REPUBLIC OF THE PHILIPPINES)  
CITY OF \_\_\_\_\_)SS

### A F F I D A V I T

I ( Name ), of legal age, ( Civil Status ), ( Nationality ), and residing at ( Address ), after having been duly sworn in accordance with law, do hereby depose and state that:

1. I am the duly authorized and designated representative of (Name of Bidder) with office address at ( Address );
2. I am granted full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for (Name of Project) of the Philippine Ports Authority, accompanied by the duly notarized Special Power of Attorney, Board/Partnership Resolution or Secretary's Certificate (whichever is applicable);
3. (Name of Bidder) is not "blacklisted" or barred from bidding by the Government of the Philippines or any of its agencies, offices, corporations, or Local Government Units, foreign government / foreign or international financing institution whose blacklisting rules have been recognized by the Government Procurement Policy Board;
4. Each of the documents submitted in satisfaction of the bidding requirements is an authentic copy of the original, complete, and all statements and information provided therein are true and correct;
5. (Name of Bidder) is authorizing the PPA General Manager or its duly authorized representative(s) to verify all the documents submitted;
6. None of the officers and members of (Name of Bidder) is related to the PPA General Manager, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management office or the end- user unit, and the project consultants by consanguinity or affinity up to the third civil degree;
7. (Name of Bidder) complies with existing labor laws and standards; and
8. (Bidder) is aware of and has undertaken the following responsibilities as a Bidder:
  - a) Carefully examine all of the Bidding Document;
  - b) Acknowledge all conditions, local or otherwise, affecting the implementation of the contract;
  - c) Made an estimate of the facilities available and needed for the contract to be bid, if any; and
  - d) Inquire or secure Supplemental / Bid Bulletin(s) issued for the *Proposed Construction of Cargo Ship Port, Port of Jubang, Dapa, Surigao del Norte*.

9. (Name of Bidder) did not give or pay directly or indirectly, any commission, amount, fee, or any form of consideration, pecuniary or otherwise, to any person or official, personnel or representative of the government in relation to any procurement project or activity.

IN WITNESS WHEREOF, I have hereunto set my hand this \_\_\_\_ day of \_\_\_\_ 20\_\_ at \_\_\_\_\_, Philippines.

\_\_\_\_\_  
Bidder's Representative / Authorized Signatory

**SUBSCRIBED AND SWORN** to before me this \_\_\_\_ day of [month] [year] at [place of execution], Philippines. Affiant/s is/are personally known to me and was/were identified by me through competent evidence of identity as defined in the 2004 Rules on Notarial Practice (A.M. No. 02-8-13-SC). Affiant/s exhibited to me his/her [insert type of government identification card used], with his/her photograph and signature appearing thereon, with no. \_\_\_\_\_ and his/her Community Tax Certificate No. \_\_\_\_\_ issued on \_\_\_\_ at \_\_\_\_\_.

Witness my hand and seal this \_\_\_\_ day of [month] [year].

**NAME OF NOTARY PUBLIC**

Serial No. of Commission \_\_\_\_\_

Notary Public for \_\_\_\_\_ until \_\_\_\_\_

Roll of Attorneys No. \_\_\_\_\_

PTR No. \_\_\_\_\_ [date issued], [place issued]

IBP No. \_\_\_\_\_ [date issued], [place issued]

Doc. No. \_\_\_\_\_

Page No. \_\_\_\_\_

Book No. \_\_\_\_\_

Series of \_\_\_\_\_

## OMNIBUS SWORN STATEMENT FOR CORPORATION OR JOINT VENTURE

REPUBLIC OF THE PHILIPPINES)  
CITY OF \_\_\_\_\_)SS

### AFFIDAVIT

I (Name), of legal age, (Civil Status), (Nationality), and residing at (Address), after having been duly sworn in accordance with law, do hereby depose and state that:

1. I am the duly authorized and designated representative of (Name of Bidder) with office address at \_\_\_\_\_;
2. I am granted full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for (Name of Project) of the Philippine Ports Authority, accompanied by the duly notarized Special Power of Attorney, Board Resolution or Secretary's Certificate;
3. (Name of Bidder) is not "blacklisted" or barred from bidding by the Government of the Philippines or any of its agencies, offices, corporations, or Local Government Units, foreign government / foreign or international financing institution whose blacklisting rules have been recognized by the Government Procurement Policy Board;
4. Each of the documents submitted in satisfaction of the bidding requirements is an authentic copy of the original, complete, and all statements and information provided therein are true and correct;
5. (Name of Bidder) is authorizing the PPA General Manager or its duly authorized representative(s) to verify all the documents submitted;
6. None of the officers, directors, and controlling stockholders of (Name of Bidder) is related to the PPA General Manager, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management office or the or end- user unit, and the project consultants by consanguinity or affinity up to the third civil degree;
7. (Name of Bidder) complies with existing labor laws and standards; and
8. (Name of Bidder) is aware of and has undertaken the following responsibilities as a Bidder:
  - a) Carefully examine all of the Bidding Document;
  - b) Acknowledge all conditions, local or otherwise, affecting the implementation of the contract;
  - c) Made an estimate of the facilities available and needed for the contract to be bid, if any; and
  - d) Inquire or secure Supplemental / Bid Bulletin(s) issued for the *Proposed Construction of Cargo Ship Port, Port of Jubang, Dapa, Surigao del Norte*.

9. (Name of Bidder) did not give or pay directly or indirectly, any commission, amount, fee, or any form of consideration, pecuniary or otherwise, to any person or official, personnel or representative of the government in relation to any procurement project or activity.

IN WITNESS WHEREOF, I have hereunto set my hand this \_\_\_\_ day of \_\_\_\_ 20\_\_ at \_\_\_\_\_, Philippines.

\_\_\_\_\_  
Bidder's Representative / Authorized Signatory

**SUBSCRIBED AND SWORN** to before me this \_\_\_\_ day of [month] [year] at [place of execution], Philippines. Affiant/s is/are personally known to me and was/were identified by me through competent evidence of identity as defined in the 2004 Rules on Notarial Practice (A.M. No. 02-8-13-SC). Affiant/s exhibited to me his/her [insert type of government identification card used], with his/her photograph and signature appearing thereon, with no. \_\_\_\_\_ and his/her Community Tax Certificate No. \_\_\_\_\_ issued on \_\_\_\_ at \_\_\_\_\_.

Witness my hand and seal this \_\_\_\_ day of [month] [year].

**NAME OF NOTARY PUBLIC**

Serial No. of Commission \_\_\_\_\_

Notary Public for \_\_\_\_\_ until \_\_\_\_\_

Roll of Attorneys No. \_\_\_\_\_

PTR No. \_\_\_\_\_ [date issued], [place issued]

IBP No. \_\_\_\_\_ [date issued], [place issued]

Doc. No. \_\_\_\_\_

Page No. \_\_\_\_\_

Book No. \_\_\_\_\_

Series of \_\_\_\_\_

REPUBLIC OF THE PHILIPPINES)  
CITY OF \_\_\_\_\_)S.S.

**BID-SECURING DECLARATION**  
Invitation to Bid No. \_\_\_\_\_

To : Philippine Ports Authority  
Bonifacio Drive, South Harbor,  
Port Area, manila

I, the undersigned, declare that:

1. I understand that, according to your conditions, bids must be supported by a Bid Security, which may be in the form of a Bid-Securing Declaration.
2. I/We accept that: (a) I/we will be automatically disqualified from bidding for any contract with any procuring entity for a period of two (2) years upon receipt of your Blacklisting Order; and, (b) I/we will pay the applicable fine provided under Section 6 of the Guidelines on the Use of Bid Securing Declaration, within fifteen (15) days from receipt of the written demand by procuring entity for the commission of acts resulting to the enforcement of the bid securing declaration under Sections 23.1 (b), 34.2, 40.1 and 69.1, except 69.1(f), of the IRR of RA 9184; without prejudice to other legal action the government may undertake:
3. I understand that this Bid-Securing Declaration shall cease to be valid on the following circumstances:
  - (a) Upon expiration of the bid validity period, or any extension thereof pursuant to your request;
  - (b) I am declared ineligible or post-disqualified upon receipt of your notice to such effect, and (i) I failed to timely file a request for reconsideration or (ii) I filed a waiver to avail of said right;
  - (c) I am declared as the bidder with the Lowest Calculated Responsive Bid, and I have furnished the performance security and signed the Contract.

IN WITNESS WHEREOF, I have hereunto set my hand this \_\_\_\_\_ day of \_\_\_\_\_ 20 \_\_\_\_ at \_\_\_\_\_, Philippines.

\_\_\_\_\_  
Name of Bidder's Authorized Representative  
(Signatory's Legal Capacity)  
AFFIANT

**SUBSCRIBED AND SWORN** to before me this \_\_\_\_ day of [month] [year] at [place of execution], Philippines. Affiant/s is/are personally known to me and was/were identified by me through competent evidence of identity as defined in the 2004 Rules on Notarial Practice (A.M. No. 02-8-13-SC). Affiant/s exhibited to me his/her [insert type of government identification card used], with his/her photograph and signature appearing thereon, with no. \_\_\_\_\_.

Witness my hand and seal this \_\_\_\_ day of [month] [year].

**NAME OF NOTARY PUBLIC**

Serial No. of Commission \_\_\_\_\_  
Notary Public for \_\_\_\_\_ until \_\_\_\_\_  
Roll of Attorneys No. \_\_\_\_\_  
PTR No. \_\_\_, [date issued], [place issued]  
IBP No. \_\_\_, [date issued], [place issued]  
Doc. No. \_\_\_\_  
Page No. \_\_\_\_  
Book No. \_\_\_\_  
Series of \_\_\_\_.

## CONSTRUCTION METHODOLOGY

Name of Project : \_\_\_\_\_  
Proposed Project Description : \_\_\_\_\_  
Location : \_\_\_\_\_

### MINIMUM SCOPE OF CONSTRUCTION METHODOLOGY

#### A. CONSTRUCTION OF RC WHARF (Area = 2,205.00 sq.m.)

1. Supply and drive A252 Grade 2, 700mmØ x 13mm thk. Steel Pipe Piles (2,221 m.t.-10,080 l.m.) including application of polyurethane external coating (2,464 sq.m.), splicing (280 pcs.), cutting (280 pcs.) and installation of reinforcing band tip (280 pcs)
2. Supply and place 3,500 psi concrete filler (1,999 cu.m.) and reinforcing steel cage (462,715 kgs of various sizes) for steel pipe piles including extraction of clogged materials (1,312 cu.m.)
3. Supply and place 3,500 psi concrete (1,525 cu.m.) and reinforcing steel bars (2226,230 kg of various sizes) for superstructure
4. Supply and install mooring bollard, 100 tons, T-head (12 sets), and RDF, Hyper Omega Fender (HOM-1000H x 100 – 12 sets)

#### B. CONSTRUCTION OF RC PLATFORM (Area = 945.00 sq.m.)

1. Supply and drive 400mm x 400mm PSC piles (3,444 l.m.), including chipping and cutting of newly driven piles up to required elevation (138 pcs), supply and place 3,500 psi reinforced concrete (403 cu.m.) steel bars (61,794 kg of various sizes) for superstructure

#### C. CONSTRUCTION OF BACK-UP AREA (Area = 7,350.00 sq.m.)

1. Construction of rock bulkhead (7,890 cu.m.), fill materials (33,741 cu.m.), reinforced concrete for retaining walls (553 cu.m. of concrete and 56,239 kg of reinforcing bars of various sizes)
2. Construction of interlocking concrete blocks pavement (7,073 sq.m.) and concrete edging (178 sq.m.), including aggregate base course (1,088 cu.m.), cement treated base course (1,061 cu.m.), and sand cushion (354 cu.m.)
3. Supply and install geotextile fabric (4,181 sq.m.)

#### D. CONSTRUCTION OF ACCESS ROAD WITH BACK-UP AREA (Area = 5,516.79 sq.m.)

1. Scrape/cut and dispose existing materials up to required elevation (593 cu.m.), including subgrade preparation (439 sq.m.)
2. Construction of rock bulkhead (8,721 cu.m.), fill materials (14,941 cu.m.), reinforced concrete for retaining walls, rc curb, zocalo walls, perimeter fence column, center island column and footings (652 cu.m. of concrete and 62,226 kg of reinforcing bars of various sizes), CHB wall for perimeter fence and center island (150mm thk. – 198 sq.m.), including plastering of CHB wall and column (501 sq.m.), cyclone wire mesh (665 sq.m.), and catch drain manhole (10 sets)

3. Construction of Portland Cement Concrete Pavement (PCCP, 250mm thk. – 5,269 sq.m.), including aggregate base course (1,054 cu.m.)
4. Supply and install geotextile fabric (4,907 sq.m.)
5. Supply and install 600mmØ RCP (117 l.m.), including gravel bedding (58.00 cu.m.)

**E. PORT LIGHTING SYSTEM**

1. Supply and installation of single arm lamp post, 10.00m ht., hot dipped galvanized (21 sets) with 70 watt, LED roadway fixtures (21 sets)

**NOTES:**

The narrative construction method will guide and familiarize the contractor and the PPA on how the project shall be carried out in accordance with the highest standard of workmanship.

The construction method shall be consistent with the Bar Chart / S-Curve Schedule, Equipment Schedule and Manpower Schedule.

\_\_\_\_\_  
Signature  
(Authorized Signing Official)

## MANPOWER SCHEDULE

Name of Project : \_\_\_\_\_

Proposed Project Description : \_\_\_\_\_

Location : \_\_\_\_\_

<b>MANPOWER (Minimum)</b>	<b>CONTRACT DURATION ( _____ Calendar Days)</b>																					
	<b>M O N T H L Y</b>																					
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22
Project Manager																						
Project Engineer																						
Materials Engineer																						
Construction Safety and Health Officer																						
Foreman																						
Specify other applicable positions, ie.:																						
- Carpenter																						
- Steelman																						
- Mason																						
- Electrician																						
- Rigger																						
- Others																						

\_\_\_\_\_  
Signature  
(Authorized Signing Official)

### EQUIPMENT UTILIZATION SCHEDULE

**Name of Project :** \_\_\_\_\_

**Proposed Project Description :** \_\_\_\_\_

Location \_\_\_\_\_

[illegible]

Signature  
(Authorized Signing Official)

## CASHFLOW BY QUARTER AND PAYMENT SCHEDULE

Name of Project: \_\_\_\_\_

Proposed Project Description: \_\_\_\_\_

Location: \_\_\_\_\_

Project Duration (days or months)	Payment Schedule (Monthly, in Pesos)	Cash flow (Quarterly, in Pesos)
<b>TOTAL</b>		

### NOTES

- The cash flow by quarter and payment schedule should be consistent with the Bar Chart and S-curb.
- Advance payment should be specified if contractor wants to avail.
- Payment schedule shall not be more than once a month.

\_\_\_\_\_  
Signature  
(Authorized Signing Official)

**SECTION X**

**CONTRACT FORM**

Republic of the Philippines  
**PHILIPPINE PORTS AUTHORITY**  
PPA Building, Bonifacio Drive, South Harbor,  
Port Area, Manila, Philippines

**C O N T R A C T**  
**FOR THE PROPOSED CONSTRUCTION OF CARGO SHIP PORT**  
**PORT OF JUBANG, DAPA, SURIGAO DEL NORTE**

KNOW ALL MEN BY THESE PRESENTS:

This Contract, made and entered into this \_\_\_\_\_ day of \_\_\_\_\_ 20\_\_\_\_, in Manila, Philippines, by and between:

**PHILIPPINE PORTS AUTHORITY**, a government instrumentality created under Presidential Decree No. 857, as amended, with principal office at PPA Building, Bonifacio Drive, South Harbor, Port Area, Manila, represented herein by its duly authorized General Manager, **JAY DANIEL R. SANTIAGO**, and hereinafter referred to as "**PPA**";

- and -

\_\_\_\_\_, a corporation duly organized and existing in accordance with Philippine laws, with office and business address \_\_\_\_\_, represented in this act by \_\_\_\_\_, duly authorized for this purpose, as evidenced by Secretary's Certificate \_\_\_\_\_, a copy of which is hereto attached and made an integral part hereof as Annex "A", and hereinafter referred to as "**CONTRACTOR**"

**W I T N E S S E T H:**

WHEREAS, in accordance with Republic Act No. 9184 and its Implementing Rules and Regulations, PPA advertised and published in a newspaper of general circulation and posted on the PPA website and G-EPS as well as in its bulletin board, an Invitation to Bid for the *Proposed Construction of Cargo Ship Port, Port of Jubang, Dapa, Surigao del Norte*;

WHEREAS, the **CONTRACTOR** and other prospective bidders submitted their respective bids for the foregoing project;

WHEREAS, after the opening of bids on \_\_\_\_\_, and the conduct of bid evaluation and required post-qualification, the bid submitted by the **CONTRACTOR** at its unit and lump sum prices set forth in its proposal was found to be the Lowest Calculated Responsive Bid in the amount of \_\_\_\_\_ (P \_\_\_\_\_), Philippine Currency;

WHEREAS, pursuant to Head Office BAC Resolution No. \_\_\_\_\_ Series of \_\_\_\_\_, award of the contract was made to the **CONTRACTOR** in a Notice of Award dated \_\_\_\_\_, in the amount of \_\_\_\_\_ (P \_\_\_\_\_), after submission of the required documents within the prescribed period and compliance to the conditions stipulated in the IRR;

WHEREAS, the **CONTRACTOR** duly accepted the award by signing its Conforme on the said Notice of Award;

NOW, THEREFORE, for and in consideration of the foregoing premises and the mutual covenants, stipulations and agreements herein contained, the PPA and the **CONTRACTOR** have agreed, as they do hereby agree, and contract as follows:

## ARTICLE I

### CONTRACT DOCUMENTS

1.01 The following documents shall constitute integral parts of this Contract, as fully as if the contents of the said documents are reproduced, incorporated and set forth herein, and shall govern and control in full force and effect the rights and obligations of the Parties, except as otherwise modified by the terms and conditions of this Contract, or by mutual agreement in writing of both parties, to wit

- a. Contract Agreement
- b. Bidding Documents
- c. Winning bidder's bid, including the Eligibility requirements, Technical and Financial Proposals and all other documents / statements submitted
- d. Performance Security
- e. Notice of Award of Contract; and
- f. Other contract documents that may be required by existing laws and the PPA such as:
  - (1) Construction Schedule and S-Curve
  - (2) Manpower Schedule
  - (3) Construction Methods
  - (4) Equipment Utilization Schedule
  - (5) Construction Safety and Health Program approved by the DOLE
  - (6) Pert / CPM
  - (7) Duly Approved Program of Work and Cost Estimates
  - (8) Certificate of Availability of Funds
  - (9) Abstract of Bids
  - (10) Resolution of Award

1.02 All Contract documents are and shall remain as the property of the PPA.

1.03 The words and expressions in this Contract shall have the same meanings respectively assigned to them in the Contract Documents referred to above.

## ARTICLE II

### CONTRACTOR'S UNDERTAKING SCOPE OF WORK

2.01 The CONTRACTOR, in consideration of the payment to be made by the PPA to the CONTRACTOR, as stated in the Contract Documents and this Contract, the latter hereby covenants to execute and complete the *Proposed Construction of Cargo Ship Port, Port of Jubang, Dapa, Surigao del Norte*; in conformity in all respects with the provisions of this Contract, as follows:

=====	
ITEMS	TOTAL AMOUNT
=====	
1. General Expenses	P
2. Construction of RC Wharf	P
3. Construction of RC Platform	P
4. Construction of Back-up Area	P
5. Construction of Access Road with Back-up Area	P
6. Port Lighting System	P
7. Reimbursable Items	P
TOTAL AMOUNT	P

2.02 The CONTRACTOR agrees to commence, perform and complete the work called for and defined in this Contract at its sole cost and expense, and to fully and faithfully furnish all materials, tools, labor supplies, equipment, services and superintendence for the implementation of this Contract in accordance with the schedule in the Contract Documents forming integral parts of this Contract.

2.03 The CONTRACTOR guarantees, among others, that all tools, equipment, machineries, instruments, accessories and materials it will supply or deliver or install and/or use in the construction and workmanship of all his work under the Contract, shall be brand new and in accordance with the Contract Documents.

2.04 The CONTRACTOR recognizes the position of trust and confidence reposed in it under this Contract, and agrees to perform its obligations hereunder in the most efficient and competent manner, use its skill and good judgment, always set in good faith, and carry out the execution of this Contract in the most sound, expeditious and economical manner consistent with the interest of the PPA.

### ARTICLE III

#### CONSIDERATION

3.01 For and in consideration of the full, satisfactory and faithful performance by the CONTRACTOR of all its undertakings defined in and provided for under this Contract and Contract Documents, the PPA agrees to pay the CONTRACTOR the total amount not exceeding (P \_\_\_\_\_),

Philippine Currency, inclusive of the 12% value added tax, payment to be made and computed on the basis of final quantities at the unit bid price for each item of work actually performed and finished for each pay item as determined and accepted by PPA and in the manner set forth in the Contract Documents, as full compensation for everything furnished and done by the CONTRACTOR under this Contract, including all works required but not specifically mentioned, and also for all losses and damages to the CONTRACTOR arising out of the work aforesaid, from the action of the elements, or from any obstruction or difficulty encountered in the prosecution of this Contract, for all expenses incurred by or in consequence of the suspension or discontinuance of the contract herein specified and for faithfully completing the contract and the whole thereof, at the time and in the manner provided in the Contract Documents.

It is agreed and understood that all bid prices specified in this contract shall be considered as fixed prices, and therefore not subject to price adjustment and escalation during the contract implementation, except under extraordinary circumstances and upon prior approval of the Government Procurement Policy Board (GPPB) or when a Treaty or International or Executive Agreement Expressly allows it. Any request for price escalation under extraordinary circumstances shall be submitted by PPA to the National Economic and Development Authority (NEDA). Extraordinary circumstances shall refer to events that may be determined by the NEDA in accordance with the Civil Code of the Philippines and upon recommendation of the PPA.

3.02 Final and full payment of the consideration herein above-mentioned shall be upon full completion of the project and fulfillment by the CONTRACTOR of all the terms and conditions set forth in this Contract.

However, it is agreed that no payment or payments made under this Contract, except the final payment upon issuance of Certificate of Completion and Acceptance, shall be understood as performance of this Contract, either wholly or in part, and no payment shall be construed to be an acceptance of defective work or improper implementation thereof.

3.03 Any payment due and payable to the CONTRACTOR may be set off against liquidated damages payable to the PPA by the CONTRACTOR under this Contract.

3.04 It is likewise understood that the CONTRACTOR shall show proof evidencing payments by the CONTRACTOR of labor, materials, supplies, insurance premiums, etc., used in the work, before any payment is made to it.

For this purpose, the CONTRACTOR shall, before payment is made on the works accomplished, submit an affidavit certifying to the fact of payments of said labor, materials, supplies, equipment, insurance premiums, etc.

3.05 All payments shall be subject to existing government accounting and auditing rules and regulations.

3.06 The PPA shall, upon written request of the contractor which shall be submitted as a contract document, make an advance payment to the contractor in an amount not exceeding fifteen percent (15%) of the total contract price, to be made in lump sum or, at the most, two installments according to a schedule specified in the Bidding Documents.

3.07 The advance payment shall be made only upon the submission to and acceptance by the procuring entity of an irrevocable standby letter of credit of equivalent value issued by a Universal or Commercial Bank.

3.08 The advance payment shall be repaid by the contractor by deducting fifteen percent (15%) from his periodic progress payments a percentage equal to the percentage of the total contract price used for the advance payment.

The contractor may reduce his standby letter of credit by the amounts refunded by the Monthly Certificates in the advance payments.

3.09 Progress payments are subject to retention of ten percent (10%) referred to as the "retention money". Such retention shall be based on the total amount due to the contractor prior to any deduction and shall be retained from every progress payment until fifty percent (50%) of the value of works, as determined by the PPA are completed. If, after fifty percent (50%) completion, the work is satisfactorily done and on schedule, no additional retention shall be made; otherwise, the ten percent (10%) retention shall be imposed.

3.10 The total "retention money" shall be due for release upon final acceptance of the works. The CONTRACTOR may, however, request for the substitution of the retention money for each progress billing with irrevocable standby letters of credit from a Universal or Commercial Bank, of amounts equivalent to the retention money substituted for and acceptable to PPA, provided that the project is on schedule and is satisfactorily undertaken. Otherwise, the ten percent (10%) retention shall be made. Said irrevocable standby letters of credit to be posted in favor of PPA shall be valid for a duration to be determined by PPA and will answer for the purpose for which the ten percent (10%) retention is intended, i.e., to cover uncorrected discovered defects and third party liabilities.

#### ARTICLE IV

##### PERFORMANCE SECURITY

4.01 To guarantee the faithful performance of the CONTRACTOR of its obligations under this Contract, it shall post prior to the signing of the Contract a performance security in the form of irrevocable letter of credit issued by a Universal or Commercial Bank, and acceptable to PPA or a combination thereof as may be required by PPA, in accordance with the following schedule:

- |    |  |   |
|----|--|---|
| a. | Irrevocable, letter of credit issued by a Universal or Commercial Bank | - Ten Percent (10%) of the total contract price                           |
| b. | any combination of the foregoing                                       | - Proportionate to share of form with respect to total amount of security |

4.02 This performance security shall be denominated in Philippine Pesos and posted in favor of PPA, and shall be forfeited in favor of PPA in the event it is established that the CONTRACTOR is in default in any of its obligations under this Contract.

4.03 Subject to the conditions of the Contract, the performance security may be released by PPA after the issuance of the Certificate of Acceptance of the project, provided that PPA has no claims filed against the CONTRACTOR or the surety company and there are no claims for labor and materials filed against the contractor.

4.04 The CONTRACTOR shall post an additional performance security following the schedule above to cover any cumulative increase of more than ten percent (10%) over the original value of the contract as a result of amendments to order or change orders, extra work orders and supplemental agreements as the case may be. The CONTRACTOR shall cause the extension of the validity of the performance security to cover approved contract time extensions.

4.05 In case of a reduction in the contract value or for partially completed works under this contract which are usable and accepted by PPA, and the use of which in the judgment of PPA shall not affect the structural integrity of the entire project, PPA may allow a proportional reduction in the original performance security, provided that any such reduction is more than ten percent (10%) and that the aggregate of such reductions is not more than fifty percent (50%) of the original performance security.

## ARTICLE V

### COMPLETION TIME: LIQUIDATED DAMAGES

5.01 The CONTRACTOR agrees and obligates itself to perform and complete all works provided for in this Contract within \_\_\_\_\_ calendar days (including Sundays and Holidays), reckoned not later than seven (7) calendar days from issuance of the Notice to Proceed. Notice to Proceed shall be issued after this Contract has been signed by the Parties hereof.

5.02 Time is of the essence of this Contract. Should the CONTRACTOR refuse or fail to satisfactorily complete the work within the specified contract time, plus any time extension duly granted and is hereby in default under the contract, the CONTRACTOR shall pay the PPA for liquidated damages, and not by way of penalty, an amount as provided in the conditions of contract, equal to at least one-tenth (1/10) of one (1) percent of the cost of the unperformed portion of the works for everyday of delay.

5.03 The project or a portion thereof may be deemed usable when it starts to provide the desired benefits as certified by the Facilities Construction and Maintenance Department of PPA.

5.04 It is understood that the damages herein provided are fixed and agreed liquidated damages and to be entitled to such damages, PPA does not have to prove that it has incurred actual damages. Such amount shall be deducted from any money due or which may become due the CONTRACTOR under the contract and/or collect such liquidated damages from the retention money or other securities posted by the CONTRACTOR, whichever is convenient to PPA.

5.05 In case that the delay in the completion of the work exceed a time duration equivalent to ten percent (10%) of the specified contract time plus any time extension duly granted to the CONTRACTOR, PPA may rescind the contract, forfeit the CONTRACTOR's performance security and take over the prosecution of the project or award the same to a qualified contractor through negotiated contract.

5.06 In no case, however, shall the total sum of liquidated damages exceed ten percent (10%) of the total contract price, in which event the contract shall automatically be taken over by PPA or award the same to a qualified contractor through negotiation and the erring CONTRACTOR's performance security shall be forfeited. The amount of the forfeited performance security shall be aside from the amount of the liquidated damages that the CONTRACTOR shall pay PPA under Section 5.02 hereof and impose other appropriate sanctions.

## ARTICLE VI

### EXTENSION OF CONTRACT TIME

6.01 Should the amount of additional work of any kind or other special circumstances of any kind whatsoever occur such as to fairly entitle the CONTRACTOR to an extension of contract time, PPA shall determine the amount of such extension; provided that PPA is not bound to take into account any claim for an extension of time unless the contractor has prior to the expiration of the contract time and within thirty (30) calendar days after such work has been commenced or after the circumstances leading to such claim have arisen, delivered to PPA notices in order that it could have investigated them at that time. Failure to provide such notice shall constitute a waiver by the CONTRACTOR of any claim. Upon receipt of full and detailed particulars, PPA shall examine the facts and extent of the delay and shall extend the contract time for completing the contract work when, in PPA's opinion, the findings of facts justify an extension.

6.02 No extension of contract time shall be granted the CONTRACTOR due to (a) ordinary unfavorable weather conditions; and (b) inexcusable failure or negligence of CONTRACTOR to provide the required equipment, supplies or materials.

6.03 Extension of contract time may be granted only when the affected activities fall within the critical path of the PERT/CPM network.

6.04 No extension of contract time shall be granted when the reason given to support the request for extension was already considered in the determination of the original contract time during the conduct of detailed engineering and in the preparation of the contract documents as agreed upon by the parties before contract perfection.

6.05 Extension of contract time shall be granted for rainy/unworkable days considered unfavorable for the prosecution of the works at the site, based on the actual conditions obtained at the site, in excess of the number of rainy/unworkable days predetermined by the PPA in relation to the original contract time during the conduct of detailed engineering and in the preparation of the contract documents as agreed upon by the parties before contract perfection and/or for the equivalent period of delay due to major calamities such as exceptionally destructive typhoons, floods and earthquakes, and epidemics, and for causes such as non-delivery on time of materials, working drawings, or written information to be furnished by the PPA, non-acquisition of permit to enter private properties within the right-of-way resulting in complete paralization of construction activities, and other meritorious causes as determined by the PPA's authorized Engineer and approved by the PPA. Shortage of construction materials, general labor strikes, and peace and order problems that disrupt construction operations through no fault of the CONTRACTOR may be considered as additional grounds for extension of contract time provided they are publicly felt and certified by appropriate government agencies such as DTI, DOLE, DILG and DND, among others. The written consent of bondsmen must be attached to any request of the CONTRACTOR for extension of contract time and submitted to the PPA for consideration and that the validity of the performance security shall be correspondingly extended.

## ARTICLE VII

### ENTIRE CONTRACT

7.01 Provisions to the contrary notwithstanding, it is agreed that this is an entire contract for one whole complete work and that partial payments on account by the PPA or the use of parts of the work or equivalent shall not constitute an acceptance of any part of the work before its entire completion and final acceptance in writing by the PPA.

## ARTICLE VIII

### CONTRACTOR'S LIABILITY

8.01 The Parties, likewise, hereby agree that the employees of the CONTRACTOR are not employees of the PPA; hence, the PPA shall not in any way be liable or responsible for any personal injury or damages including death sustained or caused by any of the employees of the CONTRACTOR and/or his sub-contractor or agent or supplier whether or not occurring during the performance of their duties. The CONTRACTOR agrees and binds itself to indemnify the PPA for whatever injuries or damages caused or occasioned or contributed to by the failure, negligence or conduct of the CONTRACTOR and/or its employees, sub- contractors, agent and supplier or consultants arising out of or in connection with or on the occasion of the performance of this Contract. The CONTRACTOR shall, at all times, stand solely liable and/or responsible for the enforcement of, and compliance with all existing laws, rules and regulations and binds itself to save and hold the PPA free and harmless from any and all liability in respect thereof and/or arising therefrom and/or by reason of this Contract and its implementation.

## ARTICLE IX

### RESPONSIBILITY OF THE CONTRACTOR

9.01 The CONTRACTOR shall assume full responsibility for the entire contract work until its final acceptance by the PPA and shall be held responsible for any damage or destruction of works until such final acceptance.

9.02 The CONTRACTOR shall be fully responsible for the safety, protection, security and convenience of its personnel, third parties and the public at large, as well as the works, equipment, installation and the like to be affected by the construction work.

9.03 Any actionable act or acts of \_\_\_\_\_ arising out of or in the course of this Contract shall be understood and binding as an act of \_\_\_\_\_ and vice-versa.

## ARTICLE X

### INSPECTION AND CONSTRUCTION OF CONTRACT WORK

10.01 Inspection of the contract work shall be made by the PPA while such contract work is in progress to ascertain that the completed works or stages comply in all respects, with the standards and requirements set forth in the Contract Documents. Notwithstanding such inspection, the CONTRACTOR shall be held responsible for the acceptability of the finished works. The CONTRACTOR shall promptly correct all works determined by the PPA as failing to meet requirements, at CONTRACTOR's own expense.

## ARTICLE XI

### NON-ASSIGNMENT AND NO SUBCONTRACT

11.01 The CONTRACTOR shall not, without the written approval of the PPA, assign, transfer, pledge, sub-contract, or make any other disposition of interest in this Contract. Any unapproved assignment, transfer, pledge, sub-contract or any other disposition, shall be sufficient ground for the PPA to terminate or cancel this Contract **motu proprio** without need of judicial action pursuant to Section 19.04 hereof. Should the PPA give its written approval, such consent shall not relieve the CONTRACTOR of its responsibilities under the Contract. The CONTRACTOR shall ensure that the terms and conditions of any such sub-contract shall comply and conform with the terms and conditions of the Contract. The CONTRACTOR shall be responsible for the observance by any such sub-contractor of the terms and conditions of the Contract.

11.02 If any portion of the project sub-contracted is not prosecuted faithfully in accordance with the Contract, the sub-contractor shall be removed or replaced immediately upon the written request of the PPA, provided, however, that any failure of PPA to make such a request shall not relieve the CONTRACTOR of its obligations under the contract. PPA shall not be responsible for the delays or costs incurred by the CONTRACTOR because of the disapproval or removal of the sub-contractor or because of the late submittal of its or his approval.

## ARTICLE XII

### INSURANCE

12.01 The CONTRACTOR shall, prior to the commencement of work, secure the standard CONTRACTOR's all risk insurance (CARI) from the Government Service Insurance System (GSIS) or any insurance company duly certified by the Insurance Commission as authorized to issue such insurance, to insure the works against all losses or damages arising from whatever cause for which the CONTRACTOR is responsible under the Contract.

## ARTICLE XIII

### WARRANTY

13.01 The CONTRACTOR shall assume full responsibility for the contract work from the time project construction commenced up to final acceptance thereof by the PPA and shall be held responsible for any damage or destruction of the works, except those occasioned by force majeure. The CONTRACTOR shall be responsible for the safety, protection, security, and convenience of its personnel, third parties, and the public at large, as well as the works, equipment, installation and the like to be affected by the construction work.

13.02 The defect liability period for the project covered by this Contract shall be one (1) year from project completion up to final acceptance thereof by the PPA. During this period, the CONTRACTOR shall undertake and complete the repair works, at its own expense, of any damage to the said project within NINETY (90) DAYS from the time the PPA General Manager or his duly authorized representative has issued an order to undertake repair. In case of failure or refusal to comply with this order, PPA shall undertake such repair works and the CONTRACTOR shall fully reimburse the former for all the expenses incurred therein upon demand.

13.03 After final acceptance of the project by the PPA, the CONTRACTOR shall be responsible for structural defects and/or failure of the said project within the period of FIFTEEN (15) YEARS from the date of final acceptance thereof by the PPA. For this purpose, the CONTRACTOR shall put up a warranty security in the form of letter of credit issued by a Universal or Commercial Bank or Bank guarantee confirmed by a Universal or Commercial Bank and acceptable to PPA in accordance with the following schedule:

- |  |   |
|--|---|
| a. Letter of Credit issued by a<br>Universal or Commercial Bank  | - Five percent (5%) of the total contract price |
| b. Bank guarantee confirmed by a<br>Universal or Commercial Bank | - Ten percent (10%) of the total contract price |

The warranty security shall be denominated in Philippine Pesos, remain effective for one (1) year from the date of issuance of the Certificate of Final Acceptance by PPA and be returned only after the lapse of the said one (1) year period.

## ARTICLE XIV

### TAXES, LICENSES, PERMITS AND FEES

14.01 The CONTRACTOR's tax, licenses, permits, fees and all other taxes, fees or charges of whatever form, kind or nature due or which may be due to the national and/or local government units and/or its instrumentalities/agencies on account of the performance and completion of the work stipulated herein, fees for the testing of materials and samples and fees for the testing and inspection of the installation by all agencies having jurisdiction and all necessary and incidental expenses relative thereto including preparation of documents and notarial fees shall be paid for and obtained by the CONTRACTOR on its own account. Should the PPA be compelled to advance the same, PPA is hereby authorized to deduct the amount advanced from whatever amount due the CONTRACTOR from PPA.

14.02 The CONTRACTOR shall pay taxes in full and on time and that failure to do so shall entitle PPA to suspend payment to the CONTRACTOR. Further, the CONTRACTOR shall during the term of this Contract regularly present to PPA a tax clearance from the Bureau of Internal Revenue (BIR) as well as a copy of its income and business tax returns duly stamped and received by the BIR and duly validated with the tax payments made thereon.

## ARTICLE XV

### AGREEMENT MODIFICATION

15.01 No modification, alteration or waiver of any provision herein contained shall be binding on the Parties hereto unless evidenced by a written amendment signed by the parties hereof.

15.02 A variation order (change order/extra work order) may be issued by PPA under the conditions set forth in the applicable provisions of Republic Act No. 9184 and its Implementing Rules and Regulations.

15.03 The PPA may, at any time by written order and without notice to the Sureties, direct the CONTRACTOR to perform additional/extra work necessary to and within the General Scope of the project as bid and awarded. The CONTRACTOR shall be paid for additional/extra work items whose unit prices shall be derived based on the following:

- a. For additional/extra works duly covered by change orders involving work items which are exactly the same or similar to those in the original contract, the applicable unit prices of work items in the original contract shall be used.
- b. For additional/extra works duly covered by Extra Work Orders involving new work items that are not in the original contract, the unit prices of the new work items shall be based on the direct unit costs used in the original contract (e.g. unit cost of cement, rebars, form lumber, labor rate, equipment rental, etc.). All new components of the new work item shall be fixed prices, provided the same is acceptable to both PPA and the CONTRACTOR, and provided further that the direct unit costs of new components shall be based on the CONTRACTORS's estimate as validated by PPA via documented canvass in accordance with existing rules and regulations. The direct cost of the new work item shall then be combined with the mark-up factor (i.e., taxes and profit) used by the contractor in his bid to determine the unit price of the new work item.

15.04 Request for payment by the CONTRACTOR for any extra work shall be accompanied by a statement, with the approved supporting forms, giving a detailed accounting and record of amount for which he claims payment. Said request for payment shall be included with the CONTRACTOR's statement of progress payment.

## ARTICLE XVI

### SUSPENSION OF WORK

16.01 The PPA or its duly authorized representative shall have the authority to suspend the work wholly or partly by written order for such period as may be deemed necessary, due to force majeure or any fortuitous events or for failure on the part of the CONTRACTOR to correct bad conditions which are unsafe for workers or for the general public to carry out valid orders given by PPA or to perform any provisions of the Contract, or due to adjustment of plans to suit field conditions as found necessary during construction. The CONTRACTOR shall immediately comply with such order to suspend the work wholly or partly.

In case of total suspension, or suspension of activities along the critical path, which is not due to any fault of the CONTRACTOR, the elapsed time between the effective order of suspending operation and the order to resume work shall be allowed the CONTRACTOR by adjusting the contract time accordingly.

## ARTICLE XVII

### INDIVISIBILITY OF OBLIGATION

17.01 It is the intent of the Contract that all the documents, annexes and addenda forming part hereof, shall be read together and that each and every provision or stipulation hereof be given full force, effect and applicability. However, in the event that one or more provisions or stipulations herein be declared null and void by the courts, or otherwise rendered ineffective, the remaining provisions and stipulations shall not be affected thereby.

## ARTICLE XVIII

### ARBITRATION/REMEDY AND RELIEF

18.01 Should there be any dispute or difference of any kind whatsoever which shall arise between the parties in connection with the implementation of this Contract; the Parties hereto shall make every effort to resolve amicably such dispute or difference by mutual consultation. In the event that such dispute or disagreement be not resolved to their mutual satisfaction, the matter shall be submitted to arbitration in the Philippines according to the provisions of Republic Act No. 876, otherwise known as the "Arbitration Laws" and Republic Act No. 9285; otherwise known as the "Alternative Dispute Resolution Act of 2004". Provided, however, that disputes that are within the competence of the Construction Industry Arbitration Commission to resolve shall be submitted thereto. Provided, further, that, by mutual agreement, the parties hereto may agree in writing to resort to other alternative modes of dispute resolution. Provided, finally, that the arbitration proceeding shall be without prejudice to the right of PPA to rescind or terminate this contract in accordance with Article XIX, Section 19.04 hereof.

18.02 Should the PPA be constrained to resort to court action to enforce or safeguard its rights and interests under this Contract, the CONTRACTOR shall be liable to the PPA for attorney's fees in an amount equivalent to Twenty Percent (20%) of the total sum claimed in the complaint, exclusive of other damages and the expenses of litigation. Venue of all court actions in connection with or arising out of this contract shall be laid exclusively in the proper court of the City of Manila.

18.03 It is clearly understood that in case a dispute or disagreement arises between the PPA and the CONTRACTOR regarding the manner by which the latter is performing works, the CONTRACTOR shall follow the instruction of the PPA relative thereto, otherwise, it shall have no right to ask for arbitration or go to court for relief.

## ARTICLE XIX

### OTHER COVENANTS

19.01 It is expressly agreed and understood that in case of irreconcilable conflict between the provisions of this Contract and the provisions of any of the contract documents, the former shall be controlling.

19.02 It should also be clearly understood that any payment or failure of the PPA to demand compliance with any of the terms and conditions of this Contract or any act of liberality on the part of the PPA shall not be construed or considered as a waiver on the part of the PPA for the enforcement of this Contract, nor shall it relieve the CONTRACTOR of any of its obligations provided thereunder.

19.03 Under no circumstances shall the PPA be held liable for the payment of any extra work, or extra cost of work, change of work, or change order undertaken without the prior written approval of the PPA to perform said work.

19.04 Notwithstanding any provision to the contrary, the PPA has the right to terminate, cancel and/or rescind this Contract **motu proprio**, in case of breach thereof by the CONTRACTOR, without need of judicial action by giving at least TEN (10) Days written Notice to that effect to the CONTRACTOR, which Notice shall be final and binding on all the parties. In such event, the PPA may take over and continue the project, and the contracts and agreements entered into by the CONTRACTOR with third parties, which the PPA in its discretion, may want to assume are hereby conclusively deemed assigned to the PPA. For this purpose, the CONTRACTOR here agrees and obligates itself to incorporate or cause to be incorporated in any contract or agreement with third parties, as same is connected with or related to the performance of any or all of the CONTRACTOR's obligations and undertakings hereunder, a stipulation providing for its assignability to and assumption by the PPA, at the option of the PPA. It is further agreed and understood that upon receipt of the Notice mentioned above, the CONTRACTOR cannot remove, withdraw or pull-out any of the equipment, machineries, tools, materials, and/or supplies brought to the project site without the written approval of the PPA.

Within thirty (30) days after termination, cancellation or rescission of this Contract, the Parties shall settle their respective accountabilities as of the date of termination, cancellation or rescission, including the refund of any and all advances made plus legal interest from date of receipt of the amount or amounts advanced.

19.05 It is expressly agreed that whenever the CONTRACTOR is behind schedule in its contract work and incurs ten (10%) percent or more negative slippage based on its approved PERT/CPM, the PPA may undertake the whole or portion of the unfinished work by administration or by negotiation through another qualified CONTRACTOR.

Whenever a work activity in the project is not being done on schedule per approved PERT/CPM, the PPA shall notify and direct the CONTRACTOR to immediately undertake such work activity. If within fifteen (15) days from receipt of such notice, the CONTRACTOR fails to start work and to show a satisfactory performance, PPA may take over the whole or portion of such work and have such work done by administration or award the same to another qualified contractor through negotiated contract at the current valuation price.

19.06 The PPA has the right to require the CONTRACTOR to supply and provide the required tools, materials, supplies, equipment, facilities, and to increase the number of workers assigned to the work when exigencies of the service so require. Should the CONTRACTOR fail, refuse or neglect to comply with the same, PPA shall have the option to take over the project in whole or in part or award the same to another CONTRACTOR through negotiated contract at the current valuation price. Any increase in cost which the PPA may incur as a result of its take-over of the project pursuant to Sections 19.04, 19.05 and 19.06 shall be borne by and charged to the CONTRACTOR.

19.07 The CONTRACTOR shall provide and do everything necessary to perform its obligations under this Contract according to the true intent and meaning of all the Contract Documents taken together,

whether the same may or may not be shown or described particularly in the drawings, plans and specifications provided that the same can be inferred therefrom. Should the CONTRACTOR find discrepancy in the drawings, plans and specifications, it shall immediately refer the same to the PPA, whose decision shall be followed.

19.08 The CONTRACTOR agrees and obligates itself to restore to its original condition, on its own account, any public road, pavement, streets or open space and/or public or private property which are excavated or in any manner used by the CONTRACTOR in connection with the performance of its obligations under this Contract.

19.09 The CONTRACTOR agrees and binds itself to hold and save PPA free and harmless from any damage, claims and rights of action by third parties arising out of or by reason of this Contract and all injuries that may be suffered by PPA due to the failure, negligence, delay or conduct on the part of the CONTRACTOR and/or its employees in the performance of their obligations under this Contract.

19.10 No final payment of the contract shall be made to the CONTRACTOR without the Certificate of Completion and/or Acceptance from the Office of the Municipal Engineer of the Municipality concerned of the local works to be restored mentioned in Section 19.08 hereof, otherwise the cost of restoration shall be made available out of any collectible/receivable by the CONTRACTOR from the PPA.

19.11 Notwithstanding any extra work, change of work or orders made, if any, by the PPA, it is agreed that the same shall be completed within the period herein fixed and provided.

19.12 The CONTRACTOR shall hold the PPA free and harmless from whatever suit and hereby binds and obligates itself to indemnify the PPA for any and all liabilities, losses, damages, judgment, awards, fines, penalties and all expenses, legal or otherwise, of whatever kind and nature, arising from and by reason of this Contract, due to the fault, negligence, act, omission, delay, conduct, breach of trust or non-observance or violation of this Contract or any stipulation and warranty by the CONTRACTOR and/or any of its employees, agents, representatives or sub-contractors.

## ARTICLE XX

### SPECIAL REPRESENTATION

20.01 The CONTRACTOR hereby represents that all documents it submitted which form integral parts hereof are authentic and duly executed with all the required formalities for the same, and that the facts and/or date contained therein are true and correct. A breach of this representation including all misrepresentation in the documents or suppression of material facts therein, which if known, could have disqualified the CONTRACTOR such that this contract would not have been made and entered into, gives the PPA the immediate right or recourse to **motu proprio** rescind, abrogate or otherwise terminate the contract without need of judicial action, in accordance with Section 19.04 hereof.

20.02 The CONTRACTOR hereby warrants that it has not given nor promised to give any money, gift or any material favor/consideration to any official or employee of the PPA to secure this Contract; that any violation of this warranty shall be sufficient ground for the PPA to revoke or cancel this Contract extrajudicially or without need of judicial intervention.

## ARTICLE XXI

### BUDGETARY REQUIREMENT

21.01 The parties hereto hereby adopt and incorporate herein by reference, Letter of Instruction No. 767 dated 16 November 1978, issued by the Office of the President, as implemented by the Letter Circular, dated 7 December 1978, of the Department of Budget and Management.

ARTICLE XXII

EFFECTIVITY

22.01 This Contract shall become effective after the same shall have been signed by the Parties hereof.

IN WITNESS WHEREOF, the Parties have hereunto signed this Contract on the date and place first hereinabove written.

PHILIPPINE PORTS AUTHORITY

By:

By:

Jay Daniel R. Santiago  
General Manager

WITNESSES:

Adrian Ferdinand S. Sugay  
Chairperson Head Office Bids and Awards Committee

ACKNOWLEDGMENT

REPUBLIC OF THE PHILIPPINES)  
City of \_\_\_\_\_ ) S.S.

BEFORE ME, a Notary Public for and in the City of \_\_\_\_\_, this \_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_, personally appeared the following:

NAME	Proof of Identity	DATE	PLACE
Jay Daniel R. Santiago	_____	_____	_____
_____	_____	_____	_____

Known to me and to me known to be the same persons who executed the foregoing instrument as:

POSITION	COMPANY	CTC No.	DATE	PLACE
General Manager	Philippine Ports Authority	_____	_____	_____
_____	_____	_____	_____	_____

and they acknowledged to me that the same is their own free act and deed as well as the free and voluntary act of the corporation they represent.

This foregoing instrument is a Contract for *Proposed Construction of Cargo Ship Port, Port of Jubang, Dapa, Surigao del Norte*; consisting of 13 pages, including this page on which this acknowledgment is written, signed by the parties and their instrumental witnesses on each and every page thereof.

IN WITNESS WHEREOF, I have hereunto affixed my hand and notarial seal on these presents at the place and on the date first above written

Doc. No. \_\_\_\_\_;  
Page No. \_\_\_\_\_;  
Book No. \_\_\_\_\_;  
Series of 20 \_\_\_\_\_;