



PROJECT FEATURE

PROJECT TITLE : Proposed Dredging of Surigao Clustered Project: Ports of Surigao, Surigao del Norte and Del Carmen, Siargao Island

LOCATION : Province of Surigao del Norte

MAJOR SCOPE OF WORK :

- 1) Dredging along berths, approaches and maneuvering areas of the ports to a designed depth below Mean Lower Low Water (MLLW) as follows:
11.00 meters @ Surigao Port
5.00 meters @ Del Carmen Port
- 2) Total Volume to be Dredged : 350,000 cu.m.
(84,000cu.m. at Surigao Port comprising of soft to highly dense earth materials such as coralline like stone and 266,000 cu.m. at Del Carmen Port comprising mostly of soft to medium clayish sand/mud and silt with possible highly compacted soil)
- 3) Disposal of dredged soil materials 15.00 kms away from the project site

APPROVED BUDGET FOR THE CONTRACT : P 187,749,751.78

TOTAL PROJECT COST : P 192,443,495.57

PROJECT (DREDGING) UNIT COST : P 570.89 per cubic meter for Surigao Port
P 501.56 per cubic meter for Del Carmen Port
(Dredging Works Only, excluding General Expenses and Re-imbursable Items)

PROJECT DURATION : 419 calendar days
(inclusive of Sundays / Holidays and unworkable condition)

(NOTE: Under PMO-Surigao's submitted Priority List of Proposed Engineering Projects (PLOPEP) for CY 2023, the dredging of Surigao Port particularly at its turning basin will provide enough space for the safety of maneuvering vessels. Likewise, deepening the channel leading to Del Carmen Port will allow big draft vessels to call thereat.)