

File Copy

PROJECT FEATURE

- PROJECT TITLE** : PROPOSED CONSTRUCTION OF R.C. PIER
- LOCATION** : Port of Lucena, Brgy. Talao-talao, Lucena City
- SCOPE OF WORK** :
- A. BACK-UP AREA**
 - a. Chip-off of existing R.C. Curb (51 l.m.)
 - b. Removal of existing lamp post (1 set)
 - c. Supply/drive/chip R.C. Sheet piles & corner piles(1,853 l.m.)
 - d. Supply/place 3,500 psi concrete for retaining (208 cu.m.)
 - e. Supply/installation of reinforcing bars for retaining wall (19,947kg.)
 - f. Supply/installation of rocks (521 cu.m.)
 - g. Supply/installation of tie-rods of various sizes (39 set)
 - h. Supply/installation of geotextile fabric (446 sq.m.)
 - i. Supply/place fill materials (2,334 cu.m.)
 - j. Construction of PCCP including aggregate base course (590 sq.m.)
 - B. R.C. PIER**
 - a. Supply/drive/chip of 400mm x 400mm PSC piles (4,260 l.m.)
 - b. Supply/place 3,500 psi concrete for the superstructure (495 cu.m.)
 - c. Supply/install reinf. steel bar for the superstructure (71,629 kg.)
 - d. Supply/installation of construction joint (24 l.m.)
 - C. MOORING AND FENDERING SYSTEM**
 - a. Supply/installation of RDF, V500H x 2000L (26 set)
 - b. Supply/installation of mooring bollard, 35T, T-head (26 set)

APPROVED BUDGET FOR THE CONTRACT	:	Php	73,662,504.11
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:	Php	83,238,629.64
PROJECT DURATION	:	420 Calendar Days	

86