PROJECT FEATURE

PROJECT TITLE	:	**CONSTRUCTION OF RO-RO RAMP AND TWO (2) UNITS BREASTING DOLPHIN**
LOCATION	:	**PORT OF SINDANGAN, SINDANGAN, ZAMBOANGA DEL NORTE**
SCOPE OF WORK		
BILL NO.1	**1.00**	**GENERAL EXPENSES**
	1.01	Mobilization, demobilization and cleaning
	1.02	Provide Construction Safety and Health Program in the execution of the project
BILL NO.2	**2.00**	**CONSTRUCTION OF RORO RAMP**
	2.01	DEMOLITION OF EXISTING CONCRETE CURB
	2.02	Supply and Delivery of Two (2) Units RC Pile (Test Pile)
	2.03	Driving of Two (2) Units RC Pile (Test Pile)
	2.04	Splicing of Two (2) Units RC Pile (Test Pile)
	2.05	Supply and Delivery of 0.45 m x 0.45 m RC Pile (4500 PSI)x30mx 18 Units
	2.06	Driving of 0.45mx0.45m RC Piles for RORO Rampx30mx 18 units
	2.07	Splicing of 18 Units RC Pile for the Roro ramp
	2.08	Supply and Installation of Reinforcing Steel Bars
	2.09	Removal and Reinstallation of Existing Mooring Bollard
	2.10	Concreting of Superstructure
	2.11	Supply and Delivery of 500H x 1500L V-Type RDF for the Ro-ro Ramp
	2.12	Installation of 500H x 1500L V-Type RDF for the Ro-ro Ramp
BILL NO.3	**3.00**	**CONSTRUCTION OF TWO UNITS BREASTING DOLPHIN**
	3.01	Supply and Delivery, and Fabrication of RC Piles(450mmx450mmx15mx2)
	3.02	Driving of 0.45mx0.45m RC Piles for Breasting Dolphin
	3.03	Splicing of 18 Units RC Pile for the breasting dolphin
	3.04	Supply and Installation of Reinforcing Steel Bars
	3.05	Concrete Works for Pile Cap
	3.06	Supply & installation of Hollow Cylindrical Rubber Dock Fenders
	3.07	Supply & installation of 50 Tons T-Head Mooring Bollard

APPROVED BUDGET FOR THE CONTRACT	:	**Php**	**24,303,730.03**
SOURCES OF FUNDING	:	**PPA Corporate Fund**	
TOTAL PROJECT COST	:	**Php**	**26,980,944.00**
PROJECT DURATION	:	**208 Calendar Days**	