

PROJECT FEATURE

PROJECT TITLE : PROPOSED WIDENING OF WHARF PHASE-2 (SOUTH BANK)

LOCATION : TMO Pasig, Pasig River, South Harbor, Manila

SCOPE OF WORK A. WIDENING OF R.C. WHARF
(Area = 1,225.06 sq.m.)

1. Removal of portion of existing RC curb and mooring bollard base.
2. Removal and reinstallation of mooring bollard (14 sets)
3. Supply & drive 0.40m x 0.40m Pre-Stressed Concrete(PSC) piles (10,706 l.m.) including splicing (271 no.).
4. Supply and place 3,500psi concrete for superstructure (639 cu.m.) including reinforcing steel bars (113,345 kg.).
5. Supply and install 400H x 1,000L V-type rubber dock fenders (34 sets), 25-ton T-head mooring bollards (3 sets) and new 25-ton mooring bollard accessories (14 sets).

APPROVED BUDGET FOR THE CONTRACT : P 97,591,914.45

Sources of Funding :

TOTAL PROJECT COST : P 110,278,863.33

PROJECT DURATION : 540 DAYS





