PROJECT FEATURE

PROJECT TITLE : **RESTORATION OF DAMAGED PORT FACILITIES**

LOCATION : **Port of Tacloban, Tacloban City, Leyte**

SCOPE OF WORK :

1 General Expenses

1.1.1 Mobilization / Demobilization and Clean-up

1.2.1 Provide Construction Safety and Health Program in the execution of the project

2 Repair of Depressed Concrete Pavement at Berth 7

2.1.1 Demolition of existing pavement and disposal of waste

2.2.1 Excavation of filling materials and piling and check-up of tie rods

2.3.1 Supply and install geotextile fabric

2.4.1 Hauling, placement, and compaction of piled filling materials

2.5.1 Supply, place and compact additional selected fill

2.6.1 Supply, place and compact 200mm thk. gravel base course

2.7.1 Supply and place 300mm thk. 3500 psi portland cement concrete pavement, 255 cu.m.

3 Overlaying of Concrete Pavement at Berth 5

3.1.1 Demolition of existing pavement and disposal of waste

3.2.1 Supply, place and compact selected fill

3.3.1 Supply, place and compact 200mm thk. gravel base course

3.4.1 Supply and place 300mm thk. 3500 psi portland cement concrete pavement, 737 cu.m.

4 Reblocking of Damaged Concrete Pavement at Berth 4, 6 and 7

4.1.1 Demolition of existing pavement and disposal of waste

4.2.1 Supply (30% of Total Volume), place and compact gravel base course

4.3.1 Supply and place 300mm thk. 3500 psi portland cement concrete pavement, 970.38 cu.m.

5 Repair of Collapsed Retaining Wall and Platform Roro Ramp 1

5.1.1 Demolition of retaining wall and concrete pavement and disposal of waste

5.2.1 Excavation of filling materials and piling

5.3.1 Supply & place (50-100 kg/pc) Core Rocks (30% of total volume)

5.4.1 Supply & place (500-1000 kg/pc) Armour Rocks (50% of total volume)

5.5.1 Supply and install geotextile fabric

5.6.1 Supply and place 3500 psi concrete on column, retaining wall and rc crub

5.6.2 Supply and place reinforcemner bars on column, retaining wall and rc curb

5.6.3 Supply and place 6" CHB with 25mm thick plastering and finishing

5.7.1 Supply (50% volume of selected fill), spread and compact excavated filling materials

5.8.1 Supply, place and compact 200mm thk. gravel base course

5.9.1 Supply and place 300mm thk. 3500 psi portland cement concrete pavement, 54 cu.m.

6 Repair of Transit Shed

6.1.1 Replace old roofing, gutters, down spout and repair of the damaged c-purlins

6.2.1 Supply and install 10 units industrial wind driven roof ventilator (600mm)

APPROVED BUDGET FOR THE CONTRACT : **Php 37,302,724.47**

SOURCES OF FUNDING : **PPA Corporate Fund**

TOTAL PROJECT COST : **Php 42,152,078.65**

PROJECT DURATION : **300 Calendar Days**