

PROJECT FEATURE

PROJECT TITLE	:	CLAVERIA PORT DEVELOPMENT PROJECT	
LOCATION	:	Port of Claveria, Taggat Norte, Cagayan	
SCOPE OF WORK	:	<p>A. BACK-UP AREA AND CAUSEWAY</p> <ol style="list-style-type: none"> 1 Chipping of existing R.C. Curb (47 l.m.) 2 Excavation of existing fill and seabed (1,367 cu.m.) 3 Supply and driving of R.C. Sheet Pile and R.C. Corner Piles (651 l.m.) 4 Chipping/cutting of newly driven piles (93 no.) 5 Supply and laying of 50-100 kg. rocks (6,299 cu.m.) 6 Supply and laying of concrete blocks (2,500 pcs.) 7 Supply and placing of fill materials (4,006 cu.m.) 8 Supply and placing of 3,500 psi concrete (739 cu.m.) 9 Supply and installation of steel reinforcement (40,851 kg.) 10 Supply and installation of 50mm dia x 10m tie-rod (24 sets) 11 Supply and placing of aggregate base course (469 cu.m.) 12 Construction of 250mm thk PCCP (2,380 sq.m.) 13 Construction of concrete slope protection (40 sq.m.) 14 Construction of ductbank, handhole and lamp post foundation (1 lot) 15 Supply and installation of 6m high hot dip galvanized steel tapered lamp post with floodlight fixtures and accessories (5 sets) 16 Construction of Perimeter fence (100 l.m.) <p>B. R.C. PIER</p> <ol style="list-style-type: none"> 1 Supply and driving of 600mm dia. Steel Pipe Piles (465 m.t.) 2 Cutting and disposal of newly driven Steel Pipe Piles (150) 3 Removal of clogged materials inside the SPP (1,819 cu.m.) 4 Fabrication and installation of Reinforcing cage (115,476 kg.) 5 Supply and placing of 3,500 psi concrete filler (1,227 cu.m.) 6 Supply and installation of reinforcing steel bar (106,989 kg.) 7 Supply and placing of 3,500 psi concrete (748 cu.m.) 8 Fabrication and installation of construction joint (54 l.m.) 9 Supply and installation of V400 x 2000L Rubber dock fender (34 set) 10 Supply and installation of 50 Tons mooring bollard (16 sets) <p>C. PASSENGER TERMINAL BUILDING</p> <ol style="list-style-type: none"> 1 Supply and driving of 400 x 400mm x 8m R.C. piles (120 l.m.) 2 Construction of 1-storey Passenger Terminal Building (50 pax, 250 sq.m.) <p>Includes:</p> <ol style="list-style-type: none"> a) Drainage, sewerage and water system b) Air conditioning units, auxiliary units such as CCTV, CATV, BGM/PA, FDAS and Telephone system. c) Office furnitures such as tables and chairs for staff and gang chairs for passengers. d) Supply and installation of 50KVA distribution transformer (1-set) 	
APPROVED BUDGET FOR THE CONTRACT	:	Php	190,234,789.18
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:	Php	214,965,311.77
PROJECT DURATION	:	450 Calendar Days	

98 8

98