w/ CAF

## PROJECT FEATURE

| | | |
|---|---|---|
| **PROJECT TITLE** | : | **CONSTRUCTION/IMPROVEMENT OF BARANGAY BUSAY COMMUNITY PORT** |
| **LOCATION** | : | **Sacol Island, Zamboanga City** |
| **SCOPE OF WORK** | : | **A. CONSTRUCTION OF BACK UP AREA AND ROCK CAUSEWAY WITH STAIRLANDING**<br>1 Supply and place 50-100 kg/pc core rocks (3,378 cu.m.) and 500 kg/pc armour rocks (2,052 cu.m.)<br>2 Supply, spread and compact sand & gravel fill ( 600 cu.m.), aggregate subbase course (246 cu.m.) and geotextile fabric (1,242 sq.m)<br>3 Construct 250mm thick Portland cement concrete pavement (617 sq.m.) including dowel bars (282 kg)<br>4 Supply and place 3,500 psi concrete for RC curb, stairlanding, and lamp post foundation (289 cu.m.) including steel reinforcements (11,542 kg) and gravel bedding (2 cu.m.)<br>5 Supply and install mooring cleats including accessories (10 sets)<br>6 Supply and install port lighting system<br>**B. CONSTRUCTION OF PASSENGER SHED**<br>1 Construction of passenger shed (Area = 140 sq.m.) including structural, architectural, plumbing and sanitary works. |

| | | | |
|---|---|---|---|
| **APPROVED BUDGET FOR THE CONTRACT** | : | **Php** | **44,699,954.84** |
| **SOURCES OF FUNDING** | : | **General Appropriations Act (GAA)** | |
| **TOTAL PROJECT COST** | : | **Php** | **49,245,940.25** |
| **PROJECT DURATION** | : | **390** | **Calendar Days** |