

PROJECT FEATURE

PROJECT TITLE	:	San Andres Port Improvement and Expansion Project
LOCATION	:	Port of San Andres, Catanduanes
SCOPE OF WORK	:	<p>A. DEMOLITION & REMOVAL WORKS</p> <ol style="list-style-type: none">1 Demolish and dispose existing structure (RoRo Ramp) for build up (77 sq.m.)2 Chip-off portion of existing R.C. Curb (34 l.m.)3 Chip-off portion of existing mooring block to be aligned to pier (15 cu.m.)4 Removed and turn over to PPA existing mooring bitts, mooring cleats and rubber dock fenders affected by demolition (12 no.)5 Chip-off existing concrete piles for build-up (12 no.) <p>B. RC PLATFORM, RORO RAMP AND RC PIER</p> <ol style="list-style-type: none">1 Supply and drive A252 Grade 2, 500mm Ø Steel Pipe Piles test pile, 3 nos. (15.06 m.t.- 132 l.m.) including application of polyurethane external coating (43 sq.m.), installation of reinforcing band tip (3 pcs), splicing (3 pcs)2 Supply and drive A252 Grade 2, 500mm Ø Steel Pipe Piles (652 m.t.- 5,704 l.m.) including application of polyurethane external coating (1,940 sq.m.), installation of reinforcing band tip (132 pcs), splicing (132 pcs) and cutting (132 pcs)3 Supply and place 3,500 psi concrete filler (274 cu.m.) and reinforcing steel cage (75,276 kgs of various sizes) for steel pipe piles including extraction of clogged materials (88 cu.m.)4 Supply and place 3,500 psi concrete (663 cu.m.) and reinforcing steel bars (109,182 kg of various sizes) for superstructure5 Supply and install of Rubber Dock Fenders (V500 x 1500L - 16 sets) and Mooring Bollard, (35-Tons, T-head - 8 sets)
APPROVED BUDGET FOR THE CONTRACT	:	Php 156,980,885.59 ✓
SOURCES OF FUNDING	:	PPA Corporate Fund
TOTAL PROJECT COST	:	Php 169,539,356.44 ✓
PROJECT DURATION	:	450 Calendar Days

