PROJECT FEATURE

PROJECT TITLE : **IMPROVEMENT/RESTORATION OF TMO/PTB 1 AND 2, PORT LIGHTING SYSTEM, COVERED WALKWAY, GUEST AND SECURITY BUILDING**

LOCATION : PORT OF TABACO CITY, ALBAY

SCOPE OF WORK

(with estimated quantity, dimension and volume)

1.00	**General Expenses**		
1.01	Mobilization Demobilization	1.00	lot
1.02	Provide Construction Safety and Health Program in the Execution of the Project	10.00	mos
2.00	**Passenger Terminal Building 1/TMO**		
2.01	Removal and Disposal Damaged Ceiling, Aluminum Doors and Windows and other obstruction	1.00	lot
2.02	Supply and installation of concrete barriers	14.00	sets
2.03	Supply and place reinforced concrete for ramp and stairs including stainless steel railings and non-skid ceramic floor tile finish in landings and steps	1.00	lot
2.04	Replacement of Ceiling	356.00	sq.m.
2.05	Supply and Installation of uPVC framed w/ laminated glass windows including enclosure of window openings	66.24	sq.m
2.06	Supply & Installation of various doors including accessories	48.15	sq.m
2.07	Supply & Installation of Metal Sliding Storm Shutter (Paint Finish)	70.08	sq.m
2.08	Painting of Ceiling, Interior and Exterior Walls	2,863.36	sq.m.
2.09	Supply and Install Restroom Fixtures, Toilet and Bath Modular Partitions including declogging of pipes	1.00	lot
2.10	Replacement of electrical wirings and fixtures	1.00	l.s
2.11	Replacement of Tiles at Passenger's Waitng Area and Comfort Room	470.28	sq.m
2.12	Replacement of Old to New PPA Signage and Logos	2.00	unit
3.00	**Passenger Terminal Building 2**		
3.01	Removal and Disposal Damaged Ceiling, Floor Tiles, Aluminum Doors and Windows and other Obstruction	1.00	lot
3.02	Replacement of Ceiling	290.80	sq.m
3.03	Supply and Installation of uPVC framed w/ laminated glass windows including enclosure of window openings	42.30	sq.m
3.04	Supply & Installation of Metal Sliding Storm Shutter (Paint Finish)	48.12	sq.m
3.05	Supply & Installation of various Doors	23.47	sq.m
3.06	Repainting of Ceiling, Interior and Exterior Walls	563.81	sq.m
3.07	Supply and Installation Plumbing Fixtures and Modular Cubicle Partitions	1.00	lot
3.08	Replacement of Floor Tiles	351.98	sq.m
3.09	Replacement of Lighting Fixtures and Wirings	1.00	lot
3.10	Repair/Replacement of Roofing including C-purlins and aluminum roof insulation	278.24	sq.m
3.11	Supply and Installation of Concrete Canopy, Partition at 2nd Flr, and Plant Box	1.00	lot
4.00	**Guest and Security Building**		
4.01	Removal and Disposal Damaged Roofing, Ceiling, Partition Wall, and other Obstruction	1.00	lot
4.02	Supply and Install Reinforcing Steel Bars	5470.08	kg
4.03	Supply and Place 3500 psi Concrete	41.64	cu.m
4.04	Replacement of Steel Trusses and Roofing Sheets including aluminum roof insulation	213.44	sq.m
4.05	Replacement of Ceiling	191.00	sq.m
4.06	Installation of CHB and Dry Wall	405.05	sq.m
4.07	Painting of Ceiling, Interior and Exterior Walls	1049.99	sq.m
4.08	Replacement of Lighting Fixtures and Wirings	1.00	lot
4.09	Supply and Installation of various type of Doors	30.51	sq.m
4.10	Supply and Installation of uPVC framed w/ laminated glass windows	20.80	sq.m
4.11	Supply and Installation of Plumbing Fixtures and connection	1.00	lot
4.12	Supply and Installation of Floor and Wall Tiles	234.25	sq.m
4.13	Supply and Installation of Millwork Cabinet (Paint Finish)	1.00	lot
4.14	Construction of Septic Tank and Catch Basin	1.00	set
4.15	Supply and Installation of Window Shutter (Paint Finish)	23.64	sq.m
5.00	**Covered Walkway**		
5.01	Removal and Disposal of the Existing Walkway	1.00	lot
5.02	Supply and Installation of Roofing including Bulkhead Wall Lamp Outdoor	461.25	sq.m
6.00	**Port Lighting System**		
6.01	Supply and Installation of LED Weatherproof Floodlights 200W including underground electrical	20.00	set

APPROVED BUDGET FOR THE CONTRACT : **Php** **18,885,391.88**

TOTAL PROJECT COST : **Php** **19,546,380.60**

PROJECT DURATION : **300 Calendar Days**