w/ CAF

PROJECT FEATURE

PROJECT TITLE	:	**CONSTRUCTION/IMPROVEMENT OF BARANGAY DITA COMMUNITY PORT**
LOCATION	:	**Barangay Dita, Zamboanga City**
SCOPE OF WORK	:	**A. CONSTRUCTION OF BACK UP AREA AND ROCK CAUSEWAY WITH STAIRLANDING** 1 Supply and place 50-100 kg/pc core rocks (4,265 cu.m.) and 500 kg/pc armour rocks (2,052 cu.m.) 2 Supply, spread and compact sand & gravel fill (2,868 cu.m.) and geotextile fabric (1,418 sq.m) 3 Construct 250mm thick Portland cement concrete pavement (751 sq.m.) including dowel bars (326 kg) 4 Supply and place 3,500 psi concrete for RC curb, stairlanding, and lamp post foundation (145 cu.m.) including steel reinforcements (6,387 kg) and gravel bedding (2 cu.m.) 5 Supply and install mooring cleats including accessories (4 sets) 6 Supply and install port lighting system **B. CONSTRUCTION OF PASSENGER SHED** 1 Construction of passenger shed (Area = 140 sq.m.) including structural, architectural, plumbing and sanitary works.
APPROVED BUDGET FOR THE CONTRACT	:	**Php 44,602,710.28**
SOURCES OF FUNDING	:	**General Appropriations Act (GAA)**
TOTAL PROJECT COST	:	**Php 49,245,852.42**
PROJECT DURATION	:	**390 Calendar Days**