

PROJECT FEATURE

PROJECT TITLE	:	WIDENING OF ACCESS TRESTLE AND CONSTRUCTION OF RORO RAMP WITH PLATFORM	
LOCATION	:	Port of Estancia, Iloilo	
SCOPE OF WORK	:	<p>A. CONSTRUCTION OF CAUSEWAY (5.135m x 6.00m)</p> <p>a. Chip-off of existing R.C. Curb (6 l.m.)</p> <p>b. Supply/place 3,500 psi concrete (21 cu.m.)</p> <p>c. Supply/installation of reinforcing bars (1,482 kg.)</p> <p>d. Supply/installation of rocks (82 cu.m.)</p> <p>e. Supply/installation of geotextile fabric (14 sq.m.)</p> <p>f. Supply/place fill materials (36 cu.m.)</p> <p>g. Construction of PCCP including aggregate base course (26 sq.m.)</p> <p>h. Supply/installation of construction joint (7 l.m.)</p> <p>B. CONSTRUCTION OF ACCESS TRESTLE AND RORO RAMP WITH PLATFORM</p> <p>a. Chip-off of existing R.C. Curb (114 l.m.)</p> <p>b. Remove existing mooring bits and used tires/fenders (10 no.)</p> <p>c. Demolition of existing mooring blocks (5 no.)</p> <p>d. Supply/drive 400mm x 400mm PSC piles (2,125 l.m.)</p> <p>e. Supply/place 3,500 psi concrete for access trestle, RoRo ramp with R.C.platform (402 cu.m.)</p> <p>f. Supply/install reinf. steel bar for R.C. platform & pier (67,736 kg.)</p> <p>g. Supply/installation of construction joint (177 l.m.)</p> <p>h. Supply/installation of mooring bollard (25T & 35T) (10 set)</p> <p>i. Supply/installation of RDF (V400H x1000L & V400H x 1500L) (13 set)</p>	
APPROVED BUDGET FOR THE CONTRACT	:	Php	36,357,823.04
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:	Php	41,084,340.03
PROJECT DURATION	:	360 Calendar Days	