

**PROJECT FEATURE**

<b>PROJECT TITLE</b>	:	<b>CONST. OF BACK-UP AREA &amp; PORT OPERATIONS BUILDING</b>	
<b>LOCATION</b>	:	<b>Port of Coron, Palawan</b>	
<b>SCOPE OF WORK</b>	:	<p><b>A. BACK-UP AREA</b></p> <ol style="list-style-type: none"> <li>1 Chipping &amp; disposal of existing R.C. Curb (124 l.m.)</li> <li>2 Removal of existing lamp post (4 sets)</li> <li>3 Supply &amp; driving of PSC Sheet pile &amp; R.C. Corner piles (4,304 l.m.)</li> <li>4 Supply &amp; placing of concrete for retaining wall (589 cu.m.)</li> <li>5 Supply &amp; installation of steel reinforcement for retaining wall (47,399 kg.)</li> <li>6 Supply &amp; installation of core &amp; armor rocks ( 3,717 cu.m.)</li> <li>7 Supply &amp; placing of fill materials (20,581 cu.m.)</li> <li>8 Supply &amp; placing of aggregate base course (799 cu.)</li> <li>9 Construction of Portland Cement Concrete Pavement (4,868 cu.m.)</li> </ol> <p><b>B. R.C. WHARF WITH RORO RAMP</b></p> <ol style="list-style-type: none"> <li>1 Supply &amp; driving of R.C. square piles (2,338 l.m.)</li> <li>2 Supply &amp; placing of concrete for R.C. Wharf (328 cu.m.)</li> <li>3 Supply &amp; installation of steel reinforcement for R.C. Wharf (65,350 kg.)</li> <li>4 Supply &amp; installation of construction joint (126 l.m.)</li> <li>5 Supply &amp; installation of Rubber dock fenders (12 sets)</li> <li>6 Supply &amp; installation of mooring bollard (4 sets)</li> </ol> <p><b>C. PORT OPERATIONS BUILDING</b></p> <ol style="list-style-type: none"> <li>1 Supply &amp; driving of PSC foundation piles (1,420 l.m.)</li> <li>2 Construction of 2-storey Port Operations Building (3,800 sq.m., 500 pax)</li> <li>3 Construction of Pumphouse and apurtenances (12.24 sq.m.)</li> <li>5 Construction of R.C. Ductbank &amp; lamp post foundation ( 30.66 cu.m.)</li> <li>6 Supply, delivery &amp; installation of gang chairs ( 1 lot)</li> <li>7 Supply &amp; installation of Distribution transformer (1 lot)</li> </ol>	
<b>APPROVED BUDGET FOR THE CONTRACT</b>	:	<b>Php</b>	<b>268,742,342.94</b>
<b>SOURCES OF FUNDING</b>	:	<b>PPA Corporate Fund</b>	
<b>TOTAL PROJECT COST</b>	:	<b>Php</b>	<b>303,678,847.52</b>
<b>PROJECT DURATION</b>	:	<b>600 Calendar Days</b>	

8

8

4