PROJECT FEATURE

PROJECT TITLE	:	**RESTORATION OF DAMAGED RC PIER AT PORT OF MANGUINO-O**
LOCATION	:	**Manguino-o, Calbayog, Samar**
SCOPE OF WORK	:	**1 General Expenses**
		1.1.1 Mobilization / Demobilization and clean-up
		1.2.1 Provide Construction Safety and Health Program in the execution of the project
		2 Repair of Damaged Portion of R.C. Pier
		2.1.1 Removal of 10 units rubber dock fender and 7 units mooring bollard
		2.1.2 Demolition of damaged r.c. deck and disposal of debris
		2.2.1 Chipping of damaged R.C. piles to cut-off elevation
		2.3.1 Supply and place 3500psi concrete jacket on 44 units single r.c. pile
		2.3.2 Supply and place rebars for item 2.3.1
		2.4.1 Supply and place 3500psi concrete jacket on 16 units double r.c. pile
		2.4.2 Supply and place rebars for item 2.4.1
		2.5.1 Supply and place 3500psi concrete for 370 l.m. r.c. beams
		2.5.2 Supply and place rebars for item 2.5.1
		2.6.1 Supply and deliver to site 35 tons mooring bollard
		2.6.2 Supply and place 3500psi concrete for 6 units mooring blocks
		2.6.3 Supply and place rebars for item 2.6.2
		2.6.4 Handle and install 35 tons mooring bollard including accessories
		2.7.1 Supply and place 0.25m thick 3500psi concrete on 940.50 sq.m. r.c slab
		2.7.2 Supply and place rebars for item 2.7.1
		2.8.1 Supply and place 3500 PSI concrete on 79 l.m. curtain wall and 19m joint
		2.8.2 Supply and place rebars for item 2.8.1
		2.9.1 Supply and deliver to site 400 x 1500 v-type r.d.f. including accessories
		2.9.2 Handle and install 400 x 1500 v-type r.d.f. including accessories
		3 Repair of Drainage Canal
		3.1.1 Removal of grills, cutting, chipping of 2 sides drain edge and disposal of waste
		3.2.1 Supply and place lintel beams on 2 sides
		3.3.1 Supply, fabricate and install grill cover
APPROVED BUDGET FOR THE CONTRACT	:	**Php 15,403,132.77**
SOURCES OF FUNDING	:	**PPA Corporate Fund**
TOTAL PROJECT COST	:	**Php 15,564,865.67**
PROJECT DURATION	:	**270 Calendar Days**