PROJECT FEATURE

PROJECT TITLE	:	**IMPROVEMENT/EXPANSION OF PASSENGER TERMINAL BUILDING (PTB) DAMAGED BY TYPHOON "TISOY"**
LOCATION	:	**Port of Calbayog, Calbayog, Samar**
SCOPE OF WORK	:	**1 General Expenses** 1.01 Mobilization / Demobilization and Clean-up 1.02 Provide Construction Safety and Health Program in the execution of the project **2 Improvement / Expansion of Passenger Terminal Building** 2.01 Demolition and disposal of remaining damaged covered walk 2.02 Removal and disposal of existing roofing, trusses, ceiling, and existing comfort room of PTB 2.03 Installation of batter board, cutting, breaking and disposal of concrete pavement 2.04 Excavation for column footing, foot tie beams, storm drainage and septic tank and disposal of waste 2.05 Supply and place 3500 psi concrete on footing,column,beams,tie beams,duct 2.06 Supply & install reinforcement bars for item 2.05 2.07 Supply, spread and compact fill materials and gravel bedding 2.08 Supply and place CHB wall, CR partition, septic tank & fire wall 2.09 Supply & install steel trusses, half truss, hip truss, end wall bracing & c-purlins 2.10 Supply and install steel tile roofing and accessories 2.11 Supply and install interior acoustic board & exterior ceiling 2.12 Supply and place doors, windows, and gang chairs 2.13 Supply and install plumbing pipes , tilings and fixtures 2.14 Supply and install stainless steel handrails 2.15 Supply and place floor tiles 2.16 Supply and install electrical wiring and fixtures, panel box, breakers and other accessories 2.17 Supply,install, testing and commisioning of airconditioning units, fire alarm sytem, tv., breakers and accessories 2.18 Supply and install aluminum composite panel, PPA Logo and Signage 2.19 Surface preparation and apply two (2) coats of paint on entire building
APPROVED BUDGET FOR THE CONTRACT	:	**Php 16,127,653.23**
SOURCES OF FUNDING	:	**PPA Corporate Fund**
TOTAL PROJECT COST	:	**Php 16,220,871.06**
PROJECT DURATION	:	**300 Calendar Days**