Republic of the Philippines

PHILIPPINE PORTS AUTHORITY

Port Management Office - Western Leyte/ Biliran

PROJECT FEATURE

PROJECT TITLE	:	**PROVISION OF GUEST QUARTER AND MULTIPURPOSE GAD HALL AT POB ROOF DECK**
LOCATION	:	PORT OF ORMOC, ORMOC CITY, LEYTE

SCOPE OF WORK

BILL NO. 1	**GENERAL EXPENSES**
1.01	Mobilization, Demobilization & Clean-up of Site
1.02	Provide and Maintenance of Engineer's Site Office
1.03	Provide Environmental Safety and Health Program
BILL NO. 2	**CONSTRUCTION OF GUEST QUARTER AND MULTI-PURPOSE GAD HALL**
2.01	Demolish and Disposal of obstructions and Existing Structures
2.02	Removal and Disposal of existing Tiles at Staircase
2.03	Chipping and Drilling of Existing concrete
2.04	Supply and Installation of Anchor Bolts, Gusset Plate and Baseplate for Pedestal
2.05	Supply and Installation of Steel reinforcements for Pedestal and Tie Beam
2.06	Supply and Installation of I - Beam Column
2.07	Supply, Place and Compaction of 3000psi Concrete Including Formworks for pedestal and Tie Beam
2.08	Supply and Installation of CHB Walls 6" and 4"
2.09	Supply and Installation of Plaster to CHB Walls
2.10	Supply, Fabrication and Installation of Steel Truss
2.11	Supply, Fabrication and Installation of Roof Beam
2.12	Supply, Fabrication and Installation of Fascia with Frame
2.13	Supply and Installation of ceiling
2.14	Supply and Installation of Spandrel Eaves
2.15	Supply and Installation of Polycarbonate Eaves
2.16	Supply and Installation of Checkered Plate, 8mm thk @ Attic
2.17	Supply and Installation of Roofing System
2.18	Supply and Installation of Wood and PVC Doors
2.19	Supply, Delivery and Installation of Glass Doors and Windows
2.20	Supply, Delivery and Installation of Glass Wall at the Staircase
2.21	Supply and Installation of Pre fabricated Stair including Painting
2.22	Supply and Installation of Marble Stone Porcelain Type Floor Tiles to GAD Hall and Guest Quarter
2.23	Supply and Installation of Non-skid Granite type Floor Tiles to Staircase Area
2.24	Supply and Installation of Unglazed Porcelain Type Floor Tiles to Comfort Rooms
2.25	Supply and Installation of Glossy Homogeneous Type Wall Tiles to Comfort Rooms
2.26	Supply and Installation of CR Partitions including Cubicle Doors for Common Toilet
2.27	Supply and Installation of Common Kitchen
2.28	Supply and Installation of Cr fixtures
2.29	Supply and Installation of Plumbing System
2.30	Supply and Installation of Sewage System

	2.31	Supply and Installation of Electrical Wiring System and Electrical Lighting Fixtures
	2.32	Supply & Installation of Main Panel Board
	2.33	Supply, Installation and Commissioning of Airconditioning System
	2.34	Supply and Installation of Rain Water Harvester System
	2.35	Supply and Application of Paints for Pedestal, Column, Walls, Girt, Ceiling, Truss, Fascia Frame, and Roof Purlins
	2.36	Supply and Installation of Steel Column
	2.37	Supply and Installation of Steel Beam, Trusses, Pergola Slats, and Roofing
	2.38	Supply, Place and Compaction of 2500 psi Concrete including Formworks for Lean Concrete
	2.39	Supply and Installation of Floor Tiles

APPROVED BUDGET FOR THE CONTRACT	: P	**25,955,365.57**
SOURCES OF FUNDING	:	**PPA CORPORATE FUNDS**
TOTAL PROJECT COST	: P	**28,940,232.61**
PROJECT DURATION	:	**360 CALENDAR DAYS**