PROJECT FEATURE

PROJECT TITLE	:	**MALALAG PORT EXPANSION PROJECT (PHASE III)**
LOCATION	:	**Port of Malalag, Malalag, Davao del Sur**
SCOPE OF WORK	:	**A. REMOVAL AND EXCAVATION WORKS** 1 Excavate and Backfill existing fill materials 2 Chopping of existing rc curb 3 Removal and disposal of existing fence 4 Removal of existing structure 5 Removal of existing solar lamp post **B. PORT OPERATIONAL AREA** 1 Supply & driving of Z-type Steel sheet pile and connector 2 Supply & installation of dowel bars for Steel sheet piles 3 Handling, pitching & driving of Steel Sheet piles 4 Supply & installation of steel waling and splice plate 5 Cutting & disposal of newly driven Steel sheet piles 6 Supply & driving of Steel Pipe pile including polyurethane & splicing 7 Handling, pitching & driving of Steel Pipe piles 8 Supply,fabricate band tip for the steel pipe piles 9 Cutting & disposal of newly driven Steel Pipe piles 10 Extraction of clogged materials inside the SPP 11 Supply & placing of sand filler for SPP 12 Supply & placing of concrete filler for SPP 13 Supply & installation of reinforcing steel cage for SPP 14 Supply, splice & driving of PSC anchor pile 15 Cutting & disposal of newly driven PSC anchor piles 16 Supply & placing of 3,500 psi concrete 17 Supply & installation of reinforcing steel bars 18 Supply & placing of gravel bedding 19 Supply & placing of 50 to 100 kg. rocks 20 Supply & installation of Tie-rod 21 Supply & installation of geotextile fabric 22 Supply & placing of fill materials 23 Supply & placing of leveling course sand cushion 24 Supply & placing of cement treated base course 25 Supply & placing of interlocking concrete block pavement 26 Supply & placing of aggregate base course 27 Construction of PCC Pavement 28 Construction of security fence (1 lot) 29 Drainage system (1 lot) 30 Portlighting system (1 lot) 31 Re-instalaltion of newly remove solar lamp post
APPROVED BUDGET FOR THE CONTRACT	:	**Php 751,909,985.81**
SOURCES OF FUNDING	:	**PPA Corporate Fund**
TOTAL PROJECT COST	:	**Php 849,658,283.96**
PROJECT DURATION	:	**630 Calendar Days**