PROJECT FEATURE

PROJECT TITLE	:	**EXTENSION OF BREAKWATER PIER**
LOCATION	:	**Port of Capinpin, Brgy. Puting Buhangin, Orion, Bataan**

A BREAKWATER PIER EXTENSION - I

1 Excavation of seabed (279 cu.m.)
2 Supply and delivery of PSC Sheet Piles and Corner Piles (5,771 l.m.)
3 Handling, pitching and driving PSC Sheet Piles and Corner Piles (5,771 l.m.)
4 Chipping/cutting and disposal of newly driven PSC Sheet Piles (199 no.)
5 Supply and placing of sacked concrete (4 cu.m.)
6 Supply and installation of steel reinforcement for the superstructure (14,007 kg.)
7 Supply and placing of concrete for the superstructure (227 cu.m.)
8 Supply and placing of rock boulders (3,186 cu.m.)
9 Construction of concrete pavement (263 sq.m.)
10 Supply and installation of solar powered light beacon (1 set)

B BREAKWATER PIER EXTENSION - II

1 Excavation of seabed (3,618 cu.m.)
2 Supply and delivery of PSC Sheet Piles and Corner Piles (16,520 l.m.)
3 Handling, pitching and driving PSC Sheet Piles and Corner Piles (16,520 l.m.)
4 Chipping/cutting and disposal of newly driven PSC Sheet Piles (590 no.)
5 Supply and placing of sacked concrete (2 cu.m.)
6 Supply and installation of steel reinforcement for the superstructure (40,606 kg.)
7 Supply and placing of concrete for the superstructure (658 cu.m.)
8 Supply and placing of rock boulders (9,925 cu.m.)
9 Construction of concrete pavement (812 sq.m.)

APPROVED BUDGET FOR THE CONTRACT	:	**Php**	**418,918,810.53**
SOURCES OF FUNDING	:	**PPA Corporate Fund**	
TOTAL PROJECT COST	:	**Php**	**473,378,255.90**
PROJECT DURATION	:	**570 Calendar Days**	