w/ CAF

PROJECT FEATURE

PROJECT TITLE	:	**CASIGURAN PORT EXPANSION AND REHABILITATION PROJECT**
LOCATION	:	**Port of Casiguran, Casiguran, Aurora**

A CONSTRUCTION OF PORT OPERATIONAL AREA (4,003.03 sq.m.)

1 Demolition of existing perimeter fence (57 l.m.)
2 Chiping-off portion of existing rc curb (87 l.m.)
3 Demolistion of existing pavement (259 sq.m.)
4 Excavation and backfilling of fill materials (216 cu.m.)
5 Remove existing lamp post and turn-over to the Authority (16 no.)
6 Supply and placing gravel bedding (24 cu.m.)
7 Supply and placing 3,500 psi concrete for rock bulkhead, stairlanding, and port lighting structures (188 cu.m.)
8 Supply and installation of steel reinforcement for the rock bulkhead, stairlanding and port lighting structures (11,439 kg.)
9 Supply and placing of 50 to 100 kg./pc. core rocks (2,177 cu.m.) and 1,000 kg./pc. armour rocks (1,488 cu.m.)
10 Supply and installation of geotextile fabric (1,073 sq.m.)
11 Supply and placing of sand and gravel fill (11,225 cu.m.)
12 Supply, spead and compact of aggregate sub-base course (3,755 cu.m.) and aggregate base
13 course (836 cu.m.)
14 Construction of PCCP (300mm thk) including dowel bars and construction joint (4,179 sq.m.)
15 Construction catch drain manhole (9 set)
16 Supply and install reinforced concrete pipe Ø 600mm (108 l.m.)
17 Construction of CHB with cyclone wire fence (57 l.m.)
18 Construction of guard house and steel gate (1 lot)
19 Construction of septic vault including accessories (1 no.)
20 Construction of catch basin including accessories (1 no.)
21 Relocation of removed lamp post (7 no.)
22 Construction of port lighting system (1 lot)
23 Supply, deliver, and install distribution transformer and its accessories (1 lot)

APPROVED BUDGET FOR THE CONTRACT	:	**Php**	**75,401,525.21**
SOURCES OF FUNDING	:	**PPA Corporate Fund**	
TOTAL PROJECT COST	:	**Php**	**85,203,723.48**
PROJECT DURATION	:	**420 Calendar Days**	