PROJECT FEATURE

PROJECT TITLE	:	**UBAY PORT EXPANSION PROJECT**
LOCATION	:	**Port of Ubay, Brgy. Poblacion, Ubay, Bohol**
SCOPE OF WORK	:	**A. REMOVAL AND EXCAVATION WORKS** 1 Chipping of existing R.C. Curb 2 Removal and disposal of existing pavement 3 Excavation of existing sea bed 4 Removal of existing bollard and fender 5 Excavation of backfilling works **B. PORT OPERATIONAL AREA WITH CONTINUOUS RORO RAMP** 1 Supply & driving of Steel sheet pile including connectors & protective coating 2 Supply & installation of steel waling and splice plate 3 Supply & installation of dowel bars 4 Supply & placing of 3,500 psi concrete 5 Supply & installation of reinforcing steel bars 6 Supply & placing of gravel bedding 7 Supply & placing of 50 to 100 kg. rocks 8 Supply & placing of rubble concrete 9 Supply & placing of concrete blocks 10 Supply & installation of Tie-rod 11 Supply & installation of geotextile fabric 12 Supply & placing of fill materials 13 Supply & placing of aggregate base course 14 Construction of PCC Pavement 15 Supply and installation of Portlighting system 16 Supply & placing of steel ramp protection 17 Supply & installation of Rubber dock fenders 18 Supply & installation of mooring bollards and mooring cleat 19 Re-installation of newly removed mooring bollards 20 Restoration of demolished pavement **C. R.C. PIER EXTENSION** 1 Supply Steel Pipe pile including protective coating 2 Handling, pitching & driving of Steel Pipe piles 3 Supply,fabricate band tip for the steel pipe piles 4 Supply & placing of concrete filler for SPP 5 Supply & installation of reinforcing steel cage for SPP 6 Supply & placing of 3,500 psi. concrete for the superstructure 7 Supply & installation of reinf. steel bar for the superstructure 8 Supply & installation of construction joints 9 Supply & installation of mooring bollards 10 Re-installation of newly removed rubber dock fener
APPROVED BUDGET FOR THE CONTRACT	:	**Php 364,310,330.23** ✓
SOURCES OF FUNDING	:	**PPA Corporate Fund**
TOTAL PROJECT COST	:	**Php 411,670,673.15** ✓
PROJECT DURATION	:	**480 Calendar Days**