PROJECT FEATURE

PROJECT TITLE	:	**NEW PORT DEVELOPMENT PROJECT**
LOCATION	:	**Port of Catbalogan, Catbalogan, Samar**

A PORT OPERATIONAL AREA WITH 2-UNITS RORO RAMP ON FILL

1 Excavate existing fill materials (42,291 cu.m.)
2 Supply and driving of U-Type steel sheet pile (1,640 m.t., 6,038 l.m.) including protective coating (12,278 sq.m.)
3 Supply and installation of dowel bars (14,240 kg.), steel waling and splice plate (31,797 kg.)
4 Supply and placing of 3,500 psi concrete (2,672 cu.m.)
5 Supply and installation of reinforcing steel bars (188,049 kg.)
6 Supply and installation of Ø50mm tie-rod of various length (405 set)
7 Supply and placing of 50-100kg/pc core rocks (24,950 cu.m.) and 1,000 kg/pc. armour rocks (4,419 cu.m.)
8 Supply and installation of Geotextile Fabric (12,605 sq.m.)
9 Supply, spread and compact sand and gravel fill (35,903 cu.m.) and aggregate sub-base course (25,797 cu.m.)
10 Supply, spread and compact aggregate base course (10,768 cu.m.) and aggregate surface course (10,908 cu.m.)
11 Supply and place gravel bedding (213 cu.m.)
12 Construction of Portland Cement Concrete Pavement (17,478 sq.m.)
13 Supply and install machine bended 20mmm thick steel ramp protection (37 set)
14 Supply and install hot-dip galvanized trench grate cover for lateral drainage (498 l.m.) and catch drain manhole (10 no.)
15 Supply and install reinforced concrete pipe culvert 900mm dia. (708 l.m.) and catch drain manhole with concrete cover (24 no.)
16 Construction of security fence (385 l.m.)
17 Supply and installation of hot-dipped galvanized angle bar for const. joints (12 l.m.)
18 Supply, deliver and install rubber dock fender of various sizes including accessories (80 set)
19 Supply, deliver and install mooring bollard, 35-Ton, Tee-head (35 set)
20 Supply, deliver and install electrical works for the port lighting system (1 set)
21 Supply and drive 450mm x 450mm PSC piles for floodlight foundation (144 l.m.)

B PUMPHOUSE WITH DOMESTIC WATER TANK AND RAINWATER TANK

1 Construction of Pumphouse with domestic water tank and rainwater tank complete with architectural finishes, structural, electrical, plumbing (booster pump and pressure tank), painting etc. (Area = 19.44 sq.m.)

C POWERHOUSE

1 Construction of Powerhouse complete with architectural finishes, structural, electrical, plumbing, painting etc. (Area = 30.68 sq.m.)

D CONSTRUCTION OF GATE COMPLEX 1 AND 2

1 Construction of Gate Complex 1 and 2, complete with architectural finishes, structural, electrical, plumbing, painting etc. (Area = 75.36 sq.m. each)

APPROVED BUDGET FOR THE CONTRACT	:	**Php**	**859,937,463.55**
SOURCES OF FUNDING	:	**PPA Corporate Fund**	
TOTAL PROJECT COST	:	**Php**	**971,729,333.81**
PROJECT DURATION	:	**720 Calendar Days**	

BIDS AND AWARDS COMMITTEE
Philippine Ports Authority - Head Office
RECEIVED
BY: chd
DATE: 8-4-26 TIME: 1:03 pm