

PROJECT FEATURE

PROJECT TITLE : **EXTENSION OF ROCK CAUSEWAY AND CONSTRUCTION OF RC PIER**

LOCATION : **Port of Basiao, Ivisan, Capiz**

SCOPE OF WORK :

A. EXTENSION OF ROCK CAUSEWAY

- 1 Chipping & disposal of existing R.C. Curb (27 l.m.)
- 2 Supply & placing of 3,500 psi concrete (275 cu.m.)
- 3 Supply & installation of steel reinforcement (13,616 kg.)
- 4 Supply & placing of core rocks & armour rocks (24,221 cu.m.)
- 5 Supply & placing of fill materials (1,877 cu.m.)
- 6 Construction of PCC Pavement including Agg. Base Course (1,432 sq.m.)
- 7 Supply & installation of Mooring cleats (24 sets)
- 8 Supply & installation of Portlighting system (1 lot)

B. CONSTRUCTION OF R.C. PIER

- 1 Supply, delivery, driving & cutting of PSC square pile (1,934 l.m.)
- 2 Supply & placing of 3,500 psi concrete for Superstructure (263 cu.m.)
- 3 Supply & installation of steel reinforcement for Superstructure (30,212)
- 4 Supply & installation of construction joints (18 l.m.)
- 5 Supply & installation of Rubber dock fenders (14 sets)
- 6 Supply & installation of Mooring bollards (8 sets)

APPROVED BUDGET FOR THE CONTRACT	:	Php	169,711,663.70 /
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:	Php	191,774,179.98 /
PROJECT DURATION	:	480 Calendar Days	/




