

PROJECT FEATURE

PROJECT TITLE : CONSTRUCTION OF GATE COMPLEX
 LOCATION : Port of Cagayan de Oro, Misamis Oriental

- SCOPE OF WORK :
- A. DEMOLITION AND REMOVAL WORKS
 - 1 Clearing & grabbing (1,831 sq.m.)
 - 2 Removal & relocation of existin lamp post (3 no.)
 - 3 Scraping of existing fill materials (366 cu.m.)
 - 4 Demolition & disposal of existing cyclone wire fence (21 l.m.)
 - 5 Demolition & disposal of existing CHB fence (100 l.m.)
 - 6 Removal & relocation of existing office (86 sq.m.)
 - 7 Demolition & disposal of existing concrete pavement (2,001 sq.m.)
 - B. CONSTRUCTION OF GATE COMPLEX
 - 1 Excavation & backfilling works (271 cu.m.)
 - 2 Subgrading & soil treatment (1,831 sq.m.)
 - 3 Supply & placing og gravel bedding (62 cu.m.)
 - 4 Supply & placing of 3,500 psi concrete (858 cum.)
 - 5 Supply, fabrication & installarion of reinforcing steel bar (47,260 kg.)
 - 6 Construction of 100mm CHB wall including reinforcement (139 sq.m.)
 - 7 Supply & placing of plain cement plaster (1,200 sq.m.)
 - 8 Painting for concrete and metal surfaces (6,111 sq.m.)
 - 9 Supply & application of water proofing (28 sq.m.)
 - 10 Supply & installation of granite floor tiles (22 sq.m.)
 - 11 Supply & installation of aluminum composite panel (146 sq.m.)
 - 12 Supply, fab. & installation of steel materials for roofing & catwalk structure (1 lot)
 - 13 Supply & installation of polycarbonate & pre-insulated panel roofing (992 sq.m.)
 - 14 Supply & installation of PVC doors & aluminum framed windows (1 lot)
 - 15 Supply & installation of drainage pipes & fittings (1 lot)
 - 16 Supply & installation of electro-mechanical materials and accessories (1 lot)
 - 17 Supply & installation of modular counter top & chair for booth teller (1 lot)
 - 18 Supply & placing of selected fill materials (325 cu.m.)
 - 19 Supply & placing of gravel base course (269 cu.m.)
 - 20 Construction of Portland cement concrete pavement (760 sq.m.)
 - 21 Construction of CHB Perimeter fence (72 l.m.)
 - 22 Construction of lined canal including steel grating cover (109 l.m.)

APPROVED BUDGET FOR THE CONTRACT	:	Php	33,506,366.39
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:	Php	37,862,194.02
PROJECT DURATION	:	270 Calendar Days	