## PROJECT FEATURE

PROJECT TITLE

MANSALAY PORT EXPANSION PROJECT

LOCATION

Port of Mansalay, Oriental Mindoro

SCOPE OF WORK

: A. BACK-UP AREA

a. Chip-off of existing R.C. Curb (107 l.m.)

b. Supply/place 3,500 psi concrete (72 cu.m.)

c. Supply/installation of reinforcing bars (5,772kg.)

d. Supply/installation of rocks (4,176 cu.m.)

e. Supply/installation of geotextile fabric (927 sq.m.)

f. Supply/place fill materials (4,178 cu.m.)

g. Construction of PCCP including agreggate base course (1,671 sq.m.)

h. Supply/installation of construction joint (15 l.m.)

## B R.C. PLATFORM AND WIDENING OF R.C. PIER

a. Chip-off of existing R.C. Curb (84 l.m.)

b. Remove existing bollards and fenders (9 no.)

c. Supply/drive 400mm x 400mm PSC piles (3,880 l.m.)

d. Supply/place 3,500 psi concrete for R.C.platform & pier (367 cu.m.)

e. Supply/install reinf. steel bar for R.C. platform & pier (59,421 kg.)

f. Supply/installation of construction joint (105 l.m.)

g. Supply/installation of accessories for bolard & fenders (4 set)

h. Supply/installation of V400H x1000L RDF (7 set)

i. Re-installation of old 25T,T-head mooring bollard (4 set)

## C NEW R.C. PIER

a. Supply/drive 450mm x450mm PSC piles (5,848 l.m.)

b. Supply/place 3,500 psi concrete for the new R.C. Pier (581 cu.m.)

c. Supply/install reinforcing steel bar for the new R.C. Pier (86,637 kg.)

d. Supply/installation of construction joint (48 l.m.)

e. Supply/installation of V600H x1500L RDF (22 set)

f. Supply/installation of 50T,T-head mooring bollard (11 set)

## D PORTLIGHTING SYSTEM

a. Supply/installation of wires & cables ( 1 lot)

b. Supply/installation of conduit pipes (1 lot)

c. Supply/installation of wiring divices (1 lot)

d. Relocation of existing solar lamp post and accessories (8 sets)

e. Supply/installation of floodlight & Lamp posts (1 lopt)

f. Supply/installation of protective devices (1 assy)

APPROVED BUDGET FOR THE CONTRACT

Php

137,909,533,55

SOURCES OF FUNDING

PPA Corporate Fund

TOTAL PROJECT COST

Php

:

155,837,772.91

PROJECT DURATION

480 Calendar Days

